

Data Recovery Excavations at the Grant Tenancy Site,
Centre Road and Lancaster Pike,
New Castle County, Delaware



by

Randolph K. Taylor, Timothy A. Thompson,
Kimberly A. Snyder and William M. Gardner
THUNDERBIRD ARCHEOLOGICAL ASSOCIATES, INC.
Woodstock, Virginia

Delaware Department of Transportation Archaeological Series No. 56



Delaware

Department of Transportation

John T. Davis
Director

Division of Highways

1987



U.S. Department
of Transportation

Federal Highway
Administration

DATA RECOVERY EXCAVATIONS

AT THE

**H. GRANT TENANCY SITE
DE RT 141 (CENTRE ROAD)**

AND

DE RT 48 (LANCASTER PIKE) INTERSECTION

NEW CASTLE COUNTY, DELAWARE

DelDOT PROJECT 85-106-01

ARCHEOLOGY SERIES NO. 56

FHWA FEDERAL AID PROJECT M-1153(7)

By

**Randolph K. Taylor, Timothy A. Thompson,
Kimberly A. Snyder and William M. Gardner**

**THUNDERBIRD ARCHEOLOGICAL ASSOCIATES, INC.
Woodstock, Virginia**

**Submitted To
U.S. DEPARTMENT OF TRANSPORTATION
Federal Highway Administration**

and

**DELAWARE DEPARTMENT OF STATE
Division of Historical and Cultural Affairs
Bureau of Archaeology and Historic Preservation**

Prepared For

**DELAWARE DEPARTMENT OF TRANSPORTATION
Division of Highways
Location and Environmental Studies Offices**

**John T. Davis
Director
Division of Highways**

1987

**Doc. Cont. No.
55-04/87/07/01**

ABSTRACT

In October of 1985, data recovery efforts were completed at the H. Grant Tenancy site in New Castle County, Delaware. The work was carried out by Thunderbird Archeological Associates of Woodstock, Virginia under a contract to the Delaware Department of Transportation. The site had been identified earlier in connection with previous survey and testing and it had been determined eligible for inclusion on the National Register of Historic Places.

Background research revealed a complex ownership history for the property parcel on which the site was located. Occupants of the site could not be ascertained with certainty based on the documents. Excavations at the site revealed the remains of a foundation, the remains of a well and attached subsidiary structures. Several discrete deposits were located in the foundation including cellar fill, a fireplace fall and a cellar floor midden. Based on the volume of stone remaining, it appears as if the house was originally constructed of something other than stone or the stone has been salvaged. The Mean Ceramic Date for the site as a whole was 1814.91.

The ceramics from Grant Tenancy were compared to a number of other sites in an attempt to define the socio-economic status of the occupants of the site. Several different statistical methods, including Chi Square, the Tau statistic, the Brainard-Robinson Coefficient of Agreement and Z scores, were used, with varying results. Based on the results of these investigations, it appears as if the occupants were of relatively high economic status in relation to the other sites examined, although archival and background search seems to indicate that the structure appears not to have been owner occupied. The high status indication suggested by the ceramic analysis was borne out to some degree by the results of the faunal analysis, e.g. remains which included better quality meat cuts indicative of higher status were found.

TABLE OF CONTENTS

	Page
Abstract	i
List of Figures, Tables and Plates	iii
Introduction	1
Previous Archeological Investigations	6
Research Design	6
Regional Culture History	7
Field Methodology	11
Laboratory Methodology	18
Glass Analysis	19
Ceramic Analysis	20
Results of the Investigations	21
Archival	21
Fieldwork	38
Intrasite Analysis	70
Spatial Organization and Patterning	89
Faunal Analysis	104
Soil Analysis	109
Comparisons with Other Sites	115
Summary and Conclusions	129
References Cited	135
Personnel	138
Appendices	
Appendix I - National Register of Historic Places Nomination Form	139
Appendix II - Total Artifact Counts and Inventory ...	148
Appendix III - Faunal Analysis	152
Appendix IV - Soils Analysis	195
Appendix V - Public Consumption Handout	198
Appendix VI - Glossary	201
Appendix VII - Research Design	203

LIST OF FIGURES

	Page
Figure 1 - Project Location Map	2
Figure 2 - Site Plan Map (Oversize)	12
Figure 3 - Foundation and Selected Features	13
Figure 4 - Controlled Surface Collection Artifact Totals ..	14
Figure 5 - Controlled Surface Collection Distribution of Ceramics	15
Figure 6 - Controlled Surface Collection Architectural Items	16
Figure 7 - 1849, Rea and Price Map	22
Figure 8 - 1860 Lake & Beers	23
Figure 9 - Chain of Title	24
Figure 10 - Parcel Boundaries, 1940	29
Figure 11 - Parcel Boundaries, Composite Drawing	30
Figure 12 - Heald Map, 1820	37
Figure 13 - Plowzone (Ap) Sample Units	40
Figure 14 - Soil Profile on N135 Grid Line	41
Figure 15 - Soil Profile on E390 Grid Line	42
Figure 16 - House Foundation, Chimney Footing Detail	48
Figure 17 - Construction Detail, Southwest Corner	49
Figure 18 - Profile of House Foundation Looking North	57
Figure 19 - Feature 8 (Well) Profile	62
Figure 20 - Feature 10, Plan	64
Figure 21 - Feature 10, Profile, Postmolds Plan and Profile	65
Figure 22 - Features 2 and 11, Plan and Profile	67
Figure 23 - Feature 9, Plan and Profile	68
Figure 24 - Feature 12 and Postmold 380a, Plan and Profile .	69

	Page
Figure 25 - Distribution Map, Surface Collection, Bottle Glass	91
Figure 26 - Distribution Map, Surface Collection, Refined Ceramics	92
Figure 27 - Distribution Map, Surface Collection, Coarse Ceramics	93
Figure 28 - Distribution Map, Excavation Units, Bottle Glass	94
Figure 29 - Distribution Map, Excavation Units, Percentages of Refined Ceramics	95
Figure 30 - Distribution Map, Excavation Units, Percentages of Coarse Ceramics	96
Figure 31 - South's Function 1, Kitchen Group Distribution .	98
Figure 32 - Distribution of Brick, Excavation Units	99
Figure 33 - Distribution of Window Glass, Excavation Units .	100
Figure 34 - Distribution of Nails, Excavation Units	101
Figure 35 - Soil Sample Location Map	110
Figure 36 - Results of Phosphorous and Potassium on a North/South Transect	111
Figure 37 - Results of pH Testing	113
Figure 38 - Results of Soils Testing Features	114
Figure 39 - Middle Atlantic Region Map Showing Sites Used for Comparison	117

LIST OF TABLES

Table 1 - Mean Ceramic Dates	72
Table 2 - South's Function, Provenience Groups with Carolina Pattern	78
Table 3 - Percentages of Decorative Types on Refined White Earthenware, all sites	121
Table 4 - Z Scores by Decorative Type for All Sites	126
Table 5 - Sum of Z Scores and Socio-economic Status	128

LIST OF PLATES

	Page
Plate 1 - Aerial View	3
Plate 2 - General View of Site Looking South	4
Plate 3 - Profile Showing Midden	43
Plate 4 - View of Foundation Looking Southwest	47
Plate 5 - Chimney Support Detail Looking East	50
Plate 6 - Southwest Corner of House	52
Plate 7 - Stoneware Bottle	54
Plate 8 - Redware Pie Plate	55
Plate 9 - Well Detail	60
Plate 10 - Well Profile After Excavation Looking South	61
Plate 11 - Barrel from Well	63
Plate 12 - Gunflints and Prehistoric Bifaces	79
Plate 13 - Buttons	80
Plate 14 - Tobacco Pipes	81
Plate 15 - Pitcher	83
Plate 16 - Miscellaneous Metal Artifacts	84
Plate 17 - Coins and Religious Medal	85
Plate 18 - Econscale Type 1: Porcelain	105
Plate 19 - Econscale Type 4: Transfer Printed Refined White Earthenwares	106
Plate 20 - Econscale Type 5: Hand Painted Refined White Earthenwares	107
Plate 21 - Econscale Type 6: Minimally Decorated Refined White Earthenwares	108

INTRODUCTION

This report presents the results of Phase III data recovery excavations conducted at the H. Grant Tenancy site (7NC-B-6) in New Castle County, Delaware by Thunderbird Archeological Associates, Inc. (TAA). The excavations were completed at the request of the Delaware Department of Transportation (DelDOT), and were designed to mitigate adverse effects resulting from proposed construction activity connected with improvements to the intersection of Route 48 (Lancaster Pike) and Route 141 (Centre Road). The Route 141 improvement plan in general consists of the construction of a four lane corridor along the present right-of-way. Specifically in the project area, the construction consists of the building of a spur from Route 141 down Lancaster Pike to Little Mill Creek. This work was carried out in compliance with the National Historic Preservation Act of 1966 (Section 106) as well as with the regulations of the Federal Highway Administration, the Delaware Department of Transportation, the State Historic Preservation Office and appropriate State laws.

The H. Grant Tenancy site is situated in the northwestern corner of a field bounded by the intersection of Route 141 and Route 48 (Figure 1 and Plates 1 & 2). It is located on a relatively flat bench of land bounded to the north by a spring and associated drainage ravine, while on the west, the land drops off gently towards Little Mill Creek. The field had been under cultivation until just prior to the onset of the initial archeological investigations. Preliminary findings suggested that the site was a domestic occupation dating to the early to mid 19th century and the site was tentatively identified as a tenancy (Barse 1985).

Background and archival investigations were conducted at various times from July, 1985 to January, 1986. Field investigations were conducted during August through September of 1985. Dr. William M. Gardner served as principal investigator on the project, Timothy A. Thompson conducted the archival investigations and Randolph K. Taylor served as field director.

TENANCY SITE

KEY MAP



NEW CASTLE COUNTY,
DELAWARE




PLATE 1

AERIAL VIEW





PLATE 2
GENERAL VIEW OF SITE LOOKING SOUTH



Appreciation for their support, administration, services and research is extended to all the involved individuals:

LOCAL INFORMANTS

Mrs. Aletta Laird Downes,
Landowner
Peter Hayward
Alex Jarrell
Fran DiMichele
Charles A. Barfels

THE UNIVERSITY OF DELAWARE

Dr. Jay Custer, Assistant
Professor
Wade Catts, Archeologist
Ellis Coleman, Archeologist
Keith Doms, Archeologist
College of Agriculture
Soils Laboratory - Soils
Analysis

THE DELAWARE STATE ARCHIVES

Sherrie Ayers
Doris Carignon

THE HAGLEY MUSEUM AND LIBRARY

Carol Hallman
Marjorie McNinch
John Rum
Jon Williams

THE BUREAU OF ARCHAEOLOGY AND HISTORIC PRESERVATION

Daniel R. Griffith, Bureau Chief
Faye L. Stocum, Archeologist
Alice H. Guerrant, Archeologist

THE FEDERAL HIGHWAY ADMINISTRATION

Charles J. Nemmers, District
Administrator
A. George Ostensen, Field Operations
Engineer
Michael J. Otto, Area Engineer

DIVISION OF HIGHWAYS

Raymond M. Harbeson, Jr., Deputy
Director
Joseph T. Wutka, Jr., Location Studies
and Environmental Engineer
Kevin Cunningham, DelDOT Archeologist
Bill Davis, Backhoe Operator
Rod Hill, Right of Way
William Brockenbrough, Project Engineer
Carolann Fendt, Project Engineer
J. A. Smith, Maintenance Supervisor
Carol L. Kates, Secretary and Word
Processing
Joanna Likens, Project Support

DIVISION OF GRAPHICS AND PRINTING

Ray Moore, Shop Supervisor
John Bordley, Pressman
Bob Farley, Pressman
Jeff Faulkner, Pressman
William Yerkes, Pressman
Dorothy Hutchins, Machine Person
Joan Pillsbury, Bindary Clerk
Grace Steele, Graphics Specialist

PREVIOUS ARCHEOLOGICAL INVESTIGATIONS

The H. Grant Tenancy site was discovered during Phase I and II archeological investigations conducted during the fall of 1983. Archival research had indicated the presence of a structure, apparently located in the approximate location of the site, on a map of the vicinity of Philadelphia published by Pomeroy and Beers in 1860. This map covered the Wilmington and Brandywine Railroad routes for New Castle County, Delaware and Delaware and Chester Counties, Pennsylvania.

A large quantity of artifacts were noted in the plowzone during the Phase I and II investigations, and testing isolated several subsurface features which suggested the presence of a structure. The site's placement in the early to mid 19th century was based primarily on the high percentage of pearlware in the assemblage (Barse 1985).

As a result of the intensive survey excavations, the H. Grant Tenancy site was determined to be eligible for nomination to the National Register of Historic Places under criterion D, 36 CFR, Part 800 (Appendix I). It was considered to be significant in that intact subsurface archeological features were present which were felt to contain potential information concerning changing economic patterns observed in the early part of the 19th century. In addition, based on the hypothesis that the site represented a tenant house, it was felt that the assemblage could provide valuable information concerning the nature of small tenant sites, as these are poorly known, both archeologically and historically (Barse 1985). The tenant house hypothesis was based on the results of the archival research which showed the name H. Grant associated with several properties in the area.

RESEARCH DESIGN

The research design was drawn from the original hypothesis that 7NC-B-6 was a tenant farm.

In response to changing economic conditions in the beginning of the 19th century, land tenure became consolidated into the hands of fewer individuals near urban areas (Bidwell and Falconer 1941:242). Landowners often had business interests connected with industrialization or commerce in urban centers and frequently lived in the city. To maintain agricultural production, a system of tenancy was employed. Tenants were probably drawn from groups of lower economic status in both urban and rural population, but very little historic research has been devoted to these individuals and little is known of their economic or cultural background. Likewise few remnants of their material culture, including their housing, have survived. Based on the findings of the Phase I and Phase II studies (Barse 1985), it was originally felt that the H. Grant Tenancy site represented the remains of such tenancy and that an examination of the material culture could provide valuable information about such sites. Because the site was felt to contain structural remains,

it was felt that it might be possible to learn more about the spatial arrangement and relationships of the dwelling and other service buildings such as storage sheds, animal pens, privies, etc. to show how these compare to the large complexes of the owners, many of which are still extant. It was also felt that an examination of the discarded material possessions from the site would allow a more precise characterization of the social and economic status of the occupants.

The methodology (which will be discussed in more detail in the Methodology section) was designed to gather data to address these and other questions. The archival research was designed to attempt to identify the occupants of the site and to develop a more general set of data concerning the social and economic conditions under which the occupants, hypothesized as tenant farmers, lived. It was expected that excavations would provide information concerning the characteristics of refuse disposal patterns for 19th century sites such as this. Machine stripping of the area was designed to uncover a maximum number of undisturbed features and deposits which would increase the data base on intrasite patterning and gained from the controlled surface collection. The controlled surface collection preceded the machine stripping and was used as a guide for this activity as well as for providing an independent data set regarding internal structure. An examination of patterning in the distribution of economically significant attributes in the artifacts was made and then compared to data from other sites to see if there are broad patterns which reflect the economic conditions of the occupants.

REGIONAL CULTURE HISTORY

The following is a brief synopsis of the regional cultural prehistory and history.

Delaware's regional prehistory has been subdivided by Custer (1980, 1983) into four major time periods. They are the Paleo Indian Period (ca. 12,000 B.C. - 6500 B.C.), the Archaic Period (6500 B.C. - 3000 B.C.), the Woodland I Period (3000 B.C. - A.D. 1000) and the Woodland II Period (A.D. 1000-1650). The Contact Period, dating from A.D. 1650 to 1750, follows the four major time periods. After about 1750, the aboriginal population in Delaware had ceased to exist as a relatively unacculturated way of life.

Paleo Indian Period

This time period dates to the terminal Late Pleistocene and early Holocene climatic eras, a time that marks the final retreat of the glaciers and the gradual development of modern climatic regimes. The Paleo Indian climate consisted of alternating wet and dry conditions characteristic of the Late Pleistocene and early Holocene and which supported the various extinct species of large game mammals such as mastodon, mammoth and moose. These animals were adapted to the various vegetational communities that

existed at the time, a mixed mosaic of deciduous and boreal forests, as well as grassland environments.

The tool kit of the Paleo Indian was oriented primarily toward the hunting of the various large game animals. Diagnostics are fluted and notched projectile points (the latter characterizing the Early Archaic) as well as several kinds of side and end scrapers. A preference for high quality cryptocrystalline lithic raw material is indicated. This reliance on high quality stone had a great effect on the Paleo Indian settlement pattern; base camps were located in the vicinity of quarries, with radiating hunting camps and special procurement sites located away from the base camp/quarry locale.

Archaic Period

The changes in the climate mentioned previously led to the establishment of modern conditions by approximately 6500 B.C. There was a corresponding change in the adaptive pattern of the aboriginal groups inhabiting the Middle Atlantic. The extinction of the large game species by this time was caused, at least in part, by the reduction in the grassland environments and the development of closed mesic forests. The larger species were replaced by more solitary browsing species such as deer, elk, and moose. Adaptive patterns were geared to the hunting of the more solitary species and the collecting of plant foods. This change in subsistence patterns is marked by the development of various grinding tools, a new technology and variety of new projectile point forms made from a wide variety of lithic materials. Settlement patterns were characterized by small seasonal base camps located to take advantage of seasonally available resources with smaller groups fissioning off in pursuit of other seasonally and locally available kinds of plant and animal foods. In the New Castle County area, sites such as the Clyde Farm and Delaware Park are representative of base camps of this time period and the following Woodland I period.

Woodland I

By 3000 B.C., increasing sea level had caused climatic/environmental changes that led to adaptive changes in the prehistoric way of life. This rise resulted in the development of brackish water estuaries. The mesic forest was replaced by a xeric type characterized by oak and hickory species, with an increase in grasslands. Temperatures were warmer and drier than before. The development of the estuaries created a rich environmental zone that could support large base camps on a seasonal schedule, which was, in part, probably semi-sedentary for a large part of the year. An increase in population is noted at this time.

The Woodland I tool kit is characterized by the broad bladed Savannah River point forms and their derivatives, as well as solid container technology. The solid container technology is first characterized by soapstone bowls in the first phases of the

Woodland I period and later by ceramic containers. Ground stone tools continue to be part of the tool kit.

Woodland II

The main characteristic marking the emergence of the Woodland II period is the development of a stable agricultural adaptation in many parts of the Middle Atlantic. Research in Delaware indicates that such a shift is not as marked as in other parts of the Middle Atlantic and that the Woodland I adaptive systems continue to function, a system characterized by intensive plant cultivation and hunting. Various ceramic types with complex decorations are characteristic of the Woodland II period in Delaware. These wares evolved out of the earlier Woodland I ceramics. Small triangular projectile points are ubiquitous and indicate the use of the bow and arrow.

Contact Period

The Contact period is the time when the Indians were in active interaction with the newly arrived European traders and settlers. The information available is the ethnohistoric sources which show rapid disruption and deculturation brought about by the combination of several factors including, importantly, high mortality rates from European introduced diseases, dependence on European manufactured goods and loss of land. The Indians resident in the northern Delaware area at the time of contact fall into the rather loosely defined Delaware. The Delaware at the early Historic period consisted of widely scattered, rather loosely organized and relatively independent local groups. Only much later did the shattered remnants form a cohesive Pan-Delaware polity. All belonged to a larger linguistic grouping known as the Coastal Algonquin, of which Delaware is a subdivision. Within the category Delaware, are further divisions of which the Southern Unami lived in southern New Jersey and along the southern shore of the Delaware River and Delaware Bay (Goddard 1978). The Minguannan are the mapped groups closest to the project area.

Regional History

Delaware was settled by the Dutch in 1630, with the establishment near Lewes of a whaling station which was soon destroyed by the Indians. The Swedes settled in the vicinity of Wilmington with the establishment of Fort Christina in 1638. This was captured by the Dutch in 1651. Settlement was characterized by scattered farmsteads along the major drainages, the Delaware River, White Clay Creek and Christina Creek (Weslager 1961).

Control of Delaware once again changed hands in 1664 with the ascendancy of the English. In 1682, proprietary rights were granted to William Penn. The axis of interaction, both politically and economically, shifted to Philadelphia and for the remainder of the historic period, at least in the larger scheme

of things, northern Delaware falls into the greater Philadelphia orbit. At the time of Penn's assumption, however, northern Delaware was quite rural, with dispersed farmsteads being distributed along the Delaware and the tributary streams (Catts and Coleman 1986). The focus of settlement was two-fold -- streams for navigation and good agricultural soils. Streams were essential at this time for communication and movement of imports and exports, as overland road systems were virtually non-existent. As a result of this settlement system, waterfront locations became the locus of early town growth. The early population expansion away from the waterfront settings was out from these rivers and streams but still within a short distance of either a mill or shipping wharf.

The second phase of expansion began in the 18th century and reflects several factors including internal population growth, heavy influx of new populations from Europe, crowding along the earlier settled locations, the growth of small population-market centers in these settings, and increases in property costs in the older locations. The interior movement was first to the best available farmlands, but as the interior road system began to grow and expand, settlement became even more dispersed. Land purchases and allocations earlier did not follow the southern system in size and small holdings were the rule. Subsequently in loci closer to the earlier settled areas and the growing market towns, larger land holdings grew as individuals acquired wealth and used this, in part, to acquire land.

Town growth and urbanization underwent several pulses (Catts and Coleman 1986). The first growth related to relationships with Philadelphia and the market and shipping center. There was then a period of stagnation which carried into the first third of the 18th century. Aggregations of populations did continue to grow around mills, transportation nodes, shipping points and bridges and ferries. Following the model presented by the geographer Lemon, Catts and Coleman (1986) noted another period of urbanization between 1730 and 1765. Wilmington saw considerable growth at this time as did a number of other towns. With this, and perhaps as a result or cause, the road system grew rapidly. In the early 19th century, improvements to the transportation system saw the growth of canal and then, in 1839, the start of rail transportation.

Settlement in the 19th century was characterized by the growth of even larger plantations and farming operations and associated small tenant farms. The H. Grant Tenancy site, which is the focus of this report, was originally felt to be one of these small, tenant farms. All of this agrarian economy was nested after a fashion with the large urban centers at the final consumption end and the tenant farms, presumably, at the basic production end. Some of the changes in the role of the farm can be tracked through the 18th and 19th century with the shift from subsistence farming with a move toward production of goods for consumption in the growing regional markets (Fletcher 1950). These changes also tie in with the growing industrial and urban


centers in the Philadelphia-Wilmington-Baltimore corridor underway in the early 190th century. As Catts and Coleman (1986) note, the later 19th century was a period of ever increasing industrialization, population growth and urbanization. Despite this, northern Delaware continued to be primarily agricultural during the 19th century. Interestingly, from the perspective of this report, tenancy continued to be a viable factor in agricultural production into the 20th century.

FIELD METHODOLOGY

Field research at the Grant Tenancy was separated into three steps, each with specific research goals. These include, in order of completion: 1. controlled surface collection; 2. screened plowzone sample; and 3. location, mapping and excavation of the house foundation and associated features. The first step was to obtain a sample of artifacts across the site from a controlled surface collection. This was done to help isolate artifact concentrations that would provide clues to locating activity areas and subsurface features. Since surface visibility was obscured by ground vegetation, the first step required that the site be plowed in order to provide maximum surface visibility and optimal collecting conditions. Once the plowing was completed, a grid was laid out with wooden stakes placed at twenty foot intervals. The grid origin was established near the entrance to the field and was arbitrarily designated as North 100, West 500, to insure that all coordinates from the site would possess a northwest quadrant designation (Figure 2).

Collecting was facilitated by fabricating a movable grid using rope. The grid was stretched from each of the wooden stakes dividing each 20 foot square section into four ten by ten units. Ten by ten foot units were chosen primarily for convenience. Each ten by ten unit was designated with the coordinate of its southwest corner and all artifacts from each unit were collected and bagged separately. Artifact counts were tabulated in the field after each section was collected. Figure 3 shows the foundation and selected features. The results were then plotted on three separate distribution maps, one indicating architectural debris (brick, nails, flat glass), one indicating artifact totals, and one showing ceramics only (Figures 4-6). The maps were useful in making decisions about the placement of five by five foot excavation units utilized in the next step of the field investigations as they delineated "hot spots" or artifact concentrations.

Step 2 was designed to retrieve a sample of artifacts from the plowzone in areas where surface concentrations were high. A total of thirty-seven five by five foot units were excavated by flat shovel and trowel (see Figures 2 and 3). All plowzone soil from the 37 hand excavated 5'x5's was screened through 1/4 inch mesh and all sub-plowzone features revealed in these units were mapped and numbered for subsequent excavation. The screened plowzone units provided additional artifact distribution data as well as giving a more complete sample for subsequent functional






FIGURE 3
H. Grant Tenancy Site (7NC-B-6)
Grid Showing Location of House
and Features 8 - 10




FIGURE 4
H. Grant Tenancy Site (7NC-B-6)
Controlled Surface Collection
Artifact Totals





FIGURE 5
H. Grant Tenancy Site (7NC-B-6)
Controlled Surface Collection
Distribution of Ceramics




FIGURE 6
H. Grant Tenancy Site (7NC-B-6)
Controlled Surface Collection
Distribution of Architectural Debris

and temporal analysis (see Laboratory Analysis section for additional details). The excavated five by five units also provided stratigraphic control across the site.

Step 3 involved the location, mapping and excavation of the house foundation and associated features. This step was facilitated by the use of heavy equipment provided by DelDOT to remove the plowzone over areas of the site not already exposed by the hand excavated five by five units. The house foundation was first discovered during the excavation of N170E85 during the plowzone sampling, excavations which partially exposed the south and east foundation walls. The machine was used to expose the remaining walls. The plowzone removal was accomplished using a front end loader to excavate the majority of the plowzone layer while the remaining few inches were removed with a backhoe fitted with a smooth-edge bucket. This provided a relatively clean surface and eliminated having to drive over freshly exposed subsoil which would have obliterated any features present. Five foot wide balk strips, following the 20 foot grid stakes previously laid out for the surface collection, were left in place to simplify mapping and eliminate the need to reset the stakes. Once the plowzone was removed by the machine, features were exposed by carefully flat shoveling the surface of the subsoil. Many of the features were visible only as faint discolorations in the soil matrix, requiring the frequent use of a water sprayer to heighten subtle color variations.

The house foundation was treated as a large feature consisting of several components, each of which were excavated separately. These components include, starting with the oldest: the cellar wall, the builder's trench, the cellar floor consisting of a thin layer of midden deposit, the "exterior midden" associated with a porch or an addition to the house, and the cellar fill, deposited when the house was abandoned and destroyed. A more complete description of each of these provenience groupings is provided in the Results of Excavations section of this report. They are mentioned here because each represents a separate episode and the excavation of the house required careful separation of these components.

The cellar wall, built from stone, was virtually 100% intact below the plowzone. It was left intact during excavations except for the central portion of the south wall which was removed during the excavation of the builder's trench. The cellar fill and the cellar floor were excavated and screened completely.

A stone lined well (Feature 8) was uncovered during the plowzone removal. Time and safety restrictions required that the well be excavated in steps using a backhoe provided by DelDOT. Excavation of the well contents proceeded by hand, leaving the walls in place until the depth of the excavation was unsafe, a little more than waist high. The base of the excavation was then covered to protect the well contents from contamination and damage. The surrounding soil was then removed with the backhoe until it was safe once again to proceed with hand excavation

inside the well. This system was repeated until the well was completely excavated.

The remaining features at the site, predominantly postmolds and rectangular pits, were excavated using standard excavation procedures. Each was cross sectioned and excavated in halves in order to provide a profile view. Soil samples and flotation samples were taken and the remaining feature fill was screened through 1/4 inch mesh.

LABORATORY METHODOLOGY

A number of different types of artifacts were collected from the archeological investigations at the H. Grant Tenancy site. Because of their varying information potential with regard to the research design and the use of computer coding, different artifact types were handled in slightly different ways. Because of changes in technology and decorative styles, the ceramics and glass were considered to be the most sensitive temporal indicators. In addition, based on previous research (Miller 1980; Beidleman et al 1983; Thompson 1985), the ceramics have been demonstrated to provide a means of evaluating economic status, thus contributing directly to the research design. Therefore, a more detailed attribute analysis of these two classes which would be amenable to computer analysis was used to record these artifact types. The attributes coded for the ceramics and glass are present in more detail below. Metal and the remaining artifact category, Miscellaneous, were simply described according to material, method of manufacture, and function, insofar as these items could be determined for a particular object. Only samples of brick and mortar were saved, the rest was counted, either in the field or in the lab and discarded. Brick which was sufficiently whole to warrant measurement, width, length and thickness dimensions were taken. Conservation measures were used on those artifacts which were felt to warrant this. These measures consisted of electrolysis for ferrous metal, treatment with Polyethylene Glycol 10-00 (Carbowax) for wood and castor oil for leather. Any artifacts which did not merit conservation, either because they were too deteriorated or of limited information potential, were described as well as possible and discarded. Examples of the kinds of artifacts that were discarded are coal, cinders and small brick fragments.

The following artifact analysis procedures were developed in connection with a data recovery project in New Jersey and greater detail on artifact coding is presented in that report (Thompson 1985), only a summary is presented here. Any deviation from that coding system is noted. A number of attributes of potential interest were identified (separately) for the glass and ceramics. Numerical codes were assigned for each of a range of possible variable states. A standard IBM 80 column coding form was subdivided and the numerical codes for each variable state were recorded directly from the artifacts. Artifacts from each Field Specimen Number were sorted and the numerical values were

recorded on the form. Items or groups of items with identical attributes were combined on the form with the set of attributes being recorded only once for the entire set. The coding forms were then entered into an Apple MacIntosh computer according to specific provenience groupings (detailed under the Results of the Excavations section) and all analyses were performed by these provenience groupings. The specific variables used in the coding are described below, separately for the glass and the ceramics.

Glass Analysis

Twenty three possible variables were identified for the glass. Variables 1-8 describe the provenience for each artifact and identical provenience coding was used for the ceramics. Variable 1 is the site number. Variable 2 is the excavation unit number, with the North/South designation indicated by the first four digits and the East/West designation indicated by the last four. Artifacts from the controlled surface collection were coded according to the collection square and a specific numerical code under another variable indicated that the items were from the controlled surface collection. Items from a general surface collection were coded under Variable 2 by eight "9's". Variable 3 was feature number, if this variable was not applicable to a certain field specimen number, a zero was coded here. Variable 4 consisted of an Area designation. This variable was used, along with natural horizon to differentiate the various provenience groupings. Items from the controlled surface collection were differentiated under this variable. The fifth variable refers to Soil Horizon. This variable included both cultural and natural horizons and was used to differentiate the various proveniences other than features. Variable 6 was used to code the arbitrary level number directly. Variable 7 consists of Provenience Other. This variable consisted of two digits, the first of which refers to whether or not the matrix from which the artifacts were extracted was native to the site or foreign (originating from a fill horizon derived from another location). All of the contexts from Grant Tenancy were native. The second digit refers to whether or not the artifacts came from a screened or an unscreened context. The final provenience variable was Variable 8 which consisted of directly coding the Field Specimen Number onto the form. Variable 9 refers to the material of the artifacts being coded, in this case, glass. All of the aforementioned variables are identical for glass and ceramics and will not be discussed under the variables below.

For glass, the next variable is Variable 10, "Type-Variety". In general, this variable refers to manufacturing techniques such as flat, blown, pressed and cut. Variable 11 refers to "Function/Shape" and because of the nature of the artifacts, varying degrees of specificity were coded. Major groupings included food consumption, food preparation, household, and food storage as well as more general terms such as unidentified container. Variable 12 records the functional group for each artifact, following South's (1977) breakdown. Variables 13-16 record physical aspects of the artifacts, i.e. "Lip Treatment",

"Body Treatment", "Base Treatment" and "Closure". Variable 17 records surface decoration that has not been coded elsewhere and Variable 18 records the color of the glass, reflecting to some degree the chemical composition. In Variables 19 and 20, the beginning and ending dates for the artifact are coded. With respect to glass, this most often referred to various manufacturing methods such as machine made or mold blown. The dates were derived from a number of sources. Variable 21 records the sherd count for all sherds within a specific Field Specimen Number that possess exactly the same attributes. Variable 23 refers to Vessel Count. This variable could rarely be used, except in the case of almost whole or whole vessels as time constraints during the analysis precluded intensive searches for mends. The final variable for glass consisted of Geographic Origin. This data was most often obtained from embossed labels on the artifact and, in most cases, such labels refer to the contents of the artifact, not the container itself.

Ceramic Analysis

For the ceramics, the coding for the provenience variables, Variables 1-9 are identical to those used for the glass and will not be reiterated here. Variable 9 refers to material which is, obviously, ceramics.

Variable 10 refers to the ware type. Commonly recognized ware types such as pearlware, creamware, ironstone, etc. were used and these were determined on the basis of paste color, paste hardness and texture. Variable 11 refers to the outer covering of the ceramic fabric. The distinction between clear and clear lead was arbitrary and was assigned on the basis of ware type since this could not be determined from the artifact itself. It was assumed that whiteware and equally modern wares possessed non-leaded clear glazes. Variable 10 is used to describe Method of Decoration. Three digits are used for this variable with the first digit referring to plastic decoration such as embossing, engine turning, et., with the second two digits referring to surface designs such as transfer printing and hand painting. color of Decoration was coded in Variable 13. This code refers only to the color of decoration and not the glaze in the case of colored glazes. If more than one color was present, the most dominant color was recorded or if no clear dominant color could be determined, it was coded as 99 for polychrome. Variable 14, Variety, was used for specific patterns or motifs, or to provide greater specifics about the artifact. For example, the "Rebekah at the Well" motif or the "Lion and the Unicorn" mark. Variable 15 was used to code the Function/Shape of the vessel insofar as this could be determined from the sherd. The general categories are similar to those used for glass, however, they are more specifically related to categories defined by Beidleman (et al 1983) in their study of collections from Alexandria, Virginia. This variable could rarely be coded except in the most general sense. Variable 16 refers to South's Function Groups (South 1977). Variable 17 refers to Type Number and follows South's table (South 1977:210-212). In addition to those types defined

by South in his table, a more general category called "General Pearlware" was added. This was used for artifacts on which the decorative element was too incomplete to allow specific assignment into one of South's types or which the decorative element was not included by South, such as sponged. The entire date range for all of South's pearlware types was used to date this type, i.e. 1780-1890, on the premise that it could date anywhere within this range. Variables 18 and 19 were used to code directly for the dates for South's types unless more specific dating information such as a maker's mark was present. Variable 20 was used to code for the presence or absence of the ceramic manufacturer's mark, the specifics of which were noted in the margin. The sherd counts (Variable 21) and the vessel counts (Variable 22) were coded as they were for glass.

In the Grant Tenancy ceramic analysis, Variable 23 consisted of Econscale Type. The Econscale types are numbers which are arbitrarily assigned to specific ware types and decorative types based on their cost to the consumer when purchased, following Miller (1980). These were coded directly for the Grant Tenancy project because a major portion of the research design was to analyze the various economic aspects of the site. The analytical process is described in more detail under the Results of the Excavations section.

RESULTS OF THE INVESTIGATIONS

Archival

The following presents the results of the archival research undertaken during the investigations. The field in which the Grant Tenancy site is located is part of a large holding in which the main structure was in the vicinity of a house presently occupied by Mrs. A. L. Downs. A number of different names are present for this structure on historic maps. On the Rea and Price Map of 1849 (Figure 7), the structure is labeled "W. Tatnall". The deed research for the previous investigations was terminated with the sale of the property by Henry Grant to John Peoples in 1866 (Deed Book H8, page 142, New Castle County records). This is undoubtedly the "H. Grant" whose name appears on the property on the Lake and Beers "Map of the Vicinity of Philadelphia and Wilmington", published in 1860. (Figure 8) This is the only map which shows a structure in the immediate vicinity of the Grant Tenancy site. "H. Grant" is also shown next to two houses on the same map that are at or near the locations of the two large houses that are still standing on the property. The relatively limited appearance of the structure on maps, along with its association (by the name "H. Grant") with two large structures on a sizeable plantation suggested the hypothesis that it was a dependency, probably a tenancy.

Subsequent property research, however, revealed a rather complicated pattern of shifting property lines across the site location, and suggested some additional hypotheses about site function. Figure 9 presents a chain of title for the property.

FIGURE 7

Rea and Price Map of 1849






Figure 9: Property Ownership, Grant Tenancy Site




Figure 9, continued

Plantation "No. 1", Grant to Peoples, HB:142

Edward Tatnell, Brandywine Hundred transferred 187 ac, 2 roods, 32 perches to Henry Grant, Philadelphia in 1852 (L6:204). Tatnell acquired this tract through five deeds: The first of these may contain the excavated site.




Figure 9, continued

Second Plantation, "Temple Tract", Grant to Peoples, H6:142

Samuel Grant, Philadelphia, transferred 24 acres, 70 perches to Henry Grant, Wilmington, in 1864 (Y7:251). If Plantation "No. 1" does not contain the excavated site, it may be on this property.





Figure 9, continued

Second Plantation, "Temple Tract", Grubb to Armstrong, C5:137

Joseph Grubb transferred a 70 perch lot which separated the southern boundary of Armstrong's 24 acre tract from the Wilmington and Lancaster Turnpike, because of the change in alignment of that road. This 70 perch lot had originally been part of a 2 acre, 28 perch lot acquired by Grubb to bring his line east to Centre Road.



After 1866, the site location appears to remain with the tract identified as the one transferred from Grant to Peoples (H8:142). That plantation, as well as another immediately to the northwest, passed to John H. Peoples in 1911. John Peoples had died in 1892 and the property had been held in trust for 10 years under the terms of his will. John H. Peoples, presumably his son, purchased the land from the trustees (G23:404). In 1914, he sold it to William Winder Laird (T24:406). The subsequent history of the property involves the transfer of the property among a number of his heirs and a holding company until it was acquired by the present owner, Aletta Laird Downs in 1941 (A43:570; Figure 10).

The Grant-to-Peoples deed (H8:142) mentions an earlier transfer from Tatnall to Grant and, from this point backwards in time, the picture is complicated by the fact that the site location sits at the corner of several different pieces of property. The margin of error in the metes and bounds given in fractions of a degree and fractions of perches, rather than minutes and seconds and fractions of feet, is such that at any particular time the site location might be on any one of three or four different tracts. An attempt will be made to provide an intelligible summary of the possibilities, without going into enormous detail. From the Grant-to-Peoples transfer forward in time, two plantations along the Lancaster Pike (in some cases, other property elsewhere as well) are mentioned. For ease of reference, these will be referred to as "No. 1" and the "Temple Tract". These are indicated on Figure 11, and before proceeding further it will be desirable to discuss that diagram.

The diagram was created by plotting separately the metes and bounds of several of the properties encountered in the deed search, and then sliding them around until the best fit was achieved. The various over-and-under-laps of property lines suggest the variations in nineteenth century survey accuracy as well as changes in magnetic declination, which was the standard alignment reference in the nineteenth century. Seven separate tracts are shown in Figure 11, each with a separate history which may or may not include the archeological site excavated as the "Grant Tenancy". A 165 foot (10 perch) circle of error around the position of the archeological site was plotted. The position of the site was plotted with reference to the intersection of the Centre Road and the Lancaster Pike as indicated by the metes and bounds of the 1940 deed to Aletta Laird Downs, which is also shown on Figure 11. The excavated features were surveyed to this position in the field. The positions of the nineteenth century properties are estimated against each other and the former twentieth century plot, as described above. The various property boundaries are shown on Figure 11, and it is impossible to obtain a perfect alignment of the corners in the neighborhood of the site. The circle of potential location error is probably considerably greater than shown, but even with an optimistic assumption of precision about the location of the site with relation to the various properties, it may have been located on any one of six different tracts. An additional complicating factor is the fact that two different roads are given as bounds

Deed A43:570 -

N42°52'E
66'





FIGURE 11

Property Boundaries, Composite



□ corners of A43:570, 1940, Wilmington Trust to Aletta Lawd Downs contemporary property lines, for reference

○ corners of L6:204, 1852, Tatnall to Grant

Grant Tenancy, L6:204, 7/1/1852, Edward Tutnall to Henry Grant, 187 ac. 2 rods 32 perches, this tract assembled by 5 other deeds to Tatnall. This is identical to Plantations No. 1 in R35:404 and Plantation No. 2 is shown here at the southeast corner of the plat. The larger overlay is plotted from A43:570- the eastern boundary of this tract is the center line of Center Road and its southeast corner is the intersection of the centerlines of Center Road and the Lancaster Pike.

for various tracts, and the change in location for one of these, the Lancaster Turnpike (and its predecessor, the "Hockessin Road") can be documented from the deeds themselves, and it is possible that the Center Road also changed position during the critical period of the deed research. This is another reason why the boundary fits along the roads do not always appear to align.

The other documentary sources investigated, including agricultural census, tax records, and others, failed to provide a positive association of a property, or owner identified in the deed research, with a structure that might have been located in the position of the excavated site, so we are left with the 1860 map (Lake and Beers) as the only evidence for an identified structure in the vicinity of the site. Since that indicated an association with "H. Grant", our research emphasized the properties traceable backwards and forwards to him. The most recent property shown on Figure 11 is the tract transferred from Wilmington Trust to Aletta Laird Downs in 1940. A modern survey had been completed for the boundaries of this property, so the boundaries are quite accurate with relationship to each other. Their relationship to the less precisely surveyed metes and bounds of the nineteenth century property is not necessarily reliable, except at a gross level. Since the site is located at or near the boundary between the two tracts transferred forward from Henry Grant (No. 1 and the Temple Tract, mentioned above) the discussion will focus on those.

Henry Grant had received "No. 1" Plantation from Edward Tatnall on the first of July in 1852 (L6:204). The deed indicated that Tatnall was a resident of Brandywine Hundred, and Grant resided in Philadelphia. Tatnall had assembled that plantation from five separate pieces of property between 1830 and 1851. The first tract mentioned is 138 acres and may include the excavated site. John Gordon acquired this plantation by assembling three undivided portions of the dwelling plantation of David Hendrickson, whose will (Will book R, page 20:1814) describes him as a farmer of Christiana Hundred. Gordon was a resident of Wilmington, and various tax assessments indicate that he owned property throughout New Castle County, presumably for purposes of rental and speculation. The land was designated by Hendrickson for his three nephews, Isaac, John, and Joseph, but no evidence was located that reveals whether or not any of them ever lived on it. No evidence could be found in the property or probate records concerning how or when David Hendrickson acquired this tract. The tract was sold by Gordon to Edward Tatnall in May of 1830 (K4:490), and was described in the deed as a "Messuage or tennement" which means that the property contained a dwelling. Since this deed also describes Tatnall's residence as Brandywine Hundred, it is unlikely that he lived on the property during his period of ownership.

If the site were not located on the tract described above, it may have been on the tract labelled "Temple Tract" on Figure 11. Henry Grant had acquired this property from Samuel Grant in September of 1864 (Y7:251). The deed describes Samuel Grant's

residence is Philadelphia, but Henry Grant appears to have moved to Wilmington by this time. The tract is described as containing 24 acres, 70 perches, and Samuel Grant had acquired it at a Sheriff's Sale in December of 1852 (L6:207). William L. Temple had defaulted on a debt to Samuel Royer, and Royer had obtained a judgement against this property, which is described as a "message", implying that it contained a dwelling. Various records in the Superior Court Books (originals in the Delaware Hall of Records) indicate that Temple himself had brought actions against others after Royer's action was brought in 1848, suggesting that Temple may have been in financial straits. Royer's suit requested a judgment for the "use of Smiley King", a fact mentioned in the Sheriff's deed, but the identity and significance of this individual could not be determined.

Temple had acquired the 24 acre, 70 perch tract only a year before Royer's suit, from Jacob P. Herdman, "Merchant of Wilmington" (V5:156; May 1, 1847). Temple is described in this deed as a mason of Mill Creek Hundred, so it is unlikely that he ever resided on the property. Two months prior to this sale, Herdman had acquired the property from William Armstrong, Jr., of Christiana Hundred for the same price he received from Temple: \$1100 (V5:184; March 27, 1847). Armstrong had received this land from his father's will of 1840 (Will Book M, page 51), and that document separately disposes of the plantation "whereon I now reside", indicating that he did not live on the Temple Tract. In that document the Temple Tract is described as "that lot on the north side of Wilmington & Lancaster Turnpike" that contained 22 acres, plus or minus. It could not be determined where William Armstrong, Sr. acquired the majority of this property, but a small section of it, probably not coincidentally 70 perches, did have an identifiable history. Since this small lot, labelled C5:137 on Figure 11, would be the portion that might contain the excavated site, its history was pursued.

Armstrong had acquired this lot from Joseph C. Grubb, who owned the plantation on the south side of the Turnpike, in January of 1839 (C5:137). The price was only \$15.00 which doesn't suggest that it was much improved. The lot was part of a larger parcel which Grubb had obtained the previous year from Joseph T. Baily, and the boundaries given for the smaller lot indicate the reason for the sale. The northern boundary of the 70 perch tract is given as the "Old Road between Wilmington and Hockessin" and the southern boundary is given as "the middle of the turnpike road". On Figure 11, these two alignments are extended as dotted arrows. It is reasonable to assume that the old road had not been used since the establishment of the Turnpike after 1811. It was still given as the southern boundary of the Temple tract in this location, however, so this transfer merely extends that property south to the road that was currently in use, and eliminates the small sliver of land owned by the Grubb, whose major land holding extended along the south side of the Turnpike.

The transfer of the larger parcel on the south side of the

The transfer of the larger parcel on the south side of the Lancaster Turnpike from Baily to Grubb (B5-435; August 21, 1838) appears to be an example of a similar realignment of property lines with reference to the Centre Road. This two acre parcel was originally acquired by Baily as part of a larger tract, labelled G3:114 on Figure 11, which straddled the Centre Road, so with this deed, the property on the west side of Centre Road was consolidated and separated from that on the east side.

That the 70 perch lot was included as part of G3:114 in its previous history is confirmed by the deed in which Baily acquires the latter tract. That deed is from John Gordon, of Wilmington, to Baily, whose residence is given as Christiana Hundred, and the northern boundary of this 99 acre tract is given as the "middle of the New Garden and Wilmington Road" (V4:12; March 24, 1835). The last named road is assumed to be equivalent to the Hockessin Road. Also transferred is a similar triangular parcel to the south (labelled Q3:5 on Figure 11) which represents a previous consolidation of property on the east side of Centre Road. The 99 acre, 48 perch tract, which included the parcel marked B5:435 on Figure 11, had been acquired by Gordon in 1813 from John Haddock, a farmer of Christiana Hundred. Since we know that Gordon continued to reside in Wilmington during this period, this farm must have been rented, or unoccupied. In the absence of any other evidence, it seems likely that the principal residence for this tract would have been located at or near the location of the structure marked "J.M. Hoffecker" on the Rea and Price Map (1849, Figure 7). This is the only structure location ever mapped within the property boundaries plotted as "G3:114" on Figure 11. If the excavated site was located within these boundaries, it would have been at the extreme northwest corner of the property on the Turnpike Road, during a period when "Manor Houses" were more commonly located near the center of a property and away from the roads.

John Haddock had acquired G3:114 in 1808 from Robert Armstrong, Jr., a farmer of Christiana Hundred. Haddock is described as a farmer of the Northern Liberties in the City of Philadelphia, and it seems likely that, since he is listed as resident of Christiana Hundred when he sells it in 1813 that he moved from Philadelphia to occupy this tract. Robert Armstrong Jr., on the other hand, inherits his interest in the property, and, since the boundaries include a new line which separates this tract from the remainder of his property it is likely that he resides there on the south side of this tract, or elsewhere. Various Armstrongs own property from this area south, and the earlier history of this tract was not pursued.

While this provides the ownership history for the properties most likely to contain the excavated site, it adds little additional basis for deciding which of these histories is pertinent to the site, and now the issue of site function might be resolved. A few additional observations might be made, however. The position of the building adjacent to the road was not typical of the residence of a major property owner, as was

previously observed. Although small lots (70 perches, two acres) appear briefly in the property histories recited above, it is fairly clear that these represent the adjustment of property holdings to the road network, rather than the creation of small residential lots, so it seems likely that the excavated site was always a rented or leased residence. Whether or not the tenant was engaged in agricultural activity is another matter, and one of particular interest since one of the research goals was to help clarify the relationship of this occupation (tenant farmer) to the artifact assemblage. Because of the location of the site near the intersection of Centre Road with Lancaster Pike, the possibility that the site represented a Toll House was raised. Also, there was some question as to why the Turnpike did not just follow the alignment of the older Hockessin road, rather than following a new alignment, as indicated by the boundaries of the 70 perch lot (C5:137 on Figure 11).

With these questions in mind, research into the Wilmington and Lancaster Turnpike was carried out. Because the economic ties of each colony had been external, following the mercantile system toward England, internal transportation networks had not been developed. As the economic integration of the various parts of the United States developed the need for better transportation arteries was perceived, but political bickering hindered government action. The need was strong and private capital was put forth to address it, specifically for building toll roads, or turnpikes (Heilbroner 1977:29-31). By the 1790's, the toll road from Lancaster to Philadelphia had been completed, and its success stimulated similar ventures. Farmers in southern Lancaster and western Chester counties sought outlets for their produce (Lindstrom 1978:100), and a toll road in Pennsylvania from Gap, on the Lancaster Turnpike, toward Newport was authorized by the Pennsylvania legislature in April of 1807. The Delaware Legislature responded by authorizing a corporation to build the section from the Pennsylvania Line to Newport (Enrolled Bills 1808-1810, Accessioned Legislative papers, originals on Microfile, Delaware Hall of Records).

The lengthy introductory material for the authorization bill emphasizes the bad condition of the existing public roads and the needs of the farmers to transport their produce, while Lindstrom suggests that the transport of low-volume high-value market goods from the regional centers to the interior was a more important factor (Lindstrom 1978:100). The fact that a petition for the building of a branch turnpike from Wilmington to the Newport-to-Gap Turnpike was granted by the legislature in 1808 tends to support the notion that the influence of merchants, more numerous in that city, was important. This branch is the "Lancaster Pike", Route 48, which runs past the Grant Tenancy. The Delaware bills authorizing the construction of turnpikes were basically copied from the Pennsylvania law with minor exceptions. Right of eminent domain and materials are granted to these private corporations, and the form of the road is specified: not more than 100 feet in width, with a twenty foot width improved by bedded wood, stone, clay, gravel or other proper and convenient

material, well packed and crowned in the middle for drainage. Provision is made for selecting the straightest route, and this is probably the explanation for the shift in alignment reflected in the deeds described above. A local variation for the Wilmington Branch is that toll houses are authorized every two miles, instead of the five mile interval specified for the original road.

The original manuscripts of the Minutes of the Wilmington Turnpike company were examined at the library of the Delaware Historical Society and some entries pertaining to the study area were noted. In March of 1812, a committee inspected a portion of the road "undertaken by John Haddock" and declared that they were satisfied. In 1814, a toll house under construction near Springer's Tavern was removed because of some unspecified "trouble to the workmen", and this may be near the location marked "Springer" west of the Oak Hill School on the Heald map (1820, Figure 12). In 1818, the road was divided into two parts: 1. from Market Street for 3 1/2 miles, and 2. from that point to the Gap Road, 3 miles, 138 perches, and different toll rates set for the two sections. Scaled on a modern map, this point would fall about 1000 feet west of Little Mill Creek, or about 1750 feet west of the excavated site. The rates are lower on the outer section, from this point to the Newport Road. The receipts and expenditures show two gates, as does the Rea and Price Map (Figure 7), but the latter map shows a gate a considerable distance further west than the dividing point calculated above, as well as one at the edge of Wilmington. In general receipts at the outer gate are lower than those for Gate 1. In 1824, the minutes acknowledge that there is no hope that the income from the road can ever pay off the principal of the bank loans for its construction, and by the late 1850's the assets, including the toll houses are being liquidated.

In summary, the turnpike was probably relocated south of the old road in order to provide a more direct route, and all of the available documentation suggests that the toll houses were in locations other than that of the excavated site. A further observation is in order at this point. The general assumption adopted during the background research was that the present alignment of the Lancaster Pike was very near to the nineteenth century position of the road, clearly leaving the excavated site on the north side of the road, even in the nineteenth century. An unsuccessful attempt was made to locate any documents that may have been retained by local governments, who were responsible for public road construction and maintenance until the first decade of the twentieth century, to determine if the present alignment was, in fact, further south than the turnpike. If the alignment of the turnpike was further north by the amount of the distance from the site location to the present road, then the excavated site would have been located on a property or properties south of the nineteenth century turnpike, and these properties were not researched for this project. A glance at Figure 11 should reveal that this is possible, though not as likely as the assumption used.


Provision is made for selecting the straightest route, and this is probably the explanation for the shift in alignment reflected in the deeds described above. A local variation for the Wilmington Branch is that toll houses are authorized every two miles, instead of the five mile interval specified for the original road.

The original manuscripts of the Minutes of the Wilmington Turnpike company were examined at the library of the Delaware Historical Society and some entries pertaining to the study area were noted. In March of 1812, a committee inspected a portion of the road "undertaken by John Haddock" and declared that they were satisfied. In 1814, a toll house under construction near Springer's Tavern was removed because of some unspecified "trouble to the workmen", and this may be near the location marked "Springer" west of the Oak Hill School on the Heald map (1820, Figure 12). In 1818, the road was divided into two parts: 1. from Market Street for 3 1/2 miles, and 2. from that point to the Gap Road, 3 miles, 138 perches, and different toll rates set for the two sections. Scaled on a modern map, this point would fall about 1000 feet west of Little Mill Creek, or about 1750 feet west of the excavated site. The rates are lower on the outer section, from this point to the Newport Road. The receipts and expenditures show two gates, as does the Rea and Price Map (Figure 7), but the latter map shows a gate a considerable distance further west than the dividing point calculated above, as well as one at the edge of Wilmington. In general receipts at the outer gate are lower than those for Gate 1. In 1824, the minutes acknowledge that there is no hope that the income from the road can ever pay off the principal of the bank loans for its construction, and by the late 1850's the assets, including the toll houses are being liquidated.

In summary, the turnpike was probably relocated south of the old road in order to provide a more direct route, and all of the available documentation suggests that the toll houses were in locations other than that of the excavated site. A further observation is in order at this point. The general assumption adopted during the background research was that the present alignment of the Lancaster Pike was very near to the nineteenth century position of the road, clearly leaving the excavated site on the north side of the road, even in the nineteenth century. An unsuccessful attempt was made to locate any documents that may have been retained by local governments, who were responsible for public road construction and maintenance until the first decade of the twentieth century, to determine if the present alignment was, in fact, further south than the turnpike. If the alignment of the turnpike was further north by the amount of the distance from the site location to the present road, then the excavated site would have been located on a property or properties south of the nineteenth century turnpike, and these properties were not researched for this project. A glance at Figure 11 should reveal that this is possible, though not as likely as the assumption used.

FIGURE 12

PORTION OF 1820 HEALD MAP OF ROADS OF NEW CASTLE COUNTY.
SURVEYED AND PRINTED BY HENRY HEALD



Additional research for other purposes is underway for the property south of the present alignment of Lancaster Pike, and this may shed additional light on the problem at some future time. In the meantime, it must suffice to observe that the background research has not positively identified the function or occupants of the site excavated as the Grant Tenancy, though the probability that it may have been occupied by a property owner has been considerably reduced. It is therefore likely that it was, indeed, a "tenancy". Whether or not the site was occupied by a tenant farmer is another matter. Since it sits immediately adjacent to roadways of some antiquity, it may have provided some services to travelers. Neither maps nor documents specifically indicate the presence of a tavern at or near this spot, but that does not rule out the possibility that this activity occurred there. Court records indicate frequent prosecutions for the selling of spirits without a license, suggesting that this was not an uncommon practice. The identification of distinctive archeological patterning for site function may further clarify the status of this site, but, for the moment, the background research leaves some ambiguity.

Fieldwork

The following presents the results of the fieldwork by provenience group and/or method of excavation. The provenience groupings were based on the soil and depositional contexts, the collection methods used and the integrity of the materials collected. Brief descriptions of the types of artifacts found are given below for each provenience group. A summary listing of the artifacts recovered is given in the Artifact Inventory, Appendix II.

Controlled Surface Collection

The results of the surface collection are shown on Figures 3-6. The site was plowed the week before the archeological team was to arrive to allow for a rain to fall and thus optimize collecting conditions. The results of the initial collection indicated that the highest concentration of artifacts occurred at the very western edge of the plowed area. The plow was brought back to the site and the surface collection was extended an additional 60 feet to the west in order to better define the entire site area. However, collecting conditions were not the same for both sections, a point which needs to be emphasized when examining the results in the figures provided here. The collection west of the East 370 line was collected under less than ideal conditions (very little rain had fallen after the plow/disc operation) and this is probably reflected in the raw counts. The results of the surface collection did prove to be a useful tool in predicting the presence of subsurface features. The house foundation and the larger features fell within the areas with the highest concentration of artifacts. As shown in Figures 3-6, this corresponds roughly to the area between East 350 and East 410; North 140 and North 200. The surface

collection, however, failed to foretell the "midden" (Feature 5, see discussion below), located south of the North 140 grid line and in the east. The reason for this is not clear.

Ceramic types recovered from the surface collection include undecorated refined white earthenwares as the majority type with pearlware (1,930) dominating and smaller amounts of creamware (241) and whiteware (433). Decorations present on the refined white earthenwares include transfer printing, hand painting, annular and edge decorated. The second largest ceramic type represented in the surface collection was coarse red earthenware (1,584), followed by refined redware (144), yellowware (49), stoneware (28) and porcelain (43). No identifiable maker's marks or patterns were present in the controlled surface collection artifacts. Tobacco pipes (301) were also present including one which was glazed. Most of the bottle glass (389) recovered consisted primarily of small sherds on which the manufacturing technique could not be determined, however, examples of both machine made and mold blown glass were found. Various miscellaneous types of hardware were found as well as slate pencils and buttons. Coins recovered from the controlled surface collection include a 1961 copper penny. A pewter tableware handle with "BEST TAR... LET...9" and an embossed crown was recovered during the surface collection. Several prehistoric artifacts were also found including a jasper flake, a chert flake and a quartz flake. A complete artifact inventory is found in Appendix II.

Plowzone Sampling

The excavation of five by five foot units was started at grid points N125E395 and N130E415 in order to relocate Units A and F from the 1983 test excavations (Figure 13). These two adjacent units had contained Feature 2 (herein referred to as Feature 2/83 to distinguish it from features recovered during the Phase III excavations), a rock cluster which was interpreted at the time as a portion of a house foundation (Barse 1985:75). The Phase III investigations later proved this interpretation to be incorrect, however. Beginning at about #410, an artifact rich midden deposit was noted lying stratigraphically between the layer of field stones and the plowzone, again, increasing with depth towards the northwest (Figures 14 and 15). Artifacts were associated with both the midden and the stone layer, but not the underlying subsoil. Figure 14 shows the profile across the site and the relationship between the plowzone, midden, stone layer and subsoil. The absence of the midden east of E405 appears to be due to its having been incorporated into the plowzone where these two strata occur at a shallower depth.

The artifact assemblage recovered from the plowzone was similar to that from the controlled surface collection with refined white earthenwares comprising the largest percentage of the ceramics. Pearlware comprised the largest group with 5,699 sherds, followed by whiteware with 1,767 and creamware with 756. Decoration on the refined white earthenwares includes transfer




FIGURE 13
H. Grant Tenancy Site (7NC-B-6)
Site Grid Showing Controlled
Surface Collection Boundary and
Plowzone Sample




FIGURE 14
 H. Grant Tenancy Site (7NC-B-6)
 East/West Profile @ N135 Grid Line





FIGURE 15
H. Grant Tenancy Site (7NC-B-6)
N/S Stratigraphic Crosssection @ E390

PLATE 3
PROFILE SHOWING MIDDEN



printed, hand painted edge decorated and annular. These were followed by coarse red earthenwares, (4,743) refined redware (705), yellowware (276), stoneware (39) and porcelain (91). The bottle glass (926) was generally undiagnostic, although some examples of pressed glass as well as fragments and mold blown bottle glass were recovered. An 1850 Indian Head Cent, an 1858 Flying Eagle Cent and an 1852 Silver Cent were recovered during the excavation of the plowzone. Other metal artifacts include various buttons (15), miscellaneous hardware and a jew's-harp. Three of the buttons were embossed with "Double Gilt...2nd Quality". A chalcedony gunflint was also found. Prehistoric artifacts found include 3 chert spalls, 4 chert flakes, 3 quartz flakes, 3 jasper flakes and the distal portion of a milk quartz projectile point or knife, in addition to heavily reworked quartz side notched point/biface which cannot be typed and a temporally undiagnostic contracting stem biface.

Feature 5, or "Midden" is defined as an artifact rich layer of dark brown silt-loam soil which rests in an elongated depression (Plate 3). This depression was not apparent on the ground surface however it penetrated the subsoil for as much as a foot in some areas (Figure 14). It appears to be an old road bed or erosional gully which has been filled in with the artifact rich soil. This soil is not appreciably different in texture and color from the overlying plowzone and may represent topsoil which has been pushed into a gully perhaps for erosional control or landscaping. There was no evidence to suggest whether this had been done recently or whether it had been done at the time of occupation of the house. From its appearance it does not seem likely that the gully had filled in naturally although this possibility cannot be ruled out. Portions of this midden were excavated and portions were simply exposed and mapped during plowzone removal with the backhoe. The base of the midden was characterized by a layer of field stones.

The Midden begins at about N125E410 and extends across the site to the northwest generally getting thicker in this direction (Figures 2, 14, 15). The gully in which the midden rests actually extends to the southeast slightly beyond the end of the midden. The absence of the midden at this point is due to the fact that the gully is shallower here and the midden fill would have been incorporated into the plowzone. It was in this gully where Features 2/83 was located during the Phase I/II investigations. The stones at the base of the gully were originally interpreted as a foundation feature.

The midden soil was a dark brown silt-loam containing artifacts which were larger and less fragmentary than those recovered from the plowzone above it.

The configuration and orientation of the midden and underlying rock feature suggest two possible interpretations, neither of which could be confidently accepted in preference to the other. One possible interpretation is that the midden represents an in situ refuse deposit in which trash was thrown

into a nearby gully on the opposite side of the house from the well. This as a practice is consistent with similar domestic sites during the 19th century. However, if the location of Lancaster Pike today is the same as it was at the time the site was occupied then this would place the refuse dump between the house and the road.

Another possible interpretation for the presence of the midden and stone layer is that stone, and then afterwards, artifact bearing soil was pushed into an erosional gully or abandoned road bed in an effort to level the field for agricultural purposes. This might have occurred at the same time the house was destroyed and the cellar and well were filled in. In each of those cases it is clear that cultivation was possible after that time. The house and the well were demolished in a manner which permitted cultivation afterwards, even directly over these two ruins. The remaining stone foundations and debris from the house and well were below the reach of the plow. The field was planted in hay at the time of the excavations and there was no surface evidence of the house except for the presence of the artifacts lying on the surface.

Artifacts recovered from the midden were again similar to those recovered from the first two provenience groupings with undecorated refined white earthenwares and coarse red earthenwares comprising the two largest groupings. Of the refined white earthenwares, pearlware was the largest group with 1,874 sherds, followed by whiteware (441) and creamware (260). Decorations on the refined white earthenwares include transfer printing, hand painting, edge decoration and annular decoration, etc. Hand painted refined white earthenwares made up a slightly larger percentage of the decorated wares, with a decrease in the various minimally decorated wares (edge decorated, annular, finger trailed, etc.). Yellowware made up the next largest group (173) followed by porcelain (50), refined redware (21), refined stoneware (22) and coarse stoneware (10). The bottle glass (248) was generally undiagnostic, with several pieces of pressed glass and mold blown glass being present. A silver thimble, various buttons and flatware fragments, a slate pencil, barrel band fragments and a gunflint were also recovered from the midden deposit. One hundred six tobacco pipe fragments were found. Prehistoric artifacts recovered include 2 distal ends of quartz biface/points, a chalcedony flake, 2 quartz flakes and a heavily reworked point.

Forty-seven and one-half 5 by 5 foot units were hand excavated with the plowzone screened. They were distributed in a linear fashion across the area of the site with the highest concentration of surface artifacts. Figure 13 shows the distribution of these units. A composite profile across the site from north to south is presented in Figure 15. A number of features including the house foundation were encountered in these units at the surface of the subsoil and a discussion of each is presented in the following section of this report.

Feature Excavation

After completion of the excavated five by five foot units, the plowzone was stripped from the remaining site area with the backhoe in order to expose the entire house foundation and to expose all other features not already identified during the plowzone sampling. The total area exposed in this manner is shown on Figure 2. A description of each feature is presented below.

House

Overlying the actual foundation of the structure was a 2Ap horizon or buried plowzone consisting of a dark brown silty loam. Artifacts recovered from this horizon include decorated and undecorated refined white earthenwares, coarse red earthenwares (531), refined redware (104), yellowware (35), coarse stoneware (5) and porcelain (21). Pearlware (613) comprised the major portion of the refined white earthenware grouping with whiteware (235) and creamware (83) also represented in smaller quantities. Glass artifacts included both window (982) and bottle glass (149). The remaining glass artifacts were undiagnostic. Can fragments, various metal hardware items, tableware fragments, buttons (14) and 2 gun flints were also found. One of the buttons was a shank type with an eagle marked with "AN.HORSTMANN & ALLIEN" and was found in the 2Ap. Another shank button marked "Robinson...EXTRA..." was also found. Seventy tobacco pipe fragments were recovered. A quartz distal portion of a biface/projectile point was also present.

All traces of the house above the surface of the subsoil were missing other than one or two stones and, of course, the artifacts within the plowzone. Plate 4 shows the exposed house foundation. Below this level, however, the cellar walls were virtually intact. The north and south walls were slumped slightly towards the interior of the house as though these were the walls which were originally pushed in at the time that the house was demolished. The cellar walls were made of stone cemented with mortar which, at the time of the excavation, was very friable and had lost its bonding properties. The interior surfaces were coated with whitewash, most of which had deteriorated and fallen off. The thickness of the walls ranged from 1.4 to 1.7 feet and were constructed by first forming two rows of larger "face stones" along the exterior and interior surfaces and then filling the resulting voids with smaller irregular stones (Figures 16 and 17). This method of construction results in a smooth "finished" appearance to the interior surface of the cellar wall.

The brick from the Grant Tenancy site was generally coarse sand with a few glazed specimens and the colors ranged from 2.5YR4/6 to 5YR6/8. The length of the brick ranged from 8.2-8.4" with a mean of 8.25". The width ranged from 3.2-4.2" with a mean of 3.93" and the thickness ranged from 1.9-2.4" with a mean of 2.04".

PLATE 4

VIEW OF FOUNDATION LOOKING SOUTHWEST



FIGURE 16
H. Grant Tenancy Site
(7NC-B-6)
House Foundation -
Detail Chimney Footing




FIGURE 17
H. Grant Tenancy Site (7NC-B-6)
House Foundation - Detail SW Corner




PLATE 5
CHIMNEY SUPPORT DETAIL LOOKING EAST



Two walls extended out from the east wall into the interior of the house (Figure 16). These were constructed in the same manner as the cellar walls and were between 1.6 and 1.7 feet thick, measuring four feet in length from the interior surface of the east cellar wall. They are positioned slightly off center of the centerline of the house and measure 5.2 feet from center to center. Each of the interior walls is simply butted against the exterior cellar wall rather than being joined with interlocking stones. This might suggest that they were added at a later time or, alternatively, that the strength provided by the interlocking method of construction was not a consideration in their design. They are interpreted as a chimney or stove support. Plate 5 shows a detail of the chimney supports. The cellar contents contained a small ash and brick concentration at the northeast corner of the cellar adjacent to these interior walls. This appears to represent a discrete depositional episode which may be some sort of ash and refuse dump. The artifacts contained within this ash and brick concentration were probably mixed with the brick at the time of demolition or shortly before. It is unlikely that they were present in the fireplace as they were unburned.

The southwest corner of the cellar wall was constructed differently from the other three corners. A detail drawing is shown in Figure 17. The corner is heavily buttressed, beginning at approximately 3 feet above the level of the cellar floor. Unfortunately, not enough of the wall remained to determine why this extra buttressing was required at this corner. It is perhaps a support for steps or a staircase (Plate 6).

An estimate was calculated of how much of the walls had been removed above the subsoil based on the amounts of stone recovered from the cellar fill. Given the very large quantity of stone removed from the excavation of the cellar fill, the question was raised as to whether the structure was wood frame or log, resting on a stone foundation or perhaps portions of the house above the cellar were also constructed of stone. The fill was predominantly stone with the remainder consisting of soil and artifacts. Very little wood was recovered from the cellar fill which may indicate that either most of the structure was stone or that the wood was simply missing at the time of demolition either from natural decay or from scavenging. By calculating the volume of stone contained within the remaining walls and comparing this with an estimate of the amount of stone contained within the fill, it is possible to determine whether or not enough stone was present in the fill to have provided an upper story. This is, of course, assuming that the stone within the cellar fill was in fact from the house walls. Excluding the two interior support walls, the cellar walls contained 294.0 cubic feet of stone and mortar. Given the exterior dimensions of the structure at 16 x 15.5 feet and with each wall averaging 1.5 feet in thickness and 3 1/2 feet high, each additional foot of wall above what was left intact would require 84.0 cubic feet of stone and mortar. The volume of stone and soil contained within the cellar fill amounts

PLATE 6
SOUTHWEST CORNER OF HOUSE



to 546.0 cubic feet. Allowing for voids and soil within the cellar fill comprising anywhere from 1/4 to 1/2 of that volume (based on a visual estimate at the time of excavation) and accounting for the volume taken up by the ash and brick concentration (21 cubic feet), and the interior wall supports (47.6 cubic feet), this leaves from 3.97 to 4.46 additional feet of cellar wall that can be accounted for from the stone recovered from the cellar fill. This translates to 6.47 to 7.96 feet of cellar wall height (measured from the cellar floor), enough for a full cellar but little else. If the structure did contain above ground portions made from stone, then the stone was removed from the site at demolition or shortly thereafter. In any case, there was very little stone in the plowzone and it appears that the site was cleared sufficiently to allow for easy cultivation of the area. Because there was very little evidence for a large scale fire, it is presumed that the absence of lumber recovered from the cellar fill indicates that the wood was either totally scavenged at the time of demolition or that the structure was abandoned for a long enough period of time for natural decay and/or scavenging to have removed most of the lumber prior to the collapses of the building in on itself and the intentional filling of the cellar.

Ceramic artifacts from the cellar fill included undecorated refined white earthenwares as the largest group, followed by coarse red earthenwares (618). Transfer printing was the major decorative type found on the refined white earthenwares. Other ware types found include refined redware (118), yellowware (42), coarse stoneware (23), refined stoneware (8), and porcelain (48). Most of the refined white earthenwares were typed as pearlware (1,225), although whiteware (419) and creamware (96) were also found in smaller percentages. An almost complete brown salt glazed stoneware bottle was reconstructed from sherds from the cellar fill (Plate 7). An impressed mark and date were present on the bottle. The mark was "J. B. Bryant" and the date was "1847". In addition, an almost entire trailed slip decorated coarse earthenware pie plate with a rouletted edge was recovered as well (Plate 8). Undiagnostic container (274) and flat glass (1,673) was also present in the fill as well as fragments of a mold blown bottle, mold type unknown. Several pieces of embossed mold blown bottle fragments were also found, however, the embossing was fragmentary and no additional information is available. Pressed glass fragments were also present. Can fragments, miscellaneous pieces of hardware, buttons (40), a thimble, a gun flint were present in the cellar fill. One of the buttons was a brass shank type marked "London...Super Fine". Three coins were found and a religious medal was also recovered from this provenience group. This has a figure on the obverse side with the words "mere de dieu priez pour nous" which translates as "Mother of God pray for us". The reverse side shows the peaked hat symbolic of the French Revolution and what appears to be a symbol of Calvary. Prehistoric artifacts recovered from the cellar fill include 2 chert flakes, the distal portion of a quartz biface, and 2 quartz flakes. In addition, a mass of charred wood fragments and heavily oxidized and

PLATE 7

STONEWARE BOTTLE




PLATE 8
REDWARE PIE PLATE




deteriorated ferrous metal encrusted with sand was removed from the cellar fill. Based on the impression left after excavation, this was interpreted as a burned keg and was mapped in situ in the field. Upon close examination in the laboratory, it was decided that the condition of the remains was beyond conservation and it was discarded.

Underlying the cellar fill was a floor midden which was clearly discernible as a compacted sandy loam and contained artifacts. It is interpreted as a "living surface" which was deposited during the occupation of the structure. It was .3 feet thick and varied little in depth across the floor. Below this level was the banded coarse sandy "C" horizon material consisting of weathered bedrock that forms the parent material for the soils in this area. Excavation of the floor midden was divided into two units. The floor midden lying between the two interior support walls was separated from the rest of the floor. Artifacts from between the two interior support walls included no ceramics, 1 bottle fragment, 4 flat glass fragments, 2 cut nails and 16 brick fragments. The artifacts recovered from the rest of the floor area included 39 ceramic fragments which were predominantly pearlware. Fourteen flat glass fragments and six bottle fragments were also included. Forty-three can fragments, a lead bale seal and a number of brick fragments, as well as a heavily reworked quartz stemmed projectile point were also recovered from this area.

The upper portion of the house extended beyond the cellar walls on the east side of the house and an addition or attachment (such as an exterior shed or porch) may have been present on the western side of the house as well. Removal of the plowzone surrounding the cellar revealed a series of six circular postmolds (P.H.1-6, Figure 2) on the western side. These followed a line parallel to the west cellar wall at a distance of 5 feet from its edge. The spacing was slightly irregular and ranged from 2.1 to 3.1 feet. Other than the builder's trench which followed the cellar wall, no other features were noted to provide clues as to the nature of the postmolds. They may represent an attached structure, a porch, or, alternatively, a fence. This is in contrast to the east side of the house where an addition or an attachment to the house was clearly evident. Here, the builder's trench extended beyond the east cellar wall forming a rectangular shaped pit measuring six feet wide and sixteen and one half feet in length, just slightly longer than the east cellar wall. The fill within this area was labeled as "exterior midden" when it was first identified and this label, although somewhat misleading, was retained for consistency. In profile (Figure 18), the trench slopes steeply from the far eastern edge to the base of the cellar wall. A linear stain was present along the eastern edge which runs parallel to the eastern cellar wall. This stain ran the length of the wall and measured 1.5 feet wide and .9 feet in depth, measured from the base of the plowzone. It is interpreted as a sill stain; the wooden sill would have provided support for floor joists extending from the top of the cellar wall. With the exception of the sill stain,

FIGURE 18
H. Grant Tenancy Site (7NC-B-6)
Profile of House Foundation Looking North



Horizontal Scale 1" = 5'

Vertical Scale 1" = 1'

the fill within this feature was relatively homogeneous from the cellar wall to its eastern edge. It consisted of a micaceous coarse sand with small weathered rocks and was relatively loose and uncompacted. It appears to have been derived from the local "C" horizon material which was re-mixed with humus and occasional artifacts. The sill stain consisted of a dark silty loam and the portion which was excavated did not contain artifacts. Including the eastern extension, the length of the house was 22 feet, with the possible addition of another five feet on the western side (of the six postmolds there represent a porch or attachment and not a fence line). The width of the house is 15.5 feet, based on the dimension of the cellar wall.

Materials recovered from the "exterior midden east" include, like the previous provenience groupings, undecorated refined white earthenwares (29) as the majority type, followed by coarse red earthenware (18), hand painted refined white earthenwares (6), transfer printed refined white earthenwares (4), minimally decorated refined white earthenwares (2), porcelain (2) and refined redware (1). Most of the refined white earthenwares were typed as pearlware (28), followed by whiteware (13). Flat glass (20) and container fragments (4) were recovered from this provenience. Other artifacts recovered include 8 cut nails, brick, mortar and coal and 1 bone button.

The ash and brick concentration in the northeast corner of the cellar is interpreted as a refuse deposit dumped into the cellar sometime prior to the filling in of the cellar. The concentration was easily discernible from the rest of the cellar fill and situated in the very corner of the cellar. It was unmixed (with the overlying fill) and provides a good sealed context. A total of 190 ceramic fragments were recovered, including 48 pearlware, 21 creamware, 1 yellowware, 23 whiteware, 36 coarse red earthenware fragments and 58 "other". Nails from this context included 65 cut and 17 wrought specimens. Mold blown bottle fragments were present, however, the type of mold could not be determined. Various hardware specimens including a horseshoe, can fragments, a ferrous metal button, a bone button and two projectile points were recovered from the ash and brick concentration. Both of the projectile points were heavily reworked and stemmed, one was from quartz and one was from rhyolite. Additionally, a large quantity of brick and coal was recovered.

The final context associated directly with the structure includes the sample of artifacts recovered from the cellar wall builder's trench. The central portion of the south wall was removed in order to recover this sample. Additionally, builder's trench artifacts recovered while exposing the upper portion of the remaining cellar wall are included. Eighty four ceramic fragments were recovered including 40 pearlware, 9 whiteware, 4 porcelain, 2 yellowware, 1 creamware, 1 stoneware, 25 redware and 2 "other". Other materials include 47 window glass fragments, 8 cut nails and 9 tobacco pipe fragments. Flatware fragments, a

horseshoe, can fragments, brick and mortar were also present. The presence of these artifacts indicates prior use of the site.

Feature 8

Feature 8 represents the remains of a well (Plates 9 and 10). The well was uncovered during the plowzone stripping and is located 10 feet from the northeast corner of the house. The methods of excavation utilized in recovering the fill and contents of the well are discussed earlier in this report. The base of the well was reached at 13 feet below the surface where the interior diameter of the well was 2.6 feet. The stone wall rested on bedrock which had been chiseled out at the base to provide an additional one half foot. The water table was measured after an overnight pause and was recorded at 11.1 feet below the surface (159.3 feet above sea level). This provided two feet of standing water. The profile of the well is shown in Plate 10 & Figure 19. The upper 11.4 feet consisted of fill which was predominantly large stones and brick, and only a slight amount of sediment. Underlying this was a layer of sandy silt. Artifacts were recovered from both layers. The ceramics from Feature 8 consisted primarily of undecorated pearlware, however transfer printed, hand painted and minimally decorated pearlware was also present. One hundred thirteen pearlware sherds were recovered. Other ware types found include coarse red earthenware (38) refined redware (6), yellowware (3), stoneware (4), whiteware (8), creamware (4) and a single sherd of porcelain. Eight tobacco pipe fragments were found. undiagnostic flat (24) and container glass (9) was also present. A copper half cent on which the date was undecipherable was present. In addition, 680 can or bucket fragments were recovered from the well. Wooden artifacts recovered from the well included 1 disarticulated bucket with one ferrous metal band, a wrought ferrous metal handle and a very heavily oxidized chain fragment. This is probably the well bucket (Plate 11). A square, wooden, possibly cedar, post fragment with a diagonally cut point at one terminus was also recovered from the well, in addition to numerous wood fragments. The well also contained oak board fragments, pine board lathe fragments and a wooden dowel fragment. An oak plank with a ferrous ring attached was found in the well; this may be a gate fastener fragment. Two fragments of leather, one of which had a punched hole for a buckle tang were recovered. These appear to be harness leather pieces. Twenty three whole cherry pits, 18 cherry pit fragment, 2 whole peach pits and 3 peach pit fragments were recovered from the well.

Feature 10

Feature 10 was a large rectangular stain measuring 10.6 by 5.8 feet. The plan view is shown on Figure 20 (see also Figure 2). The stain was relatively shallow, measuring .4 feet (below the base of the plowzone) at its deepest point (Figure 21). Three postmolds were present at the base of the feature penetrating the subsoil but were not apparent in the feature fill during the feature excavation (Postmolds A, C and D, Figure 21).

PLATE 9
WELL DETAIL




PLATE 10

WELL PROFILE AFTER EXCAVATION LOOKING SOUTH




FIGURE 19
H. Grant Tenancy Site (7NC-B-6)
Feature 8 - Well Profile




PLATE 11
BARREL FROM WELL



FIGURE 20
H. GRANT TENANCY SITE (7NC-B-6)
FEATURE 10, PLAN





FIGURE 21
H. GRANT TENANCY SITE (7NC-B-6)
PROFILE, FEATURE 10, POSTMOLDS AND STAIN-PLAN VIEWS AND PROFILES



An additional postmold was located just outside the northwest corner of the feature (Postmold E, Figure 21). These stains varied in depth and only one (A) contained a definite outer stain surrounding the postmold. The artifacts from Feature 10 include 151 ceramics, 19 pieces of window glass, 7 cut nails, 2 tobacco pipe fragments and a number of small brick and coal fragments. The ceramics included 71 pearlware, 5 yellowware, 3 creamware, 4 porcelain, 18 whiteware and 33 redware fragments. Other artifacts recovered include a gunflint and a harness ring. The feature appears to be the remains of a small structure such as a shed or outbuilding, however, because of the limited amount of information remaining, this cannot be certain.

Features 2 and 11

These two cross-cutting features were located west of Feature 10. The plan and profile of each feature are included in Figure 22. Feature 2 was a rectangular stain measuring 1.9 by 3.1 feet. The feature fill consisted of a dark yellowish brown silty loam and the artifacts contained within the feature included 24 ceramic fragments, 1 piece of window glass, 1 cut nail, 1 brick fragment and 1 tobacco pipe fragment. Feature 11 intruded into Feature 2 and consisted of a circular stain measuring 2 feet in diameter with a basin shaped bottom. The fill was similar in color and texture to Feature 2 except that Feature 11 contained more charcoal flecks. Feature 11 may have been a posthole stain in which the postmold was either not discernible or the post had been removed. The artifacts recovered from Feature 11 were very similar in type and quantity to those recovered from Feature 2. They include a total of 31 ceramics, 4 window glass sherds, 5 cut nails, 2 tobacco pipe fragments, 2 can fragments and 13 brick fragments.


Feature 9

Feature 9 was a square stain measuring 3.7 feet on each side. It was relatively shallow and was originally thought to be the base of a short term privy. This hypothesis was based upon the shape of the feature, however, and soils analysis showed this not to be the case, as the phosphorus content was too low. The function of this feature is therefore unknown. The feature fill consisted of dark yellowish brown silty loam mixed with charcoal and brick flecks. The depth of the deepest point measures .5 feet below the surface of the subsoil. The plowzone removed above the feature was 1.1 feet in thickness. The artifacts recovered from the feature included brick and coal fragments, as well as 5 mortar fragments. The plan and profile are shown in Figure 23.

Feature 12

Feature 12 is located 16 feet grid north of the northwest corner of the cellar foundation. It is measured 2.7 by 2.9 feet and is nearly square (Figure 24). The feature fill consisted of a dark brown silty sand loam with a considerable amount of mortar and gravel mixed within the fill matrix. The boundaries in plan


FIGURE 22
H. GRANT TENANCY SITE (7NC-B-6)
Feature 2 and Feature 11, Plan and Profile



PROFILE OF
CROSS-SECTION OF
FEATURE 2



PROFILE OF
CROSS-SECTION OF
FEATURE 11









-  10YR3/4, SILTY LOAM
-  10YR3/4, LIGHTLY MOTTLED
W/ 10YR4/6
-  SUBSOIL-5YR4/6, SILTY CLAY
LOAM W/ MICACEOUS PARTICLES

FIGURE 23
H. GRANT TENANCY SITE (7NC-B-6)
FEATURE 9, PLAN VIEW OF FLOOR AND PROFILE OF NORTH HALF




KEY

-  10YR3/6, SILTY LOAM MIXED W/ CHARCOAL AND BRICK FLECKS
-  SUBSOIL-10YR5/8, CLAY LOAM

SCALE-1" = 1 FT.

FIGURE 24
H. GRANT TENANCY SITE (7NC-B-6)
FEATURE 12 AND POSTHOLE 380A, PLAN VIEWS AND PROFILES



view and cross section were sharp. Several rocks were contained within the fill, the largest measuring .5 feet in length. The artifacts recovered from the fill include 14 ceramics, 3 sherds of window glass, 7 cut nails, in addition to a number of brick and coal fragments. Its function is uncertain, however, one possibility is a pillar footing indicating another structure. A postmold was located .4 feet to the northwest and consisted of an outer post hole stain with a centrally located postmold. The profile is shown in Figure 23. The postmold was square and measured .6 feet on a side. The surrounding stain measured 1.4 feet in diameter. This seems large for a fence post and it may be related to Feature 12.

Other Features

The remaining feature numbers were assigned to stains or irregularities in the subsoil which were subsequently identified as either natural depressions in the subsoil or plowscars. These included Feature Nos. 1 and 3-6. Feature No. 5 was assigned to the midden south of the house which was described earlier in the report. The postmolds uncovered during the plowzone removal will not be discussed individually to avoid redundancy. A fence row is apparent in the E340 backhoe strip and followed a course along the grid north axis of E355. The postmolds are spaced between six and eight feet. None of the remaining postmolds could be associated in a linear pattern except those which have already been discussed.

Near the end of the fieldwork, four trenches were excavated using the backhoe in the area that fell within the construction right-of-way. Construction was due to begin on the road and this area was quickly tested using the backhoe to insure that no portions of the site would be lost to construction. Trenches 1, 2 and 3 (Figure 2) were excavated to the base of the plowzone and then flat shoveled by hand to identify any features that might be present. None were found. Trench 4 was excavated through a portion of the midden deposit to help determine its extent. Figure 14 was taken predominantly from this trench and shows the relationship of the midden to the plowzone and subsoil.

Intrasite Analysis

As mentioned in the previous discussion, the artifacts recovered from the site were separated into several provenience groupings based upon their soil and depositional contexts and to some degree (particularly with reference to the miscellaneous group), on the collection methods and integrity of the materials collected. These groups include: the Controlled Surface collection, the Midden (Feature 5), the 2Ap over the foundation, the Cellar Fill, the Cellar Floor Midden, the "Exterior Midden, East side of house", the Ash and Brick Concentration, the Builder's Trench, the General Surface Collection, and the various features. All intrasite analysis was done on the basis of these groupings.

Dating the Contexts

The various contexts/provenience groupings were dated using several methods. These were South's (1972) Mean Ceramic Date and Visually Interpreted Bracket Dates (1972, 1977) as well as an examination of the artifacts to determine the "termini post quem". The termini post quem was based on either ceramic or glass technology or, in some cases, coins.

The first analytical computeration performed on the provenience groupings consisted of calculating the Mean Ceramic Date. Stanley South's (1972, 1977) types were used with one additional type added by us to account for items which were clearly pearlware but which could not be placed in any one of South's types. This additional type was called "General Pearlware" and the dates for this type are based on the beginning date given for pearlware in South's types and the latest date for pearlware in South's types. The Mean Ceramic Date in Table 1 is expressed using South's types (MCD ST) as well as using the "General Pearlware" category (GP MCD). In the majority of the cases, there was very little difference. The formula used to calculate both of the Mean Ceramic Date expressions was developed by South (1977:217) and is as follows:

$$Y = \frac{\sum_{i=1}^n X_i \cdot f_i}{\sum_{i=1}^n f_i} \quad (1.1 \text{ years})$$

Chinese porcelain Types 26 and 39 are not included in the calculation of the Mean Ceramic Date.

The Visually Interpreted Bracket Dates consist of plotting the median beginning and ending dates for each of South's types represented in the assemblage (see South 1972, 1977 for a more detailed explanation of this dating method).

The dates for the provenience groupings are presented below, from earliest to latest, with the exception of the features, which are presented at the end.

Cellar Floor Midden

This context consisted of midden deposit which was contained within the cellar foundation, under the cellar fill. The midden deposit was interpreted by us as a living floor which was deposited during the occupation of the structure. The Mean Ceramic Date obtained for this context was 1812.15 and the Visually Interpreted Bracket Dates were 1790 and 1825. No diagnostic artifacts were found, with the exception of ceramics, to aid in dating this assemblage. The terminus post quem is

TABLE 1

MEAN CERAMIC DATES, H. GRANT TENANCY SITE
INTRASITE PROVENIENCE GROUPINGS

PROVENIENCE GROUPING	SOUTH'S MEAN CERAMIC DATES	GP MEAN CERAMIC DATES
Site Total	1814.91	1816.37
Cellar Floor Midden	1812.15	1812.15
Builder's Trench	1812.60	1812.76
Midden	1812.92	1813.82
Controlled Surface	1812.99	1813.55
Plowzone	1814.54	1816.70
2Ap Over Foundation	1818.43	1819.36
Cellar Foundation Fill	1818.43	1819.30
Backhoe Backdirt	1818.54	1818.85
Exterior Midden, East	1825.18	1825.77
Ash and Brick Concentration	1831.87	1831.94
Feature 2	Sherd Count too small	
Feature 8	1817.83	1819.60
Feature 10	1815.15	1815.96
Feature 11	1814.96	1814.96

provided by South's beginning date for the whiteware ceramic type - 1820.

Builder's Trench

This context was composed of a builder's trench which was located immediately adjacent to the cellar wall. The Mean Ceramic Date for this context was calculated at 1812.60, using only South's types and 1812.26 using the "General Pearlware" type as well. The Visually Interpreted Bracket Dates for this context are 1790 and 1820 and the terminus post quem is again proved by South's beginning date for whiteware - 1820. No other diagnostic artifacts were present.

Midden (Feature 5)

The midden was dark brown layer of soil located stratigraphically between a layer of field stones which represent a filled-in erosional gully or road bed and the plowzone, with the plowzone being located above the midden. Two possible interpretations were offered for this feature, one is that the feature constitutes an in situ refuse deposit and the other is that artifact bearing soil was placed in the erosional gully in order to level the ground for agricultural purposes. The Mean Ceramic Dates for the midden are 1812.92 using only South's types and 1813.82 using the "General Pearlware" category as well. The Visually Interpreted Bracket Dates are 1780 and 1820. A bottle fragment with a glass tipped pontil mark was found in the midden as well. This can be dated from ca. 1810-1857, on the assumption that pontils were not frequently used after the invention of the snap case in 1857 (Reher 1977). Another mold blown bottle was present which showed evidence of a lipping tool and can be dated from 1850-1903. The terminus post quem is provided by the lipping tool - 1850.

Controlled Surface Collection

The Mean Ceramic dates for the controlled surface collection are 1812.99 using only South's types and 1813.55 using the "General Pearlware" type. The Visually Interpreted Bracket Dates are 1790 and 1820. A 1961 copper penny was present as well as machine made glass. The machine made glass dates from 1903 to the present (Reher 1977). This is based upon the date for the introduction of the fully automatic bottle machine. Mold blown glass was also present and consisted of a bottle with evidence of a lipping tool (1850-1903), a two piece mold blown with a pontil mark (1840-1857), and a panel bottle with letter embossing (1867-1903) (Reher 1977).

Plowzone

The Mean Ceramic Dates for the plowzone are 1814.54 for South's types and 1816.70 for "General Pearlware". The Visually Interpreted Bracket Dates are 1780 and 1820. Other diagnostic artifacts from the plowzone include a 2-piece mold blown bottle

with a pontil mark (1840-1857, Reher 1977), an 1859 Indian Head Cent, an 1858 Flying Eagle Cent and 1852 Silver Cent.

2Ap (Plowzone) Over Foundation

The 2Ap over foundation context consisted of a second plowzone lying directly over the cellar foundation. The Mean Ceramic Dates for this group are 1818.43 for South's types and 1819.36 using "General Pearlware". The Visually Interpreted Bracket Dates are 1790 and 1820. Two mold blown bottle fragments were found and although the specific mold type could not be determined, they can be dated from 1810-1903 (Reher 1977). A mold blown panel bottle dating from 1867-1903 was also found (Reher 1977). A shank button was present in this horizon. This button was marked with an eagle and "A.N. HORSTMANN & ALLIEN". It must date to after 1850 as this is the date when Henry V. Allien was taken into partnership in the New York branch of the Wm. H. Horstmann Co. (New England Publishing Co. 1972). This company made military furnishings. The terminus post quem, 1867 is provided by the panel bottle.

Cellar Foundation Fill

The cellar foundation fill was a fill zone lying directly inside of the foundation walls and is thought to have resulted from the intentional filling of the cellar. The Mean Ceramic Dates for this zone are 1818.43 for South's types and 1819.30 using "General Pearlware". The Visually Interpreted Bracket Dates are 1790 and 1825. The diagnostic glass included a bottle with evidence of a lipping tool (1850-1903), a 2-piece mold blown bottle with a pontil mark (1840-1857) and an embossed panel bottle dating from 1867-1903 (Reher 1977). Additional dating information is provided by an 1838 copper cent, a large "Coronet" cent (1816-1834) and a copper half cent (1800-1808), as well as a stoneware bottle marked "J. B. Bryant, 1847". It is unclear what this date and name refer to, whether it is the bottler of the contents or a local tavern owner or private citizen. The terminus post quem is provided by the beginning date for the panel bottle.

Exterior Midden, East

This provenience grouping consists of artifacts from a rectangular shaped pit on the east side of the house. Because of the nature of the soil, this was originally thought to be a midden, hence the name. However, upon excavation and closer examination of the feature, it was determined to be the remains of an outbuilding or addition to the main structure. The label "Exterior Midden, East" was kept to avoid confusion. The Mean Ceramic Dates for the group are 1825.18 using South's types only and 1825.77 using the "General Pearlware" category. The Visually Interpreted Bracket Dates are 1780 and 1830. No other artifacts were recovered which would aid in the dating of this feature. The terminus post quem is provided by the beginning date for whiteware - 1820.

Ash and Brick Concentration

The ash and brick concentration was located in the northeast corner of the cellar and appears to be a refuse deposit placed in the cellar prior to the cellar filing. The Mean Ceramic Dates are 1831.87 for South's types and 1831.94 using "General Pearlware". The Visually Interpreted Bracket Dates are 1790 and 1830. Mold blown bottle fragments dating from 1810-1903 (Reher 1977) were recovered. Again, the terminus post quem is provided by the beginning date for whiteware - 1820.

Feature 8

Feature 8 consisted of a well adjacent to the house foundation. The Mean Ceramic Dates for this feature are 1817.83 using South's types and 1819.60 using "General Pearlware". The Visually Interpreted Bracket Dates are 1790 and 1820. A copper half cent which was minted from 1809 to 1836 was found in this feature; the exact date on the coin could not be determined. The terminus post quem is provided by the beginning date on South's whiteware type - 1820.

Feature 10

Feature 10 was interpreted as the remains of a small shed or outbuilding. The Mean Ceramic Dates for this feature are 1815.15 for South's types and 1815.96 using "General Pearlware". The Visually Interpreted Bracket Dates are 1780 and 1825. No other artifacts were found which would aid in the dating of this context.

Features 2 and 11

Feature 2 was a rectangular stain into which Feature 11, a circular stain, intruded. Neither Mean Ceramic Dates nor Visually Interpreted Bracket Dates could be calculated for Feature 2, as the sherd count was too small. The Mean Ceramic Date for Feature 11 is 1814.96; no "General Pearlware" was present. This date, although provided here as a point of comparison with the Visually Interpreted Bracket Dates, is also suspect because of a small sherd count. The Visually Interpreted Bracket dates are 1795 and 1830. No other datable artifacts were found for either feature.

Summary of Context Dating

In general, the Mean Ceramic Dates for the H. Grant Tenancy site fall within a very close range, ca. 1812-1819. The artifact assemblage suggests an occupation confined to the first half of the nineteenth century. Although a few examples of 18th century ceramics, such as delftware, were present as well as creamware, neither was particularly numerous. In addition, at the other end of the time range, the number of whiteware and ironstone sherds was relatively small compared to the total sherd count. Both the

glass and the ceramic artifacts indicate an occupation range beginning in the early part of the 19th century and ending by the Civil War. All of the contexts associated directly with the occupation such as Feature 8 (the well), the Cellar Floor Midden and the Builders Trench have terminus post quems which predate 1850. Most of the terminus post quems are 1820 because of the presence of whiteware. The Cellar Fill, which is interpreted as a deliberate filling-in of the structure foundation, has a terminus post quem of 1867, as does the 2Ap. The 2Ap had a Mean Ceramic Date of 1818.43 in addition to panel bottle fragments (1867-1903) and a button which could not date earlier than 1850. The presence of this plowzone seems to give a date prior to 1867, when the cellar could actually have been used.

The only two Mean Ceramic Dates which are later than 1819 are derived from the "Exterior Midden, East" (1825) and the Ash and Brick Concentration (1831). The later date for the "Exterior Midden" is not surprising since it appears to represent a later structural addition to the house and may be closer to the end of the occupation. The Ash and Brick Concentration was a much smaller sample.

In general, the Mean Ceramic Dates are somewhat earlier than anticipated. To a large extent, this is because of the overwhelming representation of pearlware in the assemblage. In theory, the Mean Ceramic Date represents the middle of the occupation and, in this case, would push the beginning of the occupation into the 18th century. This is unlikely based both on the small number of sherds which are 18th century types and the presence of mold blown glass from hinged molds which could not date earlier than 1810 (Reher 1977). The skewing due to the preponderance of pearlware in the assemblage is particularly evident in the Visually Interpreted Bracket Dates which, in theory, represent the range of occupation at the site. These tend to simply echo the beginning and ending dates for pearlware (i.e. undecorated pearlware is dated by South at 1780-1830). This does not fit with the other diagnostic artifacts such as the glass.

South's Function Analysis - Intrasite

Procedures for the examination of functional groups of artifacts have been developed for historic sites by Stanley South, using a system of increasingly generalized groupings of artifacts, following a model based on ceramics which proceeds from "type" through "ware" and "class" to "group" (South 1977:92-93). The assignments are based on South's perception of what is "useful" (South 1977:92) based on his experience mainly with Colonial Period sites. His analysis produced a range of distributions of the proportions of the various artifact groups that was sufficiently regular that he defined as the "Carolina Artifact Pattern". In general, 18th century domestic sites will approximate this pattern, based on a variety of subsequent studies. Other kinds of sites sometimes vary in regular ways

from this pattern, producing their own kinds of patterns such as the "Frontier Artifact Pattern" (South 1977).

At the Grant Tenancy site, South's functional analysis was used initially to compare the various provenience groupings with one another to determine if any intrasite functional differences were apparent. The results of the comparisons of the Grant Tenancy provenience groupings to South's Carolina Pattern are shown in Table 2. The comparisons to South's Carolina Pattern was done both on a straight percentage basis and also by using a statistical test to quantify any differences and/or similarities observed. This statistical test is the Robinson Coefficient of Agreement (Doran and Hodson 1975:139). The measure was calculated for each pairwise comparison between the groups. The expectation is that assemblages that result from the same kinds of functional activity sets will have similar percentages of functional artifacts groups and, therefore, higher values of the Coefficient. If two provenience groups have high values of the Robinson Coefficient it means that they are alike; that the same kinds of functional activities are represented in the two groups. Conversely, if the two groups have low values, it means that there are differences in the functional activities. The formula for the Coefficient is as follows:

$$SR_{ij} = 200 - \frac{n}{k=1} \frac{IP}{ik} - P \frac{I}{jk}$$

The results of the analysis and the comparison to South's Carolina Pattern are presented by provenience group below. A discussion of the significance of the results of the Robinson Coefficient is presented after the results.

Controlled Surface

The Controlled Surface provenience group showed a considerably higher percentage of South's Group 1 (kitchen) artifacts than observed for the Carolina Pattern, i.e. 83.09% as opposed to between 51.8-69.2% for the Carolina Pattern. There was a corresponding decrease in the Group 2 (architectural) artifacts for the Controlled Surface assemblage (10.95%) when compared to the Carolina Pattern (19.7-31.4%). The low values for the architectural group may be the result of the deliberate destruction of the structure and the hypothesized scavenging. The values for the furniture group, Group 3, from the controlled surface collection at Grant Tenancy (.19%) were within the range of the Carolina Pattern, .1-.6%. The arms group, Group 4, is also low (0.3%) in comparison to the Carolina Pattern (.1-1.2%). Plate 12 shows artifacts from the arms group and the prehistoric artifacts. Artifacts from Group 5 (clothing) were not within the Carolina Pattern scale (.6-5.1%), comprising .28% of the total. Plate 13 shows artifacts from the clothing group. Group 6, personal group, artifacts were .09% of the total assemblage, which is quite low in comparison to the Carolina Pattern (.1-.5%). Tobacco pipes, Group 7, represented 5.18% of the

TABLE 2

SOUTH'S FUNCTION GROUPS, INTRASITE

Provenience Group	South's Function Group							
	1	2	3	4	5	6	7	8
	Kitchen	Architecture	Furniture	Arms	Clothing	Personal	Tobacco Pipe	Activities
Carolina Pattern								
Mean	63.10%	25.5%	.20%	.50%	3.00%	.20%	5.80%	1.70%
Range	51.8-69.2	19.7-31.4	.1-.6	.1-1.2	.6-5.1	.1-.5	1.8-13.9	.9-2.7
Grant Tenancy								
Controlled Surface	83.09%	10.95%	.19%	.03%	.28%	.09%	5.18%	.19%
Plowzone	87.17%	10.40%	.14%	.03%	.29%	.09%	1.68%	.20%
Midden	83.55%	14.53%	0%	0%	.21%	.06%	1.60%	.05%
Ext. Midden E	66.04%	30.19%	0%	0%	.94%	0%	2.83%	0%
2Ap	53.58%	42.97%	.23%	.06%	.49%	.06%	2.03%	.58%
Cellar Fill	52.76%	43.04%	.33%	.02%	1.30%	.12%	1.82%	.63%
Cellar Midden	75.63%	23.53%	0%	0%	0%	.84%	0%	0%
Ash/Brick	75.58%	22.64%	0%	0%	1.35%	0%	.54%	1.89%
General Surface	81.88%	13.13%	.31%	0%	.63%	.31%	1.88%	1.88%
Builders Trench	60.39%	37.36%	0%	.28%	0%	0%	1.40%	.56%
Feature 1	64.71%	29.41%	0%	0%	0%	0%	5.88%	0%
Feature 2	88.89%	7.41%	0%	0%	0%	0%	3.70%	0%
Feature 2/83	75.68%	21.62%	0%	0%	2.70%	0%	0%	0%
Feature 6	87.50%	12.50%	0%	0%	0%	0%	0%	0%
Feature 7	80.00%	20.00%	0%	0%	0%	0%	0%	0%
Feature 8	89.11%	9.49%	0%	0%	.23%	.13%	1.01%	.13%
Feature 9	0%	0%	0%	0%	0%	0%	0%	0%
Feature 10	84.10%	13.33%	.51%	.51%	0%	0%	1.03%	.51%
Feature 11	76.60%	19.15%	0%	0%	0%	0%	4.26%	0%
Feature 12	57.69%	38.46%	0%	0%	0%	0%	0%	3.85%
Feature 14	100%	0%	0%	0%	0%	0%	0%	0%
Feature 15	100%	0%	0%	0%	0%	0%	0%	0%
Feature 16	58.33%	8.33%	0%	0%	0%	0%	33.33%	0%
Features 18, 19, 20, 22	26.67%	66.67%	0%	0%	0%	0%	6.67%	0%
Feature 21	50%	50%	0%	0%	0%	0%	0%	0%

PLATE 12

GUNFLINTS AND PREHISTORIC BIFACES




PLATE 13

BUTTONS





PLATE 14
TOBACCO PIPES



collection. This is in the middle range of the Carolina Pattern (1.8-13.9%). Plate 14 presents a sample of the pipes recovered. Group 8, the activities group, diverges quite a bit from the Carolina Pattern (.9-2.7%), representing .19% of the total assemblage. Plates 15-17 present examples of other artifacts recovered.

With respect to the Srij comparisons, the highest values, 191.80% and 191.92%, are achieved with the Plowzone and the Midden, respectively. The lowest comparisons were with the 2Ap over the foundation (134.62%) the Cellar fill (132.59%), and Feature 12 (137.66%).

Plowzone

Like the Controlled Surface Collection, the Plowzone also contained a high percentage of kitchen artifacts (87.17%) and a low percentage of architectural artifacts (10.40%) when compared to South's Carolina Pattern. The furniture group, although somewhat low (.14%), was within the Carolina Pattern range. The arms group percentage was identical to that of the controlled surface collection (.03%) and was correspondingly low in comparison to the Carolina Pattern. The clothing group consisted .29% of the total artifact assemblage. The personal group percentage was low (.09%) compared to the Carolina Pattern. Group 7, tobacco pipes was also low (1.68%) falling just outside South's range. As with the Controlled Surface Collection, the representation of artifacts from the activities group was low (.20%).

As could be expected, the highest Srij comparisons were with the Plowzone and the Midden with 191.80% and 191.74%, respectively. High comparisons were also received with Feature 8 (196.04%) and Feature 10 (191.81%). Like the Controlled Surface Collection, the lowest comparability was with the 2Ap over foundation (132.76%) and the Cellar Fill (131.14%). A low value was also achieved in comparison to Feature 12 (136.58%).

Midden

Like the previous two provenience groups, the Midden also showed a much higher percentage of kitchen artifacts (83.55%) than the Carolina pattern. Although higher than the other two groups, the percentage of architectural artifacts was correspondingly low (14.53%). Neither the furniture group nor the arms group were represented in this collection and all four of the remaining groups had low representations when compared to the Carolina Pattern. The percentages were as follows: clothing group .21%, personal group .06%, tobacco pipe group 1.60% and activities group .05%.

The highest Srij values were with the Controlled Surface Collection (191.92%), the Plowzone (191.74%), and Feature 10 (195.93%). The lowest were with 2Ap over foundation (140.06%), the Cellar Fill (138.41%), and Feature 12 (144.54%).

PLATE 15

PITCHER





PLATE 16
MISCELLANEOUS METAL ARTIFACTS



PLATE 17
COINS AND RELIGIOUS MEDAL



Exterior Midden, East

In contrast to the previous provenience groups, the kitchen group constituted a much lower percentage of the assemblage from the "Exterior Midden" (66.04%), with a corresponding increase in the architectural group (30.19%). These figures, although at the high end, fall within the ranges for the Carolina Pattern. The furniture, arms, personal and activities groups are not represented at all in this provenience group. This is probably a result of the small sample size (106 items). The representation for the clothing group is within the Carolina Pattern, constituting .94% of the total assemblage.

With respect to the Robinson Coefficient, the highest values were achieved with the Ash and Brick concentration (180.32%) and the Builder's Trench (183.97%). The lowest values were with Feature 2 (152.56%) and Feature 8 (153.34%).

2Ap Over Foundation

In general, the 2Ap over foundation provenience group was more representative of the Carolina Pattern. The kitchen group constituted 53.58% of the assemblage which is at the low end of South's range. The architectural group was 42.97%, which is high. The furniture group was .23%, close to South's mean for the group. The arms group was .06% which is low; the clothing group was .49% which is not within South's range; the personal group was .06% which is low; the tobacco pipe group was 2.03% which is at the low end of South's range and the activities group was .58% which, although low compared to the Carolina Pattern, is higher than the preceding provenience groups.

The highest Srij values were obtained for the Cellar Fill (197.85%), the Builder's Trench (185.93%) and Feature 12 (185.24%). It is not surprising that high pairwise comparisons would be obtained for the Cellar Fill and the Builder's Trench as the 2Ap zone lay directly over these groups. Proximity is probably the operating factor here. Low pairwise comparisons were obtained for Feature 2 (126.04%), Feature 8 (128.80%) and Feature 10 (100%).

Cellar Fill

As with the 2Ap over foundation, the Cellar Fill had a low representation of kitchen artifacts (52.76%) and a high percentage of architectural items (43.03%). Items from the furniture group comprised .33% of the total which is above the mean for South's Carolina Pattern. The arms group is .02%, the clothing group is 1.30%, the personal group is .12%, the tobacco group is 1.82% and the activities group is .63%. The clothing group, the personal group and the tobacco pipe group are within South's ranges for the Carolina Pattern. The arms group and the activities group are low.

The highest pairwise comparisons were with the 2Ap over foundation (197.85%), the Builder's Trench (184.20%) and Feature 12 (183.69%). The lowest values were obtained for Feature 2 (123.97%) and Feature 8 (127.27%).

Cellar Floor Midden

The Cellar Floor Midden contained a much higher percentage of kitchen artifacts (75.63%) than the Cellar Fill and a corresponding lower percentage of architectural (23.53%). Probably because of the small sample size, the furniture, arms, clothing, tobacco pipe and activities groups were not represented at all. The personal group was high (.84%) in comparison with South's Carolina Pattern.

The Cellar Floor Midden showed strong affinities with the Ash and Brick concentration (192.44%) and Feature 2/83 (194.50%). A rather strong correlation is also evident between the Cellar Floor Midden and the Midden (180.44%).

Ash and Brick Concentration

Kitchen group artifacts represent 73.58% of the assemblage from this provenience group and the architectural group represents 22.64%. Neither the furniture group nor the arms group are represented at all. The clothing group represents 1.35% which is within South's Carolina Pattern. The personal group is not represented. Tobacco pipes are .54% of the artifacts which is low. The activities group is 1.89% of the total, which is over South's mean, although in the range.

The Ash and Brick concentration had the highest pairwise comparisons with the Cellar Midden (192.44%) and Feature 2/83 (194.50%). All of the other pairwise comparisons were relatively high, 155% or greater.

General Surface

Artifacts from the kitchen group from the General Surface Collection represent an extremely high percentage (81.88%) of the assemblage. The architectural group artifacts are correspondingly low, comprising 13.13%. Items from the furniture group were .31% of the total which is within South's range and slightly higher than the mean. No artifacts from the arms group were found. The clothing group comprised .63% of the total, which is just within South's range. Personal items comprised .31%, tobacco pipes comprised 1.88% and activities comprised 1.88%, all of these are within South's Carolina Pattern.

Most of the pairwise comparisons were relatively high, with the Controlled Surface (190.90%), the Midden (193.84%) and Feature 10 (193.71%) being the highest. The lowest values were for the 2Ap over foundation (139.88%) and the Cellar Fill (138.77%).

Builders Trench

Kitchen artifacts from the Builder's Trench comprised 81.88% of the total with architectural items following at 13.13%. The furniture group the clothing group and the personal group are not represented in this collection. Items from the arms group comprise .28% of the total, which is within South's range for the Carolina Pattern. Tobacco pipes were 1.40% of the assemblage and activities group items were .56% of the total, both of which are outside South's range.

Features

Only two features contained sample sizes sufficient for comparative purposes, Feature 8 and Feature 10. Kitchen group items comprised 89.11% of the assemblage from Feature 8, while architectural items were 9.49% of the total. Neither the furniture group nor the arms group were represented. Items related to clothing comprised .13% of the total as did artifacts from the personal and activities groups. Only the personal group is within South's ranges for the Carolina Pattern. Tobacco pipes comprised 1.01% of the assemblage; this is below South's range. In Feature 10, items from the kitchen group constituted 84.10% of the total and architectural constituted 13.33%. Artifacts from the furniture, arms groups are within South's ranges while the activities group is below. The clothing and personal groups were not represented. The tobacco pipe group was also low, representing 1.03% of the total.

The highest pairwise values for Feature 8 were with the Plowzone (196.04%) and Feature 2 (194.62%). The lowest were the 2Ap over foundation group (128.80%) and the Cellar Fill group (127.27%). Feature 10 showed the greatest similarities with the Controlled Surface Collection (190.97%), the Plowzone (191.81%), the Midden (195.93%) and the General Surface Collection (193.71%). The lowest values were for the 2Ap over foundation and the Cellar Fill.

Summary of South's Functional Analysis - Intersite

In general, the Grant Tenancy site does not conform particularly closely to the Carolina Pattern. For the site as a whole, kitchen artifacts constitute 77.91% of the assemblage. South's range for this group is 51.8-69.2%, so this is high. On the other hand, at Grant Tenancy, the architectural items comprise 18.980% which is below South's range of 19.7-31.4%. The low representation of architectural items may be the result of scavenging. Furniture items represent .20% of the total at Grant. This is within South's range of .1-.6%, although at the low end. The arms group at Grant Tenancy is quite low, .03%, compared to the Carolina Pattern, .1-1.2%. The clothing (.45%), personal (.09%) and activities (2.9%) groups are under-represented as well. South's range for these groups is from .6-5.4% for clothing, .1-.5% for personal and .9-2.7% for

activities. The tobacco pipe group, although low (2.17%), is within South's range of from 1.8-13.9%.

The Robinson Coefficient of Agreement shows a remarkable consistency among the deposits with thirteen of the eighteen provenience groupings showing thirteen or more Srij values over 150%. The greatest number of high values were obtained for the Cellar Midden and Feature 2/83 which had all 17 values over 150%. It is not surprising that the cellar midden should have such a large number of high values if it is indeed a "living floor". It is however, surprising that Feature 2/83 should have so many high values if this is a deliberately filled in erosional gully. It may have been that the depression was not deliberately filled in at a single time but that the refuse/fill within the gully could have naturally accumulated over the period of occupation of the site. The Exterior Midden East and the Ash and Brick concentration had 16 values over 150%. The provenience groupings with the smallest number of high values were the 2Ap over foundation and the Cellar fill. They both had 8 values over 150% and 9 values under 150%. Feature 12 also had a relatively small number of high values with 9 over 150% and 8 under 150%. The small number of high values for the Cellar Fill may be related to the deliberate filling in of the foundation walls to facilitate cultivation at the site. If the cellar was deliberately filled in after the occupation of the site, then the deposition patterns may not be characteristic of the site as a whole. It is unclear why the 2Ap lying directly over the foundation should be so unrepresentative of the site as a whole if it is indeed a naturally developed soil horizon. It is probably because artifacts from the Cellar Fill horizon which are, in general, not characteristic of the site have been plowed up into the 2Ap.

The differences between the provenience groupings do not seem to relate to temporal factors as the Cellar Floor Midden which had the greatest number of high values as a Mean Ceramic Date of 1812.15 and the Exterior Midden East and the Ash and Brick concentration which had the second greatest number of high values have Mean Ceramic Dates of 1825.18 and 1831.87, respectively. The Cellar Fill has a Mean Ceramic Date of 1818.43 and the 2Ap has a Mean Ceramic Date of 1818.43.

Spatial Organization and Patterning

One of the major research questions to be addressed in this report and a major component of the Determination of Eligibility statement (see National Register Nomination, Appendix 1) was spatial patterning/organization at the Grant Tenancy site. In addition, the spatial plan realized at the Grant Tenancy site was to be compared to both tenancies and owner occupied sites in order to determine if a typical tenancy plan could be identified and if this plan can be identified solely by archeological data. The data retrieved from the Grant Tenancy site was compared to the Robert Ferguson site (Coleman et al, 1983), a tenant farm, the William Hawthorn site (Coleman et al, 1985), an owner

occupied dwelling and the Mudstone Branch site (Heite 1984), also owner occupied.

There are several ways to approach these questions. One way is to examine standing structures or the remains of structures at a site and determine their function, either by the architecture of a particular structure in the case of extant buildings or by an examination of the artifact assemblages associated with structural remains. At the Grant Tenancy site, although extensive excavations were conducted either by hand excavation or by machine stripping, intact structural remains were found for only one building, the main house. A suggestion, in the form of artifact concentrations and postmolds, of one additional structure (Feature 10) was also found. On the basis of its size, this additional structure appears to be an outbuilding or shed of unknown function.

Another way to investigate a spatial patterning at a site is to examine the types of artifacts found at different locations within a site in order to see if different functional areas may be delineated. At the Grant Tenancy site, this type of investigation was conducted at two levels. First, the distributions of bottle glass, coarse ceramics and refined ceramics were plotted for the controlled surface collection to determine if gross functional differences were present across the site (Figures 25-27). It was hoped that this might also provide an indication of the function of the outbuilding represented by Feature 10. In addition, all levels were combined for each excavation unit and the distributions of bottle glass, coarse wares and refined wares were plotted for the individual excavation units. The results of these distributions, on a percentage basis, are shown on Figures 28-30. As these figures indicate, there is little difference found across the site, whether they are associated directly with the structural remains of the main house or in some other area. The major concentrations of all three artifact classes are in the main structure, in the Midden (Feature 5) area and from N195E400 north to N230E400. The greatest concentration of artifacts within the main structure area is from those units which had levels containing the cellar fill. The other units in the main structure area only had levels containing the plowzone and the buried plowzone or the 2Ap horizon and, in some cases, lay directly over the foundation wall. As a consequence, the artifact numbers are reduced. The area north of N210E400 and containing N230E400 and N250E400 is an erosional gully or, possibly, an old road bed. N210 is located at the top of the slope, N230 is halfway down the slope and N250 is at the bottom of the slope. The amount of slope wash increased north of N230 and the greatest accumulation was in N250, where approximately 2 feet of silty slope wash overlay rocks and gravel. The greatest concentration of artifacts from the units around the erosional gully was in N230. If these artifacts were the result of slope wash, one would expect the greatest concentration to be located in N250 where there was the greatest concentration of soil. Therefore, it appears as if the concentration of artifacts in




FIGURE 25
Controlled Surface Collection
Distribution of Bottle Glass




FIGURE 26
Controlled Surface Collection
Distribution of Refined Ceramics




FIGURE 27
Controlled Surface Collection
Distribution of Coarse Ceramics

FIGURE 28
Distribution of Bottle Glass
Excavation Units




Figure 29

Percentages of Refined Ceramics
Excavation Units





Figure 30
Percentages of Coarse Ceramics
Excavation Units



N230 may be the result of refuse dumping in the area adjacent to and within the gully.

A third approach involved separation of the artifacts into South's (1977) function groups in order to determine if certain kinds of artifacts were found in certain areas in the hopes of delineating different functional activity areas. These were plotted for both the controlled surface collection and the excavation units. Both the surface collection and the excavation units show fewer artifacts of any functional class, immediately adjacent to the main house on the east and west sides. This tends to substantiate the hypothesis that the main house extended beyond the foundation walls in these directions, either in the form of an attached shed or a porch. In the surface collection distribution maps, there appears to be a concentration of at least kitchen debris north from the 150 line to the 190 line, from the E360 line to the E380 line (Figure 31). This suggests that an entrance to the main house may have been located on the western side and that refuse was discarded out this entrance. In general, the greatest concentrations of artifacts contained within any of South's function groups are in the main structure area and in the Midden/Feature 5 area. A similar pattern of functionally mixed refuse deposits was noted for the William Hawthorn where although artifact concentrations were observed in the rear and side yards, continuous occupation, from the mid-18th century to 1961 probably obscured the functional distribution of artifacts (Coleman et al 1984:156). At Grant, although functional differences are not apparent, this does not appear to relate to temporal factors as was seen at the William Hawthorn site because the occupation period was much shorter. Instead, at Grant, the horizontal extent of the spatial utilization appears compressed and it may be this compression which has obscured functional differences. In other words, the occupants of the Grant Tenancy site were using a much smaller area which caused a mixing of functional areas.

In addition, the architectural debris was separated into brick, window glass and nails and plotted on a percentage basis to determine if any differences existed in these artifact classes. These distributions are shown on Figures 32-34. As Figure 33 indicates, the percentages of window glass are relatively close through the site area. Although it is not marked, there does seem to be slightly higher percentages of brick around the main structure than in the midden area (Figure 32). The concentration of brick in N180E400 probably represents the remains of a chimney. In contrast, there seems to be somewhat higher percentages of nails in the midden area around Feature 10 (Figure 34). As noted, Feature 10 was hypothesized to represent the remains of an outbuilding and, based on the higher percentages of nails, it appears to have been frame.

In their research design for the Robert Ferguson site, Coleman et al (1983:24) hypothesized that the number and kinds of outbuildings present at a tenant farm should be representative of the day to day use of the occupants and not a reflective of




FIGURE 31
Controlled Surface Collection
South's Function Group 1

Figure 32
Percentage of Brick
Excavation Units




Figure 33
Percentage of Window Glass
Excavation Units





Figure 34
Percentage of Nails
Excavation Units



those kinds of subsidiary structures needed to operate a large farm. The excavations at the Robert Ferguson site yielded the remains of only two outbuildings, a chicken house and a barn (Coleman et al 1983:91) and the excavators suggest that a similar number of auxiliary structures may be characteristic of tenant farms. This is in contrast to a large owner occupied farms such as the Hawthorn site where a greater number of auxiliary structures were present (Coleman et al 1984:68). If the pattern of few outbuildings is characteristic of tenant farmers, then the Grant Tenancy site fits, as the remains of only one (or perhaps two) possible outbuildings were found, Feature 10 and possibly Feature 12. Feature 10, measuring 19.6 by 5.8 feet is not of sufficient size to have been a barn and appears to have been a small shed. It is difficult to ascertain the size of Feature 12, cannot be ascertained as it is, at best, the remains of an individual pillar footing and no additional footings were found. While no evidence of a barn was found at the Grant Tenancy site during these excavations, it is possible that a barn or additional outbuildings may have been located outside the impact zone in which the excavations took place. In any event, the number of outbuildings observed at the Grant Tenancy site based on the present evidence precludes interpretation of the site as a large working farm, although some evidence of on-site butchering of at least cows and pigs was present in the faunal assemblage.

Heite (1984) found that, at the Mudstone Branch site, although the exact placement of the outbuildings and refuse disposal areas may vary somewhat through time based on the position of the entrance road to the house, an attempt was always made to keep the front yard area (what Heite terms as the "ceremonial space") free of trash and/or outbuildings (Heite 1984). In addition, refuse disposal areas at this site tended to be on the eastern side of the building in relation to the ceremonial space (Heite 1984:71-72). Heite documented this shift through time by plotting the road positions in relation to the distribution of temporally diagnostic ceramic types. A shifting pattern of trash disposal and temporally confined concentrations of artifacts was also present at the Robert Ferguson site (Coleman et al 1983:81). At this site, the authors found whiteware farther from the house, in the east yard area near the kitchen door and earlier types, such as pearlware, were found closer to the house out the back door in the western section. At Grant, in contrast, although Lancaster Pike may have shifted from one side of the house to the other, the same temporally confined concentrations of artifacts were not observed. If as Heite (1984:14) postulates, houses generally tended to face the main transportation artery at the time of the house construction, the front of the structure at Grant would have faced north toward the erosional "gully/depression" which may be the oldest road bed. The road then appears to have shifted closer to its present location south of the structure, on the opposite side of the house. If refuse disposal patterns at the Grant Tenancy site were following Heite's pattern, one would expect that the artifacts from the concentration south of the structure to be earlier than the artifacts on the north side of the structure as

the occupants of the site attempted to maintain a "ceremonial space". This does not appear to be the case at Grant as an examination of the types of ceramics found north and south of the house show similar temporal ranges. Based on what was found at the Robert Ferguson and the Mudstone Branch sites, one would expect to find most, if not all, of the later ceramic types occurring at the site on the north side of the house and this is not the case. However, the occupations at both the Mudstone Branch and the Robert Ferguson sites were longer than what is hypothesized for Grant and the effect that this may have on the temporal concentration of ceramic types is not known.

In summary, the pattern of refuse disposal at the Grant Tenancy site does not conform closely to Heite's pattern at the Mudstone Branch site or to the patterns observed at the Robert Ferguson or William Hawthorn sites. Instead, it appears closer to the Brunswick pattern presented by South (1977:47) in which the occupants of site discarded refuse out entrance areas to the structure, regardless where the entrance was located. Since the entrance ways at Grant cannot be definitely ascertained, it cannot be stated that Grant follows the Brunswick pattern exactly but the pattern of refuse disposal appears to be similar. The fact that Grant is closest to the Brunswick pattern may be the result of its earlier, more temporally confined occupation. In addition, South states that in sites which follow the Brunswick pattern, nearby depressions were also used for trash disposal (1977:47). This appears to be true of Grant as well.

Econscale Analysis

In addition, ceramics from the site were coded according to Econscale Types. The Econscale Types are arbitrarily assigned numbers which are based on ware type and method of decoration. They are derived from Miller's (1980) work in which he developed a relative cost index scale for refined white earthenwares based on the cost differential between undecorated wares and wares decorated with different kinds of decoration. The refined white earthenwares consist of pearlware, whiteware and creamware. These ware types were combined for the economic status analysis following Miller (1980:15-18) who concluded that, based on historical sources, the manufacturers of what archeologists today would classify as different ware types, did not recognize these differences. Instead, they were defined by the manufacturers on the basis of their decoration. Because of this, Miller (1980:18) suggests that decoration and vessel form are more useful when examining economic status.

In order to use Miller's cost indices as he developed them, the number of different vessels forms by decorative types must first be calculated. Unfortunately, the size of the sherds and the size of the collection at the Grant Tenancy site precluded this type of categorization, therefore, the Econscale Types developed in connection with another project (Thompson 1985) were used in an attempt to determine the relative economic status of the occupants of the Grant Tenancy site. Each Econscale Type

represents a level of effort and cost on the part of the manufacturer; a cost which must be passed onto the consumer. It was felt that even though information concerning vessel form could not be obtained, the Econsale Types could be used as the more costly decorative types are always more expensive, regardless of vessel form. For the Grant Tenancy project, it was hoped that an examination of the decorative types within the refined white earthenwares and a comparison of the results of this examination with other sites would give some indication of Grant's economic status in relation to these other sites. For the site as a whole, the percentages break down as follows: Econsale Type 1 (porcelain) - 282 sherds, .97%; Econsale Type 4 (transfer printed refined white earthenwares) - 2178 sherds, 7.50%; Econsale Type 5 (hand painted refined white earthenwares) - 1553 sherds, 5.35%; Econsale Type 6 (minimally decorated refined white earthenwares) - 1,831 sherds, 6.31%; Econsale Type 7 (undecorated refined white earthenwares) - 11,245 sherds, 38.74%; Econsale Type 11 (yellowware) - 610 sherds, 2.10%; Econsale Type 12 (coarse stoneware) - 118 sherds, .41%; Econsale Type 13 (coarse earthenwares) - 9714, 33.47%; Econsale Type 21 (refined redware) - 31 sherds, .10%. Plates 18-21 show representative ceramics from the site.

As could be expected, undecorated refined white earthenwares made up the largest percentage (38.74%) of sherds at the site, followed closely by coarse earthenwares (33.47%). The low representation of stonewares at the site (.41%) is somewhat surprising, however, it is assumed that, based on the large representation of coarse earthenwares, that most of the utilitarian ceramics were of coarse earthenware. The reason for this is unknown. It may be that the coarse earthenware vessels were more easily obtainable or less expensive.

Faunal Analysis

Dr. David Clark, Catholic University, Zooarcheology Lab, conducted the faunal analysis for the Grant Tenancy site. His results and methodology are presented in some detail in Appendix III. In general, the faunal remains from the various provenience groupings were quite similar. Evidence for on-site rearing and butchering of domestic animals was present in the assemblage. Few of the skeletal elements found were sawed or cut and those saw marks present were indicative of hand sawing techniques. The cut marks were the result of axe blows. Both of these served to indicate on-site, non-commercial butchering (Appendix III, page 3). Evidence of symmetrically sawed meats indicating systematic butchering, primarily for specialty meats was not found. This systematic butchering is most common, according to Dr. Clark, after the mid-1800's with the development of more efficient butchering techniques (Appendix III, page 4).

Cow, pig and sheep constituted the bulk of the meat diet, with cow and pig being the most common. Wild species such as box turtle, rabbit, oyster and hard shell clam were also utilized as food resources (Appendix III, page 33). Refuse from the initial

PLATE 18
ECONSCALE TYPE 1: PORCELAIN




PLATE 19

ECONSCALE TYPE 4: TRANSFER PRINTED REFINED WHITE EARTHENWARES




PLATE 20

ECONSCALE TYPE 5: HAND PAINTED REFINED WHITE EARTHENWARES



PLATE 21

ECONSCALE TYPE 6: MINIMALLY DECORATED REFINED WHITE EARTHENWARES



butchering of the animal was much more common for cow and pig remains and a wide variety of skeletal parts were found. Sheep remains, on the other hand, were less diversified (Appendix III, page 34).

Better quality meat cuts were recorded for both the cow and sheep remains. The most common cow remains were shoulder, chuck, sirloin and roast meat cuts. The most common pig remains were Boston Butt and picnic shoulder as well as half hams. Sheep remains were represented by foreshank, rack of lamb, loin and hind leg of lamb (Appendix III, page 34).

Soils Analysis

Soil chemical analysis was conducted on selected samples from the Grant Tenancy site. Plowzone samples were taken from each of the excavation units and a sample was taken from each of the features, where this was possible. The samples were sent to the University of Delaware College of Agricultural Soil Laboratory which provided results for phosphorus (P), potassium (K), magnesium (Mg), calcium (Ca), manganese (Mn) and zinc (Zn). The tabular results of this analysis are contained within Appendix IV. Previous studies have shown that changes occur in the soil chemistry as a result of past human activity. It was hoped that the soil analysis would be helpful in interpreting some of the more ambiguous feature and to better define and interpret activity areas. While the soils analysis was not used in this instance to locate subsurface features prior to excavation, these results demonstrate the potential for such application.

In a test case study, Custer (et. al 1986) provides the results of soil chemical analysis at a 19th century farmstead/blacksmith complex in northern Delaware. Known activity areas were subjected to soil analysis to test previous assumptions archeologists have made concerning the relationship of soil chemistry to certain human activities. Custer (et. al 1986) found that not all of the chemical indices provided results that were expected. Calcium and magnesium levels showed little or no relationship to specific activity areas while phosphorus and potassium were high (as expected) in a machine shop/grist mill area but were not high (contrary to prediction) in an animal penning area. The authors conclude that certain activities will not always alter the soil chemistry in ways which can be detected, given current techniques (Custer et. al 1986:94).

At the Grant Tenancy site, the effects of artificial fertilizing for agricultural practices presented a few problems. The results obtained for calcium, magnesium, manganese and zinc were at the maximum values obtainable and therefore were useless for archeological interpretations. Phosphorus and potassium provided the most promising results for plowzone sampling and recorded levels for the two nearly mirrored each other (see Figure 35). The pH values (Figure 36) ranged from 5.4 to 6.7 or moderate to weakly acidic.

FIGURE 35
Soil Sample Location Map





FIGURE 36

PHOSPHOROUS AND POTASSIUM VALUES, PLOWZONE



The area to the east and southeast of the house foundation (Figure 2) contained a number of features whose function remains unclear. These include Features 2, 9, 10 and 11. While each varied considerably in size, all intruded into the subsoil by about .5 feet. The feature fill in all cases was very similar and consisted of a dark yellowish-brown silty loam and was slightly different from the overlying plowzone. In all cases, the feature fill contained a moderate amount of artifacts. Figure 37 presents the results for phosphorus and potassium and shows that the values for the four similar features are relatively close and fall slightly lower than the ranges for the same two chemicals for the plowzone in this vicinity. Aside from the interpretation presented earlier for Feature 10 as a small shed or structure, the function of the other features remains unresolved. As stated earlier, the soils chemical analysis ruled out a privy function for Feature 9.

The soil chemical analysis for the plowzone revealed that all but two chemicals were rendered useless for interpretation as their values were artificially high due to modern agricultural fertilization. Phosphorus and potassium, however, were useful in flagging the house structure in addition to marking rather dramatically the site and non-site areas.

The soil chemical data for a linear north/south sample transect are presented in Figure 38. This figure provides a visual representation of the FIV values for phosphorus and potassium for each sample location along the transect. The grid points are shown along the X-axis while the FIV values are shown on the Y-axis. The graph indicates three areas which had different value ranges for these two indices. Each of these areas correspond to different activity area as determined through excavations. The first area lies between grid points N120 and N160. This corresponds to the midden and out-building area. The values for phosphorus and potassium here average between 60 and 70 FIV and can be considered moderate in comparison with the other two areas. The second area lies between grid points N170 and N185 and represents the sample taken immediately over the house foundation. Here the values are significantly elevated with the exception of two low values for potassium.

The third area falls between grid points N185 and N250. This is essentially an off-site area consisting of a slope and gully. Grid point N190 roughly corresponds to the point where the slope begins to drop off towards the gully. Grid point 250 is located at the base of the slope. The values for the phosphorus and potassium were considerably lower than either of the other two areas. This is probably due to the fact that aside from being off the site and unaffected by cultural activities, this area was also on a greater slope.

The pH values for the same transect are shown on Figure 36. In comparison with the potassium and phosphorus values noted above, the results are reversed between the midden/outbuilding

FIGURE 37

pH Values, Plowzone





FIGURE 38

Phosphorous and Potassium Values,
Features



area and the house foundation area. The pH values for the former are elevated above those for the latter.

The slope/gully area exhibited very low values at the top of the slope which increased as the base of the gully is reached. This is probably due to greater erosion at the top of the slope with greater amount of slopewash accumulated towards the base of the slope.

While the results of the soil chemical analysis at the Grant Tenancy site did not dramatically alter nor add to the overall picture, they did demonstrate that positive results can be obtained for some chemical indices. In this case, phosphorus and potassium levels from the plowzone samples were shown to be markedly elevated in those parts of the site that contained high concentrations of artifacts and associated features. These elevated values were especially evident from the samples directly over the buried house foundation.

Prehistoric Component

A small prehistoric component was found at the Grant Tenancy site which was mixed with the historic period artifact concentration. No subsurface prehistoric features were encountered and all of the material was recovered from either the plowzone or within historic feature fill. The artifacts, from the Phase I/II and Phase III investigations included 34 flakes, 5 shatter fragments, and 9 bifaces. No diagnostic artifacts were included. The flakes and shatter material included 23 quartz, 3 chalcedony, 5 jasper and 8 chert pieces. The bifaces included 6 quartz, 1 jasper, 1 chert and 1 rhyolite specimens. None of the bifaces could be assigned to an established type because they were either heavily reworked or broken fragments. Three of the quartz bifaces were distal ends of points, two were heavily reworked notched points and 1 was a similarly reworked stemmed point (Plate 12). The jasper and the chert bifaces were broken unidentifiable fragments and the rhyolite bifaces was stemmed but also heavily reworked.

The prehistoric component at the Grant Tenancy site is similar to two sites reported nearby during the Phase I investigations (Barse 1985) and is interpreted as a small procurement site.

Comparisons With Other Sites

One of the major research problems to be addressed in this study was a determination of the economic status of the occupants of the Grant Tenancy site. One way of determining the economic status of the occupants of a particular site is to examine the discarded material possessions, particularly the ceramics. Ceramics are felt to be sensitive indicators of economic status because of well documented fluctuations in cost of either different ware types or different decorative techniques through time. There are several ways to approach this problem. One

developed by Miller (1980) and used by Klein and Garrow (1984) and others is to calculate minimum vessel counts and use documentary evidence such as price lists and catalogues to assign relative cost values to the vessel counts. Still others (Thompson 1985) feel that both ware type and decorative method may indicate socio-economic status. This is again based on the relative cost of various ware and decorative types to the consumer.


In an attempt to define the socio-economic status of the occupants of the Grant Tenancy site, the Econscale Type method developed by Thompson (1985) was used to group the ceramics into categories which represent relative cost levels. Using this method, Econscale Types from the Grant Tenancy site were statistically compared to the Econscale Types from other sites in the hope of determining its economic status in relation to these other sites. Initially, a number of different sites including those mentioned here and a number of different statistical methods were used to compare the percentages of Econscale Types at these sites. These include the Robinson Coefficient, Wise's Status Analysis, and the Tau statistic. In the interests of clarity and because the results from many of these methods were equivocal or clearly did not work, only the most promising results are reported here. The data and the results of the statistical measures not contained within this report are available to interested researchers at the Department of Transportation, Division of Highways.

The measures used in the analysis reported here included the Chi Square Test of Association which tests association between variables (in this case the decorative types on the refined white earthenwares) and z scores which measure deviation from the mean. The z scores were then summed in order to rank the sites used for this analysis in terms of their relative economic status. As mentioned previously, based on Miller's (1980) work, as the cost of different decorative methods on the refined white earthenwares was well documented and was felt to be the most sensitive indicator of economic status, only these ware types were used in the analysis. In order to determine the effects that time and geographic location may have on the results, the sites were examined first as a whole, then according to their geographic location and ten year temporal intervals.

Although very preliminary, the results indicate that the ways in which sites deviate from the population mean seems to provide the most useful indicators of relative economic status. These measures and the results are described in more detail later in the report.

The following presents a brief summary on the sites used for comparison. These sites were chosen either for convenience or because they represented sites with well documented socio-economic status. Additional information may be obtained from the primary sources. Figure 39 shows the location of these sites.

FIGURE 39
Map of Middle Atlantic
Showing Locations of Sites Used for
Comparison



Anthony Hotel/Riseing Son Tavern (7NC-E-65): Mean Ceramic Date - 1822. This is a village tavern site which is located in Stanton, Delaware in the Coastal Plain. The archeological investigations conducted here from which the data was derived consisted of data recovery work. See Thompson 1984 and 1987 for additional details.

Springdale: Mean Ceramic Date - 1810. This is a rural domestic site in Middletown, Virginia, in the Ridge and Valley province. Archeological investigations at this location consisted of limited testing. Although documentary research conducted on the site is not extensive, it was the dwelling of one of the more prominent settlers in the area and is assumed to be of relatively high economic status. No published reports are available, excavation notes and artifacts are on repository at Thunderbird Archeological Associates, Woodstock, Virginia.

44PM44 (PM-4III): Mean Ceramic Date - 1818. This is a rural domestic site near Portsmouth, Virginia, in the Coastal Plain. Phase I and II archeological investigations were conducted at this location. The socio-economic status is unknown. See Thunderbird Archeological Associates 1981 for additional details.

44PM34 (PM-II): Mean Ceramic Date - 1823. Also a rural domestic site near Portsmouth, Virginia, in the Coastal Plain. Phase I and II archeological investigations were conducted here. The site appears to represent a backyard area associated with structural remains. It is possible, although the documentation is unclear, that it may be a plantation house known as Manor Farm, however, 44PM24 may also be a candidate for the location of Manor Farm. See Thunderbird Archeological Associates 1981 for additional details.

Robert Ferguson: Range of Occupation - 1837-1940. This site is located in New Castle County, Delaware in the Coastal Plain. It is a well documented tenancy and is of low to middle economic status. Data recovery investigations were undertaken here. See Coleman et al 1983 for additional details.

44PM35 (PM-KI): Mean Ceramic Date - 1823.34. This is a rural domestic site located in Portsmouth, Virginia in the Coastal Plain. No documentary evidence regarding economic status was found. Preliminary and intensive archeological investigations were undertaken. See Thunderbird Archeological Associates 1981 for additional details.

44PM42 (PM-RI): Mean Ceramic Date - 1820.19. This site is a rural domestic site located in Portsmouth, Virginia in the Coastal Plain. The materials were derived from a trash pit containing unburned and burned household refuse. Preliminary and intensive investigations were conducted. Although no documentary evidence is available for the early 19th century, the site was a tenancy later in that century. This use may have begun earlier

and a low to mid socio-economic status use hypothesized. See Thunderbird Archeological Associates 1981 for additional details.

44PM16: Mean Ceramic Date - 1796.76. This is a rural domestic site in Portsmouth City, Virginia in the Coastal Plain. Archeological investigations consisted of Phase II intensive testing. Although originally thought to be a free black tenancy, this hypothesis was not confirmed by the Phase II testing. Socio-economic status is unknown. See Thunderbird Archeological Associates 1982 for additional details.

44CS48: Mean Ceramic Date - 1797.38. This rural domestic site is located in Chesapeake City, Virginia in the Coastal Plain. Phase II intensive testing was conducted at the site. This site was originally thought to be a slave dwelling, however, the testing revealed this not to be the case. Although the socio-economic status of the site through time is unclear, it is known that at least by 1846, the owner resided on the premises and an inventory of moveable goods indicates farming was his occupation (Thunderbird Archeological Associates 1982:49).

44PM22: Mean Ceramic Date - 1807.79. This is a rural domestic site located in Portsmouth City, Virginia in the Coastal Plain. Intensive archeological investigations were conducted here. The socio-economic status of the site is unknown although it was originally thought to have been occupied by free blacks and/or tenants. See Thunderbird Archeological Associates 1981 for additional details.

Belle Grove: Mean Ceramic Date - 1815.58. This is a rural domestic site located near Strasburg, Virginia in the Ridge and Valley. Archeological investigations by Thunderbird Research Corporation consisted of limited testing in specific impact areas. In terms of the socio-economic status, the site is a plantation house and would be expected to be of relatively high economic status. Excavation notes and artifacts are on repository at Thunderbird Archeological Associates, Woodstock, Virginia.

44PM24 (PM-LII): Mean Ceramic Date - 1826.61. This is a rural domestic site located in Portsmouth, Virginia in the Coastal Plain. The documentary evidence regarding economic status is unclear, it may either be a plantation house known as Manor farm or a dependency of that structure. Preliminary and intensive archeological work was conducted here. See Thunderbird Archeological Associates 1981 for additional details.

44PM31 (PM-DI): Mean Ceramic Date - 1827.83. This is a rural domestic site located in Portsmouth, Virginia in the Coastal Plain. Little documentary evidence is available for the site, however, it may be a dependency of a larger plantation and a low to mid economic status is projected. Preliminary and intensive investigations were undertaken. See Thunderbird Archeological Associates 1981 for additional information.

44PM12: Mean Ceramic Date - 1827.85. This is a rural domestic site located in Portsmouth, Virginia in the Coastal Plain. No documentary evidence is available for the economic status of the site, however dependencies of a primary structure located nearby would not be unexpected in this location (Thunderbird Archeological Associates 1981:95). Preliminary and intensive investigations were undertaken.

44PM17: Mean Ceramic Date - 1829.03. This is a rural domestic site located in Portsmouth, Virginia in the Coastal Plain. No documentary evidence was available regarding economic status although, according to the family oral history, the site was the location of a detached kitchen. However, this function cannot confidently be assigned to the site during the Antebellum period (Thunderbird Archeological Associates 1982:40). Preliminary and intensive archeological investigations were undertaken here. See Thunderbird Archeological Associates 1982 for additional details.

44PM36 (PM-LI): Mean Ceramic Date - 1832.05. This is a rural domestic site located in Portsmouth, Virginia in the Coastal Plain. No documentary evidence regarding economic status is available. For additional details, see Thunderbird Archeological Associates 1981.

Howard McHenry (18BA100): Mean Ceramic Date - 1848.17. This site is located in Baltimore County, Maryland. It is a well documented 19th century mill and tenancy. Intensive archeological investigations were conducted here. See Hurry and Kavanaugh (1983) for additional information.

William Hawthorn (7NC-E-44): Mean Ceramic Date - 1855. This is a rural domestic site located in New Castle County, Delaware. Documentary evidence clearly shows that this site was of high economic status as the occupants were in the upper 4-12% of the taxable local population (Coleman et al 1984:179). Data recovery excavations were conducted at this site. See Coleman et al (1984) for additional details.

The statistical measures chosen to examine the Econscale Types included the Chi Square Test of Association and z scores. Composite sums of the z scores were also calculated in order to provide a ranking of the sites based both on the degree to which and the direction in which they deviate from the mean. The sites within the sample were grouped in several different ways. First, all of the sites were analyzed as a group. Second, the sites were grouped according to their geographic location. This included: The Delaware sites, the Ridge and Valley of Virginia and the two Portsmouth groupings. Third, the sites were grouped according to their Mean Ceramic Date, in ten year intervals, for example 1795-1805, etc. The percentage of each decorative type on the refined white earthenwares was used rather than sherds count as the sample sizes from the sites differed widely. However, none of the sites had less than 100 sherds. Table 3 presents the percentages of the decorative types for all sites.

TABLE 3

PERCENTAGES OF DECORATIVE TYPES ON REFINED WHITE EARTHENWARES
ALL SITES

SITE	MCD	TP RWE	HP RWE	MD RWE	UND RWE*
MEAN		14.44	3.943	7.022	74.58
44PM16	1796.76	13.45	1.17	5.85	79.53
44CS48	1797.38	4.81	6.97	5.53	82.69
44PM22	1807.79	5.17	6.03	6.9	81.9
Springdale	1810.79	15.83	6.61	8.02	69.34
Grant Tenancy	1814.91	12.96	9.24	10.89	66.91
Belle Grove	1815.58	12.59	2.30	6.91	78.19
44PM44	1818.65	13.28	0	4.69	82.03
44PM42	1820.19	13.62	.66	7.31	78.41
Anthony Hotel	1822	16.5	4.4	8.7	70.3
44PM34	1823.27	5.45	1.82	7.88	84.85
44PM35	1823.34	16.91	0	3.68	79.41
44PM24	1826.61	86.22	2.43	1.62	9.73
44PM31	1827.83	14.68	.92	6.42	77.96
44PM12	1827.85	3.45	.86	1.72	93.97
44PM17	1829.03	9.68	2.42	4.03	83.87
44PM36	1832.05	9.12	.63	4.40	85.85
Robert Ferguson	1837	4.05	7.19	14.08	74.67
Howard McHenry	1845	3.18	8.14	18.83	69.85
William Hawthorn	1855	13.39	13.12	5.96	67.53

*MCD - Mean Ceramic Date

TP RWE - Transfer Printed Refined White Earthenware

HP RWE - Hand Painted Refined White Earthenware

MD RWE - Minimally Decorated Refined White Earthenware

UND RWE - Undecorated Refined White Earthenware

Chi Square Test of Association

The Chi Square Test of Association was used to determine if significant non-random differences, i.e. significant relationships, in the percentages of transfer printing, hand painting, minimally decorated and undecorated exist within the population of sites being examined. Our hypothesis was that the percentages of the decorative types are related to economic status and this association will hold true regardless of time and geographic location. That the differences between the percentages of the decorative types are related to cost differences in the purchasing power of individuals of varying economic status. It was decided to reject the null hypothesis, that there is no relationship, at the .001 level and the critical values were calculated on this basis. If the null hypothesis were true, then we would see differences in observed frequencies and the expected frequencies as large as those in our sample in less than 1 in every 1,000 replicated studies (Hopkins and Glass 1978:317).

The formula used to calculate the Chi Square Test of Association was:

$$c^2 = \sum \frac{nc}{100} \frac{(P-Pe)^2}{Pe}$$

with the value of c^2 increasing as the observed proportions between the groups being compared differ (Hopkins and Glass 1978:317).

Chi Square values were then calculated, grouping the sites as described previously. It was felt that the temporal and geographic groupings would eliminate these two factors as reasons for the observed differences between the groups. It was expected that if time or geographical location was the reason for the observed differences within our sample populations, then the null hypothesis would be valid because the values from the sites would be almost identical. The Portsmouth sites were separated into two groups as they were from slightly different geographic locations.

Looking at our sample population as a whole, a Chi Square value of 2450.2085 was achieved, with 54 degrees of freedom. The critical value for rejection of the null hypothesis would be somewhere between 76.2 (50 degrees of freedom) and 88.4 (60 degrees of freedom), therefore for this grouping, the null hypothesis would be rejected.

Separating the sites into ten year time slots, the following results are obtained. Two sites were included in the 1795/1805 grouping, 44PM16 and 44CS48. A Chi Square value of 20.2328 with 3 degrees of freedom and a critical value of 11.3 were obtained. Grant Tenancy, Springdale and 44PM22 were included in the

1805/1815 group. A Chi Square value of 23.0372 with 6 degrees of freedom and a critical value of 16.8 was achieved. The 1815/1825 group included Belle Grove, 44PM44, 44PM35, the Anthony Hotel and 44PM34. A Chi Square value of 59.9588 with 15 degrees of freedom and a critical value of 30.6 was obtained. The next group, 1825/1835 included 44PM24, 44PM31, 44PM12, 44PM17 and 44PM30. A Chi Square value of 638.0016 with 12 degrees of freedom and a critical value of 26.2 was attained. The final group, 1835/1855 obviously constitutes more than a 10 year time span. This was necessary to include the remaining sites in the sample, including Howard McHenry, Robert Ferguson and William Hawthorn. It was felt to be necessary that they be included in the sample as they have well documented socio-economic status. Any other grouping would exclude one of these sites. A Chi Square value of 294.4826 with 6 degrees of freedom and a critical value of 16.8 was obtained for these sites.

As mentioned previously, Chi Square values were also calculated for the site based on geographical location. The first grouping included all of the sites from Delaware - Grant Tenancy, the Anthony Hotel, Robert Ferguson, and William Hawthorn. A Chi Square value of 346.6599 with 9 degrees of freedom and a critical value of 21.7 was obtained for this group. The second grouping included the first group of Portsmouth sites - 44PM16, 44CS48, 44PM22 and 44PM17. A Chi Square value of 28.8435 with 9 degrees of freedom and a critical value of 21.7 was attained. The second group of sites from the Portsmouth area were studied during a different investigation and include 44PM44, 44PM42, 44PM34, 44PM35, 44PM24, 44PM31, 44PM12 and 44PM30. A Chi Square of 856.6395 with 21 degrees of freedom and a critical value of 38.9 was obtained for this group. The Virginia Ridge and Valley sites include Belle Grove and Springdale. A Chi Square of 15.5155 with 3 degrees of freedom and a critical value of 11.3 were calculated. Howard McHenry could not be included in a geographical grouping as no other sites from Maryland were present in the sample.

Since all of the Chi Squares exceeded the critical values, our hypothesis that there are significant differences between the sites examined in the decorative methods on the refined white earthenwares, was proved valid. The reverse is also true, that the null hypothesis - that no significant differences exist - was proved invalid. It should be cautioned, however, that the results of the Chi Square Test of Association only determine if significant, non-random differences exist in the population being studied. The test cannot determine the reason for the observed differences within the population, this is a matter for interpretation. Based on the results from the temporal and geographical groupings, the Chi Square values seem to indicate that temporal period and location are not the root of the observed differences. However, these results are very tentative and need to be more fully explored. We are hypothesizing based on Miller's (1980) work that the root of the observed differences is socio-economic status, however personal preference in decorative type and other randomly distributed variables cannot

be ruled out. It must also be observed that this only accounts for one grouping factor at a time (i.e. geography, alone; temporal period, alone), and does not take into account, or correct for interdependent variation within groupings.

Parametric Statistics

Statistical analyses based on assumptions of random sampling and normal distribution of variation are not uncommon in archeology, although these assumptions are seldom completely justified and often clearly contradicted. In spite of these vagaries, many parametric statistical analyses remain robust when used in archeological situations, and, having applied measures described above with less limiting assumptions, traditional mean-based analyses were applied to see if clear-cut patterning could be discovered in the data.

Z Scores and Z Score Ranking

Since graphing the Econscale Type values for each site seemed to indicate some patterning in relation to the mean, it was decided to use z scores to compare the observed percentages of an Econscale Type at the sites to the population mean percentage for that type. The expectation would be that sites of higher economic status would have above average quantities of transfer printed and hand painted refined white earthenwares (because of their higher cost) and smaller proportions of minimally decorated and undecorated (because of their lower cost). In other words, it was projected that sites would vary from the population mean percentage for each type in certain ways, depending upon their socio-economic status.

In addition, an attempt was made to use the sum of the z scores for all the decorative types to rank the sites according to their relative economic status within the study population. The results of this are described later in this section.

It should be emphasized again that the application of descriptive statistical techniques that depend upon assumptions of random sampling and normal distribution to data sets such as these is a highly speculative venture, and the results described here must be regarded as tentative and subject to adjustment or discard as the result of future research. The unusual defense of this procedure is to point out that, though the assumptions may be poorly met (or not at all), at some point when the numbers of measurements is sufficiently large, the "Law of Large Numbers" (Crou 1969:211-212) will dictate that the different measured variations in the values will approach a normal distribution. Whether or not this would be true in the case of this particular category of measurements, and whether the data used to produce this analysis is sufficiently "representative" (if not random), remains to be seen. There seemed to be no harm in the attempt however, provided that the results were regarded with sufficient caution.

As mentioned previously, z scores measure deviation from the population mean. Table 4 presents the z scores by decorative type for each of the sites in the study population. The formula used is:

$$z = \frac{X - m}{Sx}$$

where X is the sample mean, m is the population mean and S is the standard deviation (Hopkins and Glass 1978:221). This measure allows the comparison of distributions of measurements with different ranges, reducing each measurement to a common scale -- the standard deviation. When a normal distribution is assumed, the proportion of cases above or below the observed value is calculated based on the area of the normal curve to the left (or right) of the given z-score (Hopkins and Glass 1978: 401-405). 46.81% of the population of sites analyzed here fall below Grant Tenancy in observed frequencies for the transfer printed refined white earthenwares (assuming the values are normally distributed), 92.05% of the population fall below for the hand painted refined white earthenwares, 83.40% of the population falls below for the minimally decorated refined white earthenwares and 32.28% falls below for the undecorated refined white earthenwares. The Robert Ferguson site, a known tenancy of lower economic status has the following percentiles: 27.70% of the population falls below the site for transfer printed, 81.33% for hand painted, 96.08% for the minimally decorated and 50% for the undecorated. The Howard McHenry site, also a known tenancy, compares in the following manner: 26.11% of the population falls below this site for the transfer printed wares, 87.49% for the hand painted wares, 99.84 falls below for the minimally decorated wares and 38.97% for the undecorated wares. At the William Hawthorn site, a site of known high economic status, 47.61% of the population falls below or transfer printed, 99.41% for hand painted, 39.36% for minimally decorated and 33.72% for the undecorated.

Based on the z scores, the two known tenancies exhibit very similar types of variation from the mean with close scores for transfer printed, hand painted and minimally decorated. As could be expected, the William Hawthorn site has higher scores for transfer printed and hand painted and lower scores for minimally decorated and undecorated. Grant Tenancy's z scores are much more similar to those from William Hawthorn for transfer printed, hand painted and undecorated except that Grant Tenancy has a higher value for minimally decorated. Based on this, if in fact Grant is a tenancy as the documentary evidence suggest, it is certainly not one of lower socio-economic class.

Because it was felt that a single Econscale Type or variable could not provide an adequate indication of economic status, a method was devised using the combined totals of the z scores to provide a single value which could then be used to rank the sites in terms of their relative economic status. It was hoped that

TABLE 4

Z SCORES AND PERCENTAGE OF POPULATION BELOW
DECORATIVE TYPES ON REFINED WHITE EARTHENWARES

SITE	TP	% below	HP	% below	MD	% below	UN*	% below
44PM16	-.06	47.61	-.76	22.36	-.29	38.59	.30	61.79
44CS48	-.55	29.12	.83	79.67	-.37	35.57	.48	31.56
44PM22	-.53	28.81	.62	73.24	-.03	48.80	.44	67.00
Springdale	.08	53.19	.73	76.73	.25	59.87	-.31	37.83
Grant	-.08	46.81	1.45	92.65	.97	83.40	-.46	32.28
Belle Grove	-.14	55.57	-.45	32.64	-.03	48.80	.22	58.71
44PM44	-.07	47.21	-1.08	14.01	-.58	28.10	.44	33.00
44PM42	.05	48.01	-.90	18.41	.07	52.79	.23	59.10
A. Hotel	.12	54.78	.13	55.17	.42	66.28	-.26	39.74
44PM34	-.51	30.50	-.58	28.10	.22	58.71	.61	72.91
44PM35	.14	55.57	-1.08	14.01	-.84	20.05	.29	61.41
44PM24	4.09	99.99	-.42	66.28	-1.35	8.85	-3.9	.007
44PM31	.01	49.60	-.83	20.33	-.15	44.04	.20	57.93
44PM12	-.63	26.43	-.85	19.77	-1.33	9.18	1.16	12.30
44PM17	-.27	39.36	-.42	33.72	-.75	22.66	.55	70.88
44PM36	-.30	38.21	-.91	18.14	-.66	25.46	.67	74.86
R. Ferguson	-.59	27.76	.89	81.33	1.76	96.08	.005	50.00
H. McHenry	-.64	26.11	1.15	87.49	2.95	99.84	-.28	38.97
W. Hawthorn	-.06	47.61	2.52	99.41	-.27	39.36	-.42	33.72

*TP - Transfer Printed
 HP - Hand Painted
 MD - Minimally Decorated
 UN - Undecorated

this would eliminate some of the problems in using indices which rely too heavily on one or at most, two, variables. For this analysis, the z scores were combined in very specific ways. The transfer printed and hand painted refined white earthenwares are both higher cost items and a negative z score indicates a value below the mean for that decorative type at a particular site. Conversely, a positive z score indicates a value above the mean. Therefore, the negative z scores for the higher valued types, transfer-printed and hand painted, from each site were added together to obtain an algebraic sum. For the lower cost items such as minimally decorated and undecorated, a positive z score indicates a value above the mean, or proportionally more lower cost items and a negative z score indicates a value below the mean and proportionally fewer lower cost items. Based on this, the algebraic sum of the z scores for these types were subtracted from the sum obtained for the higher valued types, in effect reversing the signs of those scores. In this way, a single value accounting for all of the variables could be obtained. The computational formula for this measure is:

$$Z \text{ sum} = (TP_z + HP_z) - (MD_z + UD_z)$$

where "TP_z" is the z score for the transfer printed refined white earthenwares at a particular site, "HP_z" the z score for hand painted refined white earthenwares, "MD_z", minimally decorated, and "UD_z", undecorated. Percentile groupings (area below in a normal curve) were also calculated for the decorative types at each site. The results are shown in Table 5.

Although extremely preliminary in nature, the results seem to indicate that this measure has some utility. However, the following cautions must be made. This measure has only been used with a limited number of sites, not all of which have well documented socio-economic status, and the method is based on the assumption that certain directions of deviation from the mean in percentages of decorative types on refined white earthenwares are normally distributed and are an indicator of economic status.

Howard McHenry, a known tenancy of low economic status, had the lowest value, 0-2.16. According to this measure, only 1.54% of the population in a normal distribution would have values lower than those observed at the Howard McHenry site. Robert Ferguson, another known tenancy of low economic status, had a value of 0-1.48. This means that 6.94% of the population in a normal distribution would have achieved lower scores than Robert Ferguson. The median score .78 was attained by Belle Grove. This means that only 21.77% of the population in a normal distribution would have achieved lower scores than Belle Grove. This is somewhat puzzling as Belle Grove would have been expected to be of higher economic status since it was a large plantation complex. However, only the results from a limited testing program which was confined to specific impact areas were used and this may have skewed the results somewhat. The deposits from which the samples were drawn may not have been associated with the plantation house itself but with a dependency, possibly a

TABLE 5

ALGEBRAIC SUM OF Z SCORES FOR PERCENTAGES OF
REFINED WHITE EARTHENWARES, AND KNOWN SOCIO-ECONOMIC STATUS

SITE	Z SUM	% BELOW	KNOWN STATUS	DATE
Howard McHenry	-2.16	1.54	Low to Middle	1845
44PM34	-1.92	2.74	Unknown, one of two locations for Manor Farm	1823.27
Robert Ferguson	-1.48	6.94	Low to Middle	1837
44PM12	-1.31	9.51	Unknown	1827.85
44PM42	-1.25	10.56	May be tenancy Low to Middle (?)	1820.19
44PM36	-1.22	11.12	Unknown	1832.05
44PM44	-1.01	15.62	Unknown	1818.65
44PM31	- .87	19.22	May be dependency Low to Middle (?)	1827.83
44PM16	- .83	20.33	Unknown	1796.76
Belle Grove	- .78 (MEDIAN)	21.77	Middle to High	1815.58
44PM17	- .49	31.21	Unknown	1829.03
44PM35	- .39	34.83	Unknown	1823.34
44PM22	- .32	37.45	Unknown	1807.75
Rising Son Tav.	.09	53.59	Unknown	1822
44CS48	.17	56.75	Unknown	1797.38
Grant Tenancy	.86	80.51	Tenancy, originally thought to be low to middle	1814.91
Springdale	.87	80.78	High	1810.79
William Hawthorn	3.15	99.93	High	1855
44PM24	8.89	99.99	Unknown, one of two locations for Manor Farm	1826.61

slave or servants quarters. The Anthony Hotel achieved a score of .09 which puts 46.41% of the population in a normal distribution below this site. Grant Tenancy achieved quite a high value using this measure. With a score of .86, 80.51% of the population in a normal distribution would have had a lower score. Springdale, projected to be of high economic status, obtained a similar score, .87, with 19.22 of the population falling below. The William Hawthorn site had a score of 3.15 which means that over 99% of the population in a normal distribution would have a lower score. This fits well with the documentary evidence as the site is known to be in the upper percentiles of the tax records. 44PM24 achieved the highest score, 8.89. According to this, 99.99% of the population would have a higher score. It is difficult to say if this attribution is correct as none of the Portsmouth sites had been extensively researched, however, 44PM24 is one of two possible locations for a residence known as Manor Farm. If the results of the combined z scores are correct, 44PM24, appears to be the more likely candidate, as 44PM34, the other candidate, achieved a relatively low score.

Based on the results described above, the Grant Tenancy site appears to have been inhabited by individuals of relatively higher economic status than most of the sites examined. Because the archival records which were examined presented information about the owners of the property, rather than the occupants of the site, it is difficult to say if this attribution of status is correct. Although tenancies are usually thought to be of lower economic status, the fact that an individual does not own his residence does not necessarily preclude a higher economic status (Klein & Garrow 1964).

SUMMARY AND CONCLUSIONS

This report has presented the results of data recovery excavations at an archeological site known as the Grant Tenancy site. Documentary evidence during the Phase II investigation had revealed the presence of a structure in this location on an historic map. The name, H. Grant, associated with the house was also associated with other structures in the area and evidence was available which suggested that H. Grant lived elsewhere. Therefore, the site was interpreted to be the remains of a tenancy. Since tenancies were poorly known archeologically, the site was determined to be eligible to the National Register of Historic Places. A considerable amount of documentary research was devoted to an attempt to answer the question of who lived at the site, and what their occupation and position in the community was. This effort was complicated by the fact that during the nineteenth century the excavated site was located at or near the corners of several different pieces of property with different histories. The relatively imprecise nature of nineteenth century property surveys coupled with the fact that some of the principal landmarks, i.e. the Lancaster Pike, had changed location one or more times during and since the period made it impossible to conclude with certainty which property the site was associated

with when it was occupied prior to the map indication of its association with the plantation belonging to Henry Grant in 1860. It seems likely the structure did not represent the principal residence of a property owner as the archival research showed most of the owners lived elsewhere. Thus the assumption that the site was occupied by a renter appears to be confirmed, if only by negative evidence.

The excavations at the site revealed a foundation with the remains of a well and subsidiary structure. Several discrete deposits were located within the foundation including a cellar fill which was assumed to result from the demolition of the structure, a refuse deposit containing ash, brick and artifacts and a cellar floor midden. Based on the volume of stone necessary for a stone house, it appears as if the house was originally constructed of something other than stone or that the stone from the house had been scavenged.

In addition to the historic component at the site, a small prehistoric component was present as well. This was interpreted as a procurement site.

Chemical analysis of selected soil samples at the site revealed the amount of phosphorus and potassium within the soil can be a particularly useful diagnostic tool in determining the presence of either subsurface features or of a structure. At the Grant Tenancy site, both phosphorus and potassium levels in plowzone soil samples were elevated in those parts of the site that contained high concentrations of artifacts and associated features. The levels were especially high from the plowzone samples over the buried house foundation.

The ceramics from the site primarily consisted of pearlware with various decorative methods including transfer printing, hand painting, shell edge and finger painting. Of the decorated pearlware sherds, transfer printing was the most common. Lesser amounts of whiteware and creamware were found. Glass artifacts were relatively sparse and tended to be undiagnostic. Most of the glass artifacts which did contain diagnostic attributes were either from pressed glass pieces or from mold blown pieces. Most of the identifiable nail fragments were cut, although some wrought specimens were present. Other metal artifacts found included coins, can fragments and various miscellaneous hardware and tool fragments. Mean Ceramic Dates of 1814.91 using South's types only and 1816.37 using the "General Pearlware" category were obtained for the site.

The Grant Tenancy site does not conform very closely to South's Carolina Pattern with very large percentages of kitchen items and corresponding low percentages of the other functional classes. Only the furniture and the tobacco pipe groups were within South's ranges.

When the percentages for South's function groups obtained for the Grant Tenancy site are compared to the William Hawthorn

site and the Robert Ferguson tenancy, the following results are obtained. Like William Hawthorn, the Grant Tenancy site contained a high number of kitchen group artifacts with percentages of 62.45% and 77.91% respectively. Coleman et al (1984:170) feel that the high percentage of kitchen items at the Hawthorn site and in South's Carolina Pattern are indicative of the length of occupation at these sites, with both of these sites having origins in the 18th century and extending into at least the mid 19th century. Occupation at the Ferguson site, on the other site, did not begin until 1837 (Coleman et al 1984:176). Although some 18th century materials were present at Grant, they were not particularly numerous and later ceramic types such as whiteware and ironstone were in the minority. Based on this, Grant does not seem to have sustained the length of occupation that the Hawthorn site did. The preponderance of kitchen items at Grant is therefore somewhat puzzling. Grant Tenancy had less architecturally related artifacts than either of the other two sites with a percentage of 18.90%. Robert Ferguson had 45.64% and William Hawthorn had 32.60%. Coleman et al (1984:176) attribute the higher percentage of architectural items at the Robert Ferguson to the site's 19th century origins and the rise in metal and construction materials that would accompany such a site. The low frequency of architectural materials at Grant Tenancy site may be the result of scavenging or it may be the result of its earlier origins. The furniture group percentage (.20%) at Grant is between the two values obtained for the other two sites. Robert Ferguson had a value of .33% and William Hawthorn had a value of .05%. The arms group at Grant was much lower than either Robert Ferguson or William Hawthorn. Grant had .03%, Robert Ferguson had .34% and William Hawthorn had .12%. Grant had a much higher percentage of clothing group items than either of the other two sites, 145%. Both Robert Ferguson and William Hawthorn had values of .19%. No personal group items were found at the Robert Ferguson site. Grant Tenancy had a value of .09% and William Hawthorn had a value of .05%. Grant Tenancy had extremely different values than both the other sites for the tobacco pipe and activities groups. Grant had a value of .29% for activities and 2.17% for tobacco pipes. Robert Ferguson had a value of 2.85% for the activities group and .63% for the tobacco pipe group. William Hawthorn had a value of 4.42% for the activities group and .12% for the tobacco pipe group.

As can be seen from the above, Grant Tenancy is not particularly close, in terms of South's function groups, to either the Robert Ferguson site, a known tenancy, or the William Hawthorn site, one of known high economic status.

Analysis of the faunal remains undertaken at the Robert Ferguson tenancy and the William Hawthorn site indicated cattle (*Bos taurus*), sheep (*Ovis aries*) and pig (*Sus scrofa*) as the major components of animal protein in the diet. A large number of teeth, head and foot elements were found, indicating at-home butchering and rearing of these animals (Coleman et al 1984:180). There was a noticeable lack of butchering or saw marks on the

remains which the authors attribute to the preparation of wholesale meat cuts for marketing (Coleman et al 1984:180). In addition, no evidence of wild food utilization was found, which is attributed to the "settled nature of New Castle County, even in the late 18th century" (Coleman et al 1984:180). High quality meat cuts were absent from both sites and it appears as if the occupants of both sites were consuming inferior cuts such as those used for stews and soups (Coleman et al 1984:180). Coleman et al feel that the higher quality meat cuts resulting from the on-site butchering provided a saleable surplus while the lower quality cuts were consumed by the occupants of the sites. They conclude that, based on the pattern observed at both William Hawthorn and Robert Ferguson, "food consumption habits may not vary with socio-economic status" (Coleman et al 1984:180).

Similar butchering patterns were observed at the Grant Tenancy site; no symmetrically sawed portions indicating systematic butchering was found. However, according to Dr. David Clark (Appendix III), this may be a reflection of the time period during which the site was occupied as evidence of symmetrically sawed butchering techniques is most common after the mid 1800's (Appendix III).

Like the other sites, cow, pig and sheep remains constituted the major domestic food resources at Grant Tenancy. Chicken was also found. However, in contrast to the other sites, Grant Tenancy indicated utilization of wild food sources as well. Rabbit, box turtle, oyster and hard shell clam remains were found. The reason for this difference is unclear. Coleman et al (1984:180) feel that the absence of wild food resources is related to the settled nature of the area as early as the 18th century. Since evidence of wild resource utilization was found at Grant Tenancy which is in a similar rural setting in the same area, this seems unlikely at least in the immediately local setting. The species represented in the Grant assemblage are present even in the more heavily urbanized modern area today. Perhaps the difference is the result of individual food preferences by the occupants of the sites or, at the William Hawthorn site at least, the contexts from which the faunal remains had been taken were disturbed.

Also in contrast to the William Hawthorn and the Robert Ferguson sites, evidence of high quality meat cut consumption was found at the Grant Tenancy site. Although not definitive, this lends credence to the assertion that the site was occupied by individuals of somewhat higher economic status than was originally anticipated.

At the beginning of the 19th century, changing economic conditions and patterns of agricultural production resulted in the consolidation of land tenure into the hands of fewer individuals in northern Delaware. Because the owners of the lands had business interests and frequently lived in the urban centers, it was necessary to maintain a system of tenancy in order to facilitate agricultural production. The Grant Tenancy

site was originally felt to be such a tenancy and the work at the site was designed to allow a more precise documentation of the social and economic status of the occupants of the site. Although somewhat inconclusive, current evidence indicates that the site was not owner occupied and it appears to have been a tenancy. Based on Clark's faunal analysis, at least some degree of agricultural production is evident in the form of animal rearing and butchering, however, it is difficult to say if this was solely for household use or for market.

An examination of spatial patterning and organization at the H. Grant Tenancy site indicates that, in addition to the main structure, the remains of at least one, perhaps two, service buildings were present. A similar pattern of a low number of auxiliary structures was observed at the Robert Ferguson site (Coleman et al 1983:91), a known tenant farm. If a low number of subsidiary structures is characteristic of tenant farms, it would only be representative of those tenant farms at which the tenants were living adjacent to or in close proximity to the main farm, or at those in which the tenants had access to agricultural facilities at a larger farm. It would not be the expected pattern at tenant properties which were leased as working farms. In this case, one would expect a greater number of service buildings. In any event, based on the results of the present excavations, the Grant Tenancy site does not appear to have a sufficient number of service buildings to have been a working farm. However, it is possible that the subsidiary structures were located farther away from the main house, outside the impact zone for this project.

Refuse disposal patterns at the Grant Tenancy site were also examined and compared to other sites in order to determine how closely they conformed. In general, the refuse disposal patterns at the Grant Tenancy site were closer to the Brunswick pattern observed by South (1977) in which refuse was present around all entranceways, than those observed at either the Mudstone Branch (Heite 1984) or the Robert Ferguson site (Coleman et al 1983), at which attempts were made to keep the front yard area clear of refuse. No evidence for temporal or functional separation of refuse deposits was found.

As previously stated, one of the research goals was a documentation of the economic status of the occupants of the Grant Tenancy site. In this research, the economic status was measured by examining the decorative methods on the refined white earthenwares. Based on Miller's (1980) work, this attribute was hypothesized to be an indication of economic status because of the cost differences between these decorative methods.

One way of examining the decorative methods in order to determine economic status is to sum deviation from the mean or z scores for these decorative methods. This gives a single, normalized score by which relative economic status may be attributed. It is, in effect, a ranking method because the

scores are obtained by pooling the data from a group of sites and determining the position of particular sites within the pool, in relation to the others.

Using this method, the Grant Tenancy site appears to be of relatively high economic status. This is supported to some extent by the results of the faunal analysis which indicated the consumption of high quality meat cuts. This does not necessarily contradict the tenant status of the site as there are at least two schools of thought regarding the level of economic status among tenancies. Klein and Garrow (1984:80) feel that the relationship between tenancy and socio-economic status is not clear-cut. They feel that middle and even high status individuals often rented property and that tenancy alone is not a reliable indicator of economic status (Klein and Garrow 1984:80). Coleman et al, on the other hand, feel that tenancies are often lower economic status individuals (Coleman et al 1983:24) at least compared to individuals living in the main house on the same property. The work at Grant Tenancy seems to support Klein & Garrow's contention.

Therefore, based on the results obtained during this research, the Grant Tenancy site appears to have been occupied by individuals of higher economic status than most of the other sites examined in this study. In the absence of documentary evidence and vessel form analysis for cost index values, deviation from the mean in terms of the frequencies of certain kinds of decoration on refined white earthenwares seems to be the most fruitful method tested in this study of obtaining some idea of the economic status of a particular site. However, this method needs to be tested more extensively before it can be determined useful.

At their most basic, the statistical methods used in this study simply demonstrate that ceramic assemblages vary in a significant non-random manner for reasons that have yet to be determined. We have hypothesized that socio-economic status is the reason for this variance. However, other factors exist which cannot be discounted. These include personal preference, relative availability of ceramics at sites, i.e. the distribution of available decorative types based on the proximity of the site to a major trade route or port, and urban vs. rural site position.

REFERENCES CITED

- Barse, William P.
 1985 Phase I and II Archeological Investigation of the Route 141-Centre Road Corridor in New Castle County, Delaware. Delaware Department of Transportation Archeology Series No. 35. Dover, DE
- Beidleman, D. Katharine, T. E. Davison, R. Napoli, R. Wheeler and P. Weiss
 1983 Creating a Data Base: The City's Test Square. In Approaches to Preserving a City's Past. City of Alexandria, Virginia.
- Bidwell, Percy and John I. Falconer
 1941 History of Agriculture in the Northern United States, 1620-1860. New York: Peter Smith.
- Catts, Wade P. and Ellis C. Coleman
 1986 Local Historical Summary. In Current Research in the Historic Archaeology of Northern Delaware. Edited by Jay F. Custer and Kevin Cunningham. Bulletin of the Archaeological Society of Delaware, Number 21.
- Chou, Ya-lun
 1969 Statistical Analysis. Holt, Rinehart and Winston.
- Coleman, Ellis C., Kevin W. Cunningham, David C. Bachman, Wade P. Catts, and Jay F. Custer
 1983 Final Archeological Investigations at the Robert Ferguson/Weber Homestead, Ogletown, New Castle County, Delaware. Delaware Department of Transportation Archeology Series No. 16. Dover, DE.
- Coleman, Ellis C., Kevin W. Cunningham, Jim O'Connor, Wade P. Catts, and Jay F. Custer
 1984 Phase III Data Recovery Excavations of the William M. Hawthorn Site 7NC-E-46, New Churchman's Road, Christiana, New Castle County, Delaware. Delaware Department of Transportation Archeology Series No. 26. Dover, DE.
- Custer, Jay F.
 1980 Archeological Research in Delaware, Fiscal Year 1980. Delaware Division of Historical and Cultural Affairs, Dover.
 1983 Delaware Prehistoric Archeology: An Ecological Approach. University of Delaware Press, Newark.
- Custer, J. F., Ellis Coleman, Wade P. Catts, and Kevin Cunningham
 1986 Soil Chemistry and Historical Archeological Site Activity Areas: A Test Case From Northern Delaware. Historical Archaeology Volume 20.

- Doran, J. E. and F. R. Hodson,
1975 **Mathematics and Computers in Archaeology.** Harvard Press, Cambridge, Massachusetts.
- Fletcher, S. W.
1950 **Pennsylvania Agriculture and County Life 1640-1840.** Pennsylvania Historical and Museum Commission, Harrisburg.
- Goddard, Ives
1978 **Delaware.** In **Handbook of North American Indians**, W.C. Sturtevant, ed. Northeast is: 213-239. Smithsonian Institution, Washington, D.C.
- Heilbroner, Robert L.
1977 **The Economic Transformation of America.** Harcourt Brace Jovanovich, Inc., New York.
- Heite, Louise B.
1984 **Archaeology Investigations of the Mudstone Branch Site, Dover, Kent County, DE.** Delaware Department of Transportation Archeology Series 26. Dover, De.
- Hopkins, Kenneth D. and Gene V. Glass
1978 **Basis Statistics for the Behavioral Sciences.** Prentice-Hall, Inc., Englewood Cliffs, New Jersey.
- Hurry, Silas and Maureen Kavanagh
1983 **Intensive Archeological Investigations at the Howard-McHenry Site, A Nineteenth Century Mill/Tenancy.** Maryland Geological Survey, Division of Archeology File Report No. 182, Baltimore
- Klein, Terry and Patrick H. Garrow (Editors)
1984 **Final Archeological Investigations at the Wilmington Boulevard Monroe Street to King Street, Wilmington, New Castle County, Delaware.** Delaware Department of Transportation Archeology Series No. 29. Dover, DE.
- Lindstrom, Diane
1978 **Economic Development in the Philadelphia Region, 1810-1850.** New York: Colombia University Press.
- Miller, George L.
1980 **Classification and Economic Scaling of 19th Century Ceramics.** *Historical Archaeology* 14:1-41.
- New England Publishing Company
1972 **The Complete Checklist of Button Makers (1710-1976).**

- Otto, John Solomon
 1976 Status Differences and the Archaeological Record - A Comparison of Planter, Overseer and Slave sites from Canon's Point Plantation (1794-1861), St. Simon's Island, Georgia. Ph.D. Dissertation, University of Florida (1975). University Microfilms, Ann Arbor, Michigan.
- Reher, Charles A. (Editor)
 1977 Settlement and Subsistence Along the Lower Chaco River: The C.G.P. Survey. University of New Mexico Press, Albuquerque.
- South, Stanley
 1972 "Appendix IV - Statistical Data - Minus Chinese Porcelain." In The Conference on Historic Site Archaeology Papers (1971), Volume 6, Parts 1 and 2, edited by Stanley South.
- 1977 Method and Theory in Historic Archaeology. Academic Press, New York.
- Thomas, David H.
 1976 Figuring Anthropology. Holt, Rinehart and Winston, New York.
- Thompson, Timothy A.
 1984 Phase I and II Archeological Investigations of the Stanton Intersection, Stanton, New Castle County, Delaware. Delaware Department of Transportation Archeology Series No. 32. Dover, DE.
- 1985 Economic Status in Nineteenth Century Bridgeboro. Thunderbird Archeological Associates. Report prepared for the New Jersey Department of Transportation, Trenton.
- 1987 Data Recovery Excavations at the Rising Son Tavern, Rt. 7 - Limestone Road, Stanton, New Castle County, Delaware. Delaware Department of Transportation Archeology Series No. 51. Dover, DE.
- Thunderbird Archeological Associates, Inc.
 1981 An Intensive Archeological Reconnaissance of a Proposed Coal Transshipment Facility Site, Portsmouth, Virginia. Report Prepared for EnviroSphere Company, Lynhurst, New Jersey.
- 1982 An Evaluation of Nine Archeological Sites in Portsmouth City and Chesapeake City, Virginia. Report prepared for EnviroSphere Company, Lynhurst, New Jersey.
- Weslager, C. A.
 1961 Dutch Explorers, Traders and Settlers in the Delaware Valley. Philadelphia.

PERSONNEL

William M. Gardner, Principal Investigator

BA in Psychology, University of Florida at Gainesville,
Ph.D. in Anthropology, University of Illinois. Presently
Professor in Anthropology Department, The Catholic
University of America, Washington, D.C. and President,
Thunderbird Archeological Associates. Over 17 years of
experience in Middle Atlantic Archeology.

Timothy A. Thompson, Archivist

BA in Anthropology, University of Florida at Gainesville,
MA in Anthropology, The Catholic University of America.
Presently Staff Archeologist and Archivist, Thunderbird
Archeological Associates. Over 10 years of experience in
Middle Atlantic Archeology.

Randolph K. Taylor, Field Director

BA in Anthropology, University of Virginia, MA candidate,
The Catholic University of America. Presently Staff
Archeologist, Envirosphere, Inc. Over 5 years of
experience in Middle Atlantic Archeology.

Snyder, Kimberly A.

BA and MA in Anthropology, The Catholic University of
America. Presently Contracts Manager, Thunderbird
Archeological Associates. Over 10 years of experience in
Middle Atlantic Archeology.

Field Crew: Debra Desarmeaux, David Weinberg, Pamela
Stephenson, Pamella Carmichael, Melanie Meyers, Carol
Medlar and Steven Hunt. Ms. Carmichael also provided
services as field draftsman.

Lab Crew: Mary Folsom Barse.

Faunal Analysis: Dr. David Clark of the Zooarcheology Research
Facility, Department of Anthropology, The Catholic
University of America. He was assisted by Randolph
Taylor, Elizabeth Giarrantana and Bernadette Monacelli.

Soils Analysis: The Soils Laboratory, College of Agriculture,
The University of Delaware.

APPENDIX I

National Register of Historic Places
Inventory-Nomination Form
for the
H. Grant Tenancy Site
7NC-B-6

United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places
Inventory—Nomination Form

received

date entered

See instructions in How to Complete National Register Forms
Type all entries—complete applicable sections

1. Name

historic Tenancy Site, H. Grant Property (7NC-B-6)

and/or common Aletta Laird Downs Property

2. Location

street & number Located in NW quadrant of intersection of Rte. 48
Lancaster Pike, and Rt. 141, Centre Road ☒ not for publicationcity, town Wilmington ☒ vicinity of

state Delaware code 10 county New Castle code 002

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input type="checkbox"/> private residence
<input checked="" type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input checked="" type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
		<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property

name Mrs. Aletta Laird Downs

street & number Rte. 48 Lancaster Pike & 141 Centre Road

city, town Wilmington ☒ vicinity of state Delaware

5. Location of Legal Description

courthouse, registry of deeds, etc. Register of Deeds
New Castle County Courthouse

street & number City-County Building

city, town Wilmington state Delaware

6. Representation in Existing Surveys

William P. Barse
title 1984 Phase I & II Archeological has this property been determined eligible? ☒ yes ☐ no
Investigations of the Rt. 141 Corridor, New Castle County, DE. Delaware Department of Transportation Archeology Series 33, Dover, DE. ☐ federal ☒ state ☐ county ☐ local
March 1985 140

depository for survey records Del. Department of Transportation

city, town Dover state DE

7. Description

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved date <u>ca. 1843</u>
<input type="checkbox"/> fair	<input checked="" type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

The H. Grant tenancy site was identified as the result of a reconnaissance survey, and additional data was gathered during an intensive survey of this location. This assessment was carried out for the Delaware Department of Transportation to fulfill their obligations under Section 106 of the National Historic Preservation Act to evaluate the effects of the proposed improvements to Delaware Route 141 on significant or potentially significant cultural resources, as defined by the National Register of Historic Places (36 CFR 1202). The site is located just to the north of the Lancaster Pike (Delaware Route 48) on the east side of Little Mill Creek and west of Route 141 (Figs. 1&2, Plate 1)

The significant component of the site is a nineteenth century occupation which appears to be a tenancy associated with the larger plantation complex identified on maps and in deed research as belonging to W. Tatnall, Henry Grant, John Peoples, and others. A pre-historic component, consisting of a chipping scatter is also present, but is not regarded as significant.

The site is located adjacent to an intermittent spring run which forms the northern boundary of the site, at the edge of the rather steep-sided valley of Little Mill Creek. The boundaries of the site were determined by the limits of artifact scatter observed in the test units on the east and west, and by the limits of construction disturbance for the present alignment of Lancaster Pike on the south.

It is not entirely clear where the exact position of the 19th century alignment of the Lancaster Pike is, but it is presumed to be beneath the present paved alignment (or destroyed by the construction of the present alignment). Other than highway improvements, the land use of the surrounding area is in substantially the same condition as during the site occupation: agriculture. The site is presently in pasture, and the thickness of the root mat suggests that it has been so for some time. However, a plow zone is present throughout the site, suggesting that the site area was cultivated after it ceased to function as a domestic residence.

Eleven 50 cm. shovel tests were distributed across the site area during reconnaissance survey to identify the limits of the artifact scatter and to evaluate the likelihood for sub-plow-zone features. Some of the latter, including a segment of structure foundation, (Square F) were identified in the placement of five foot by five foot test squares during the site testing program. A number of post-molds were identified suggesting the presence of support features and spatial distribution data. The variety of functional classes included in the artifact inventory support the attribution of this site as a residential site, and the integrity of the sub-plow-zone features suggests that significant data are present. The fact that the site has been plowed represents only a minor limitation in the data base, since the ability of plowed historic sites to retain spatial patterning of artifact distributions is clearly established by field research (Plates 2,3, & 4).

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input checked="" type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates	Builder/Architect

Statement of Significance (in one paragraph)

The H. Grant Tenancy Site (7NC-B-6) is significant because it is likely to contribute data important in the understanding of the history of this area and the surrounding region. Test excavations revealed that artifact distribution data are present in the plow zone, and that remains of structures and other facilities are present undisturbed below the plow zone. This will allow the characterization of spatial patterning for this common but uninvestigated site type. The following discussion provides a context within which to evaluate the research values of the site.

Delaware was settled by the Dutch in 1630, with the establishment of a whaling station near Lewes. This was soon destroyed by the Indians. The Swedes settled in the vicinity of Wilmington with the establishment of Fort Christina in 1638. This was captured by the Dutch in 1651. Settlement was characterized by scattered farmsteads along the major drainages, the Delaware River, White Clay Creek and Christina Creek (Weslager 1961).

The English obtained control of Delaware in 1664, which was followed by the granting of proprietary rights to William Penn in 1682. This placed Delaware under control of Philadelphia, both economically and politically. Although subsistence farming continued, commercial centers were beginning to be established to channel goods to Philadelphia. Such centers were Christina, Stanton and Ogletown. Throughout the 18th century, the increasing population stimulated the development of new towns and the development of more effective communication networks. This was especially apparent after the development of the towns of Baltimore and Annapolis.

The 19th century saw the development of canals and railroads to accommodate the commercial trade between these towns. The Philadelphia, Wilmington, and Baltimore Railroad was begun in 1839. However, the road system of Delaware lagged considerably behind the railroads as a means of transportation. Settlement in the 19th century was characterized by the large plantations and associated small tenant farms, as well as with the urban areas associated with the commercial towns.

A gradual change in the role of the farm occurred from the 18th through to the 19th centuries. During the 18th century, farming was primarily oriented to the production of goods for subsistence, a pattern that changed gradually to one involving production of goods for consumption on the growing national market. This change ties in with the growing industrial and urban centers in the Philadelphia-Wilmington-Baltimore corridor that was under way in the early 19th century noted above. While this scenario is known on a large scale, how the changing economic framework of the area affected the local household in terms of the organization of material culture is unknown, and accessible only archeologically. One would expect to witness a changing access to goods and the development of differing patterns of consumption based on economic status, as well as a growing diversity in patterns of land usage. Questions concerning what percentage of the population remained on a subsistence level as opposed to those engaged in production for market consumption are unknown, and would be most accessible through archeological investigations.

Deed research revealed that this location was consistently part of a sizeable plantation, and map research indicates that the principal residence of the owners is in the

United States Department of the Interior
National Park Service

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Continuation sheet

Item number 8

Page 2

location presently occupied by the owner, facing Centre Road (Rt. 141). A structure does appear at the tenancy site on one of the several maps that cover the area and show dwellings, the Eckel Map of 1860. The variety and distribution of the artifacts, as well as the subsurface features, suggest that this site was a domestic site, and since the principal residence on the property is already accounted for, a tenancy is implied.

A number of specific research questions can be addressed using the data present at 7NC-B-6:

1. Does the spatial organization of the structures and other facilities conform to a "typical" plan, as identified by other research (Heite 1984).
2. Does the realized plan resemble that common to owner-occupant sites, which can be documented to some degree from extant structures at such sites, or does it reflect a plan peculiar to the tenant situation, and retrievable largely from archaeological data? (The plan at this site can be identified as conforming or variant; comparison to other research at other tenant sites will be needed to confirm a specific pattern, i.e. Thomas 1983).
3. To what degree does the artifact assemblage express the lower economic status of a tenant, in comparison to owner-occupied sites? Are those patterns in the artifact assemblages, specifically in the distribution of cost-sensitive decorative attributes on whiteware, peculiar to tenants and distinguishable from other socio-economic groups?

Data developed at the H. Grant tenancy can establish base-line evaluations of patterns for this type of site to be compared with future research at other tenant houses and owner occupied site. Current research by DeDOT in downtown Wilmington can be used for comparisons between rural tenants and urban dwellers. In summary, testing has demonstrated that data are present in usable contexts at the H. Grant Tenancy Site to address a number of pertinent research questions current in historical archaeology.

9. Major Bibliographical References

Heite, Louise B. 1984 Archaeological Investigations at the Mudstone Branch Site, Saulsbury Road, Dover, Kent County, Delaware. Delaware Department of Transportation, Division of Highways, Location and Environmental Studies Office, Dover.

South, Stanley 1977 Method and Theory in Historical Archaeology. Academic Press, New York.

Thomas, Ronald A. 1983 Archaeological Data Recovery at an Eighteenth Century Farmstead in Lewes, Sussex County, Delaware. Mid-Atlantic Archaeological Research, Inc., Newark, Delaware.

Verlanger, C.A. 1961 Dutch Explorers, Traders and Settlers in the Delaware Valley. Philadelphia: Eckel, Henry 1860 Map of Wilmington and Brandywine R.

10. Geographical Data

Acreage of nominated property approximately 1/3 acre

Quadrangle name Wilmington North, Del.-PA

Quadrangle scale 1:24,000

UTM References

A

1	8
---	---

4	4	8	0	4	0
---	---	---	---	---	---

4	4	0	1	0	2	0
---	---	---	---	---	---	---

Zone Easting

Northing

B

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

Zone

Easting

Northing

C

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification The boundaries and corners of the site are shown on the attached drawing. The UTM position of corner A was measured from the center of the highway bridge across Little Mill Creek on the Wilmington North Quadrangle Sheet (see attached map) and is accurate to plus or minus twenty meters. The UTM coordinates for the remaining corners were then measured on the DelDOT plan at a scale of one inch (continued on attachment)

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title William P. Barse

organization Thunderbird Archeological Associates date 2/23/84

street & number Rte. 1, Box 1375 telephone 703-635-3860

city or town Front Royal state VA 22630

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

 national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature

title

date

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

144

Attest:

date

Chief of Registration

United States Department of the Interior
National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only
received
date entered

Continuation sheet

Item number 10

Page 2


equals twenty-five feet, but are really only as accurate as corner A. The attached drawing also shows grid points for the Delaware State Plane Coordinate System, from the DelDOT plan. The southern boundary ("A" to "E") of the site follows the northern right-of-way margin of the present alignment of the Lancaster Pike. It is expected that there would be road construction disturbance to the south of that line. The eastern boundary of the site ("E" to "D") marks the position where artifacts had fallen to near zero in the test pits. From corner "D", through "C", to "B", the northern boundary of the site follows the lowest points in the drainage swale, which forms a logical natural boundary. It is possible that some remains associated with the site might be located north of this boundary, but artifacts were falling off in this direction, and anything north of the swale would be outside the impact zone, as presently defined. The western boundary of the site ("B" to "A") is at a break point in the slope. From this line to the west, the ground slopes rather steeply toward the channel of Little Mill Creek, and it is projected that this area would not have been occupied.

FIGURE 1


TENANCY SITE NATIONAL REGISTER NOMINATION

UTM-18.448040.4401020
WILMINGTON NORTH U.S.G.S. QUAD.

KEY MAP



NEW CASTLE COUNTY,
DELAWARE




0.5 0 0.5 1.0
SCALE IN MILES

1 0 1
SCALE IN KILOMETERS

FIGURE 2

TENANCY SITE NATIONAL REGISTER NOMINATION



NOTE:

TEST SQUARES ARE LABELED
BY CAPITAL LETTERS.
S.T.=SHOVEL TEST



APPENDIX II

Artifact Inventory

Total Artifact Counts

	Phase I/II	Phase III	TOTAL
CERAMICS			
redware	565	11422	11987
whiteware	341	3484	3825
stoneware	3	100	103
porcelain	6	330	336
creamware	82	1454	1536
yellowware	34	627	661
pearlware	673	12926	13599
other	0	591	591
CERAMIC TOTAL	1704	30934	32638
GLASS			
bottle (colored)	33	1197	1230
bottle (clear)	6	881	887
tableware	5	29	34
storage	25	0	25
milk glass	0	3	3
miscellaneous	64	155	219
GLASS TOTAL	133	2265	2398
lamp chimney	0	0	0
window glass	454	6748	7202
METAL			
staple	0	3	3
wrought nail	14	46	60
cut nail	54	3456	3510
wire nail	2	0	2
roofing nail	0	0	0
architecture	0	19	19
furniture	0	6	6
household	4	917	921
miscellaneous	9	129	138
tool	0	4	4
arms	0	3	3
screws	0	25	25
wire	0	0	0
sheet	0	3	3
unidentified	1	281	282
nail fragment	17	249	266
METAL TOTAL	101	5141	5242

OTHER			
button/bead	2	130	132
miscellaneous	376	40996	41372
plastic	0	5	5
marbles	0	2	2
pipes	44	772	816
brick	213	16737	16950
oyster/clam	20	12	32
OTHER TOTAL	655	58654	59309

GT Prehist TOT

Prehistoric Artifact Count

	Phase I/II	Phase III	Total
QUARTZ			
flake	12	8	20
chunk	1	0	1
shatter fragment	2	0	2
biface, distal	0	3	3
notched biface	0	2	2
stemmed biface	0	1	1
CHALCEDONY			
flake	1	2	3
JASPER			
flake	1	4	5
biface fragment	0	1	1
CHERT			
flake	0	6	6
spall	0	2	2
biface fragment	0	1	1
RHYOLITE			
stemmed biface fragment	0	1	1
TOTAL ARTIFACTS	17	31	48

APPENDIX III

Faunal Analysis of the H. Grant Tenancy Site

By

Dr. David Clark
Zooarcheology Research Facility
Department of Anthropology
The Catholic University of America

The faunal analysis at the Grant Tenancy site was done on the basis of the following groups which correspond to the provenience groupings in the remainder of the report.

Group A - Contolled Surface

Group B - Plowzone

Group C - Midden

Group D - 2Ap Over Foundation

Group E - Cellar Fill

Group F - Cellar Floor Midden

Group G - Exterior Midden, East

Group H - Ash and Brick Concentration

Group I - Builder's Trench

Group J - Miscellaneous Uncontrolled Proveniences

Grant Tenancy

The faunal assemblage from the Grant Tenancy Site consisted of 2354 specimens, of which 2140 were bones and 214 were shell fragments. This material was analyzed by designated provenience "Groups" and "Features" and they are listed in Table 1 by number of specimens per species. Groups were analyzed as single units but all the features were analyzed as one unit due to their small size -six of nine assemblages yielded less than 10 bones (Table 1).

In this report, the Group assemblages are presented, followed by the Features. First, a general discussion is presented for each provenience, then, a detailed discussion of each species. Finally, an overview discussion/conclusion section is presented. The discussion sections refer to data tables and figures at the end of the report, where applicable.

METHODS

The assemblage had been previously washed and placed in clear, plastic, bags with the appropriate provenience data.

The material was initially sorted into identifiable and unidentifiable fragments. The identifiable fragments were then grouped by species and element, where possible. Simultaneously, each specimen was studied, in detail, to identify pertinent data such as saw or cut marks, evidence of scavenging, age and sex data, physical condition, and meat portions. In turn, the identification and provenience data were recorded on small labels and stapled in the corner of each plastic bag. The clear bag allowed the artifacts and analytical data to be viewed without opening the bag. After each assemblage was analyzed in this way, the data from each bag label was recorded on standard data sheets and then tabulated. Consequently, a final report was prepared and generally included the major text, data tables, figures and illustrations and photographs, where applicable.

Identification of the faunal materials was aided by the use of a skeleton comparative collection of modern animals housed in the archeology laboratory, Department of Anthropology, Catholic University.

Also, a collection of commercially sawed bone sections, etc., from modern "supermarket meats" as well as an extensive assemblage of bone elements from modern farm butcherings (Clark 1985) was used to classify and describe symmetrically cut and sawed bone elements from the assemblages. In many

cases, concentrations of symmetrically sawed bone elements of large domestic species were more common after the 1850s in historic faunal assemblages, I have studied, from the Middle Atlantic region. This is certainly linked to the development of more efficient commercial butchering techniques.

Maturation data used for computing "age at death", was recorded where possible. However, since the assemblage was highly fragmented and usable joint ends and teeth were often broken and deteriorated, maturation data was scarce. Also, for the preceeding reasons, measurements on the bones were impossible in most cases and thus, sex and age data were minimal.

TERMINOLOGY

A number of terms used in the text refer to skeletal elements and technology and are explained in this section. Most of these are references to species discussions and the data Tables 2-20.

Although scientific names are used in the text and on charts, the common names for all animals are used in the discussions sections. Consequently, the reader becomes familiar with the taxonomic names along with the common names.

The tables include the genus or class group names for animals such as Bos = cow or Aves = birds. They are listed horizontally. The rest of the faunal data is listed vertically, such as skeletal elements, number of specimens (elements, fragments), maturation data, etc. (Tables 2-20). The tables include a listing for provenience (Prov.) and modifications (Mod = Cut and Sawed) vs. totals.

Unidentifiable bones are grouped in categories. They include large mammals (Lg. mam.) referring to pig and cow sized animals; medium mammals = fox sized animals; small mammals = mouse to squirrel sized animals.

Cut and sawed bones are common in the assemblage, especially sawed elements. Cut or axed vertebrae are often identified as "split". That is, during the initial butchering of the animal, a common technique is to split the vertebrae column (backbone) down the middle from top to bottom. This process separates the carcass in two equal halves. The result is that the vertebrae are, also, split in two and are commonly found in the refuse faunal assemblage.

Sawed bones are a common occurrence in the assemblage. Frequently, sawed specimens exhibit a high degree of symmetry as far as sawing technology is concerned. In many assemblages, sawed elements are very common and reference is often made to symmetrically sawed bone which refers to systematic butchering technology on a professional or commercial level. A good example of this level of technology

is the abundance of symmetrically sawed sections representing "specialty" meat portions. Sawed bone sections consist of thick or thin, cross-cut sections usually from the shafts of legbones (femur, tibia, humerus), ribs, and innominates (pelvis). Examples of these sections are illustrated in Figures 4 and 5. This type of sawing represents systematic butchering of entire animals such as cows, sheep and, especially, pigs. For assemblages I have analyzed from sites in the Middle Atlantic region, this type of technology is more common after the mid-1800's.

Limitations of Research

This assemblage represents many smaller assemblages of material. Unfortunately, small assemblages yield less information, in general. Also, most of the assemblages were in very fragmented condition which decreases the identification of species and thus decreases the amount of information recoverable.

Other problems focus on the interpretation of the faunal remains, specifically. With smaller samples, there is always a limited variety of skeletal elements represented in the assemblages. Furthermore, historic faunal assemblages are frequently but not always represented by food refuse in the form of individual meat portions. Rarely, especially in urban contexts, does an assemblage contain the complete remains of butchered animals which is more characteristic of assemblages from more rural contexts like farmsteads, plantations, etc. Thus, an important consideration is the number, distribution, and type of meat portions represented in an assemblage especially since most of the faunal remains represent food refuse.

Burnt and incinerated bone specimens were exceedingly rare in all the assemblages. This suggests that meats were often prepared by methods other than exposure to direct heat or the bone was removed and discarded prior to cooking. Such methods included pickling (salting), smoking, and cooking in liquid (boiling, stewing, etc.).

Acknowledgement

With great appreciation I would like to thank Randy Taylor for assistance with processing all the faunal remains, Elizabeth Giarratana for her support and faithful devotion in preparing the Tables, etc., and Bernadette Monacelli for preparation of the manuscript and her constant encouragement.

Group A

The group A faunal remains were from surface collections. The material consisted of 91 bone fragments (Table 1) and was in poor physical condition. Most specimens were cracked and split with deep fissures running into the bone. The surface of many fragments was peeled off in layers which limited the identification of the elements. The entire assemblage was very fragmented which diminished the overall analytical interpretations.

Unidentifiable large mammal remains accounted for 46% (42) of the total (91). Cow and pig remains were very common but consisted, mostly, of teeth.

Bos taurus (Cow)

Cow remains included mostly teeth and hindleg fragments (Table 2). The teeth were probably refuse from initial butchering since they are not associated with meaty areas of the body. One sawed femur (upper hindleg) shaft was from a round roast and a tibia (lower hindleg) fragment represented a hind-shank cut (Figure 1).

Sus scrofa (Pig)

Pig bones (14) were mostly teeth from both the upper and lower jaws. This material is probably refuse from initial butchering. One shoulder (scapula) fragment was identified and represented a "Boston Butt" roast (Figure 2).

Ovis aries (Sheep)

Sheep remains included a single tibia (lower hindleg) fragment and was from a shank half "leg of lamb" (Figure 3).

Terrapene carolina (Eastern Box Turtle)

One plastron (lower shell) fragment was identified as box turtle which is a very common terrestrial species adapted to moist meadow, field and forest fringe environments. Box turtles were a common food resource.

Callinectes sapidus (Blue Crab)

Four fragments were identified as blue crab (Table 2) and included claws and shell fragments. The blue crab ranges from low-salinity of the tidal-freshwater zones to the full salinity of open ocean. Blue crabs are a very popular food resource, especially in the Chesapeake Bay region. ✓

Group B

The assemblage from Group B included 531 bone and 77 shell fragments (Table 1). Unidentifiable large mammal remains constituted 68% (415) of the total assemblage indicating the highly fragmented nature of the assemblage.

The most common species identified were cow, pig, and oyster but many smaller wild animals were also recorded (Table 1). There were 11 species identified in all.

The assemblage was in good physical condition but highly fragmented which diminished the overall interpretations.

Bos taurus (Cow)

Cow remains were very common (51) but were mostly isolated teeth (Table 3). Most of the teeth were fragments and probably represented refuse from initial butcherings. Other elements were from ribs, fore and hind limbs and foot extremities (toes and ankle bones). One of the rib was a sawed shaft section, probably from a short-rib portion. Rib-joint fragments, though usually rare, were also identified and are often removed with the vertebrae (backbone) representing standing-rib roasts. The remainder of the shoulder (scapula) fragments were from chuck and necks cuts. One fragment was an axed joint of the scapula (shoulder) which is often removed when the chuck portions are separated from the neck and lower shoulder meats (Figure 1). Thus the scapula joint is often removed and discarded during initial butchering. The blade of the shoulder (scapula) is retained within meaty portions such as the "blade" pot roast or chuck (blade) steak (Figure 1). A cut astragalus (ankle) was recorded and is associated with the hind-shank portions but is usually removed, separately, during initial butchering (Figure 1).

The maturation data from tooth wear patterns suggested that 2 cows were at least 2.7 years old at death.

Sus scrofa (Pig)

Pig remains (28) were all teeth except 2 leg bone fragments (Table 3). A humerus (upper foreleg) shaft fragment was from a picnic shoulder cut (Figure 2). One fibula (lower hindleg) shaft fragment represented a "shank-half" ham. The isolated tooth remains were probably refuse from initial butcherings, as the heads are usually removed and discarded soon after the animal is killed and cleaned (Figure 2).

The limited maturation data from tooth wear patterns indicated that 2 pigs were less than a year old at death.

Ovis aries (Sheep)

The remains of sheep (9) were less common than those of cow or pig (Table 3). Teeth were numerous and probably represented refuse from initial butchering. Other elements were from the fore and hindlegs and vertebrae, and represented fore-shank, hind-"leg of lamb", hind-shank and "rack of lamb" portions (Figure 3).

Tooth wear maturation data indicated that 1 sheep was 17 months old at death.

Unidentifiable Large Mammals

This material constituted 68% of the total assemblage and probably represented large domestic animal remains. Large wild animal remains (white-tailed deer) were not identified in this collection. Most of the fragments were from longbones (legs) and ribs.

Sylvilagus sp (Rabbit)

A single rabbit foot bone was identified (Table 3). Cottontail rabbits are very common in the eastern U.S. and were often hunted for food.

Rattus rattus (Black Rat)

Rat bones were rare and only 2 were identified in the entire assemblage. Rats are common refuse scavengers and their remains are often identified in faunal assemblages. Gnaw marks from rat incisors are often identified in historic assemblages, however, gnawed bone was rare in this assemblage which suggested the refuse deposit was protected from prolonged scavenging.

Gallus gallus domesticus (Chicken)

Chicken remains (3) were rare and included wing and back portions (Table 3).

Turtles

Terrapene carolina (Eastern Box Turtle) was identified and consisted of 7 shell fragments (Table 3). Box Turtles

are very common terrestrial species and were a common food resource.

Pisces (Fish)

The remains of perch and bass were identified (Table 3). Both species were represented by scales and skull fragments. Both are common freshwater species

Crassostrea virginica (American Oyster)

Oyster remains (56) were very common and included mostly complete valves (shells). This material was very deteriorated and exhibited a chalky texture. Oysters usually live in colonies in saline areas from estuary to subtidal ocean zones and are a common food resource. Their shells were also used for mortar and fertilizer.

Mercenaria mercenaria (Hard Clam)

Less common than oyster, hard clams (21) included mostly shell fragments (Table 3). Hard clams have a more restricted distribution than oysters. They live in saline tidal flats and burrow just below the surface in muddy-sand or sandy areas. They are a common food resource.

Group C

The faunal assemblage from Group C consisted of 266 bones and 50 shell specimens (Table 1). Of this, 201 (64%) fragments were unidentifiable large mammal remains.

There were a wide range of species identified. Of these, cow, pig, sheep, box turtle and oyster were most common. Many small wild species were important secondary food sources (Table 1).

This material was in good physical condition but highly fragmented which limited the analytical data from the assemblage.

Bos taurus (Cow)

Cow remains (37) were common and a wide range of elements were recorded, representing most major portions of the skeleton (Table 4). This evidence demonstrates that the remains include refuse from initial butchering. Especially important were toe, ankle, knee, teeth, jaw and cranial elements which are not associated with meaty areas of the animal. These elements are usually removed and discarded during the initial stages of butchering. Interestingly enough, one patella (knee) and astragalus (ankle) were cut or axed. The knee was split in two, which resulted from the initial processing when the hind leg are disarticulated and divided into major meat portions (Figure 1). The astragalus was probably cut while processing the lower hindlegs.

The most common elements were hindlegs, vertebrae, and forelegs. The hindleg remains were, mostly, from round and shank roast cuts. One innominate (pelvis) represented a sirloin roast (Figure 1). Vertebrae were common and represented chuck and standing-rib portions. Two of the vertebrae were split resulting from initial butchering when the backbone is split in two from top to bottom creating two equal halves of the carcass. This produces lengthwise splitting of the vertebrae body (centrum).

Ribs were cut and sawed in sections representing short-rib and short-plate meat portions (Figure 1). One rib-joint fragment was identified and is usually butchered with "standing-rib" or short-loin meats (Figure 1).

There were 2 sawed shoulder (scapula) fragments identified representing chuck roast portions. One humerus (upper foreleg) element was from a "rolled" shoulder cut and an ulna (lower foreleg) from a foreshank cut.

The preceeding evidence demonstrates that with a greater diversity of elements there is a corresponding increase in the range of meat portions. Most of the cuts mentioned above were better quality portions associated with meaty areas of the body.

The maturation data from, both, tooth wear and bone fusion patterns, indicate that 2 cows were at least 3 years old at death.

Sus scrofa (Pig)

Pig remains (12) included, mostly isolated teeth resulting from initial butcherings. Two humerus (upper foreleg) shaft fragments were from picnic - shoulder cuts (Figure 2).

Maturation data from toothwear patterns were limited but suggested that 1 pig was less than 1 year old at death.

Ovis aries (Sheep)

Sheep bones were less common than cow or pig (table 4). Also, compared to cow and pig, sheep teeth were scarce. The common elements were from the hindlegs. Several hindleg bones were from "butt" and shank-half "leg of lamb" portions (figure 3). A radius (lower foreleg) was from a fore-shank cut.

Unidentifiable Large Mammals

This material included 201 fragments probably remains of large domestic mammals. Fragments from large wild species (i.e., white-tailed deer) were not identified. Most of this material represented longbone (fore-hindlegs) fragments (Table 4). There were 33 incinerated or calcined bone specimens from, either, burning or chemical weathering.

Terrapene carolina (Eastern Box Turtle)

Box turtle bones (10) included only shell fragments (Table 4). This species is adapted to most meadow-woodland fringe habitats and was often used for food.

Crassostrea virginica (American Oyster)

Oyster shell remains (41) were relatively common and unbroken valves (shell). Oysters are found in saline waters

in estuary to subtidal ocean zones. Oysters are a popular food resource and the shells were often pulverized for mortar or fertilizer.

Mercenaria mercenaria (Hard Clam)

Hard clam remains were less abundant than those of oysters (Table 4). Hard clams have a limited distribution. They require high salinity environs (at least 2/3 that of ocean water) and prefers tidal flats with muddy-sand or sand. They burrow just below the surface in shallow water. Hard clams are a common food resource.

Group D

Group D consisted of 243 bones and 15 shell fragments and exhibited a wide range of domestic and small wild species (Table 1). Of the total, 129 (50%) fragments were unidentifiable large mammal remains. The most common species were cow, pig, sheep, and box turtle.

The material was in good physical condition but highly fragmented which limited the identification of many elements.

Bos taurus (Cow)

Cow remains (10) included isolated teeth, vertebrae and a few hindlimb fragments (Table 5). The teeth probably represent refuse from initial butcherings. The hindleg and vertebrae were from hind-shank, neck and short-loin cuts (Figure 1).

Sus scrofa (Pig)

The remains of pig were relatively common and represented a wide range of skeletal elements from most parts of the body including isolated teeth, hindlimbs, vertebrae, innominates (pelvis) and forelimbs (Table 5). Many of these elements, such as, teeth, ankle, and toe bones most likely constitutes refuse from initial butcherings. One tibia (lower hindleg) fragment was from a "shank-half" ham and two vertebrae representing "Boston shoulder butt" and loin cuts (Figure 2).

Maturation data was limited but tooth wear patterns indicated that 1 pig was less than a year old at death.

Ovis aries (Sheep)

Ten sheep bones were identified and were, mostly, hindlimb and vertebrae fragments (Table 5). Interestingly, sheep teeth were not recorded which contrasts sharply with the data for cow and pig. Sheep skulls are usually discarded after butcherings and, excluding teeth,, are rarely identified in most assemblages. The hindlimb and innominates (pelvis) fragments were probably from hind "leg of lamb" portions (Figure 3). The vertebrae remains constitute loin and "rack of lamb" roasts. Two vertebrae were split lengthwise, the result of axing the backbone down the middle during initial butchering which produces two equal halves of the carcass. "Rack" meat portions are easily removed from the half carcass.

Sylvilagus sp. (Rabbit)

Rabbit remains were rare (3) in the assemblage. This species occupies open-field and woodland fringe habitats, and is a common food resource.

Rattus rattus (Black rat)

Rat remains (4) were scarce. They frequently scavenge refuse deposits and 3 bones from Group D exhibited gnaw marks which match rat incisors, especially since rats were the only rodents identified in this assemblage. In general, it was apparent that rat scavenging was minimal and suggests that the refuse deposit was protected, to some degree, from prolonged rodent scavenging.

Gallus gallus domesticus (Chicken)

Chicken bones (14) represented wing, back, breast and leg portions. However, other elements, including vertebrae, lower leg and mandible (jaw) fragments are not meaty portions and represent refuse from processing whole carcasses.

Terrapene carolina (Eastern Box Turtle)

Box turtle remains were very abundant (43) and represented at least five individuals. A variety of elements were identified, including limb bones, innominates (pelvis) and, as usual, shell fragments. Apparently, entire turtle carcasses were processed at the site. The box turtle is a common terrestrial species and lives in moist field and woodland fringe habitats. It is often used as a food resource.

Pisces (Fish)

Fish remains were rare consisting of 2 indeterminable skull fragments.

Crassostrea virginica (American Oyster)

Oysters were represented by 6 shell fragments. This species is a common food resource and the shells were often pulverized and used for mortar mix or fertilizer.

Mercenaria mercenaria (Hard Clam)

Hard clam remains were mostly fragments and, as mentioned elsewhere, this species is a popular food resource.

Group E

Group E represented the largest assemblage from the Grand Tenancy site, consisting of 708 bone and 40 shell fragments (Table 1). Of the total, 366 (52%) fragments were unidentifiable large mammal bones which demonstrates the fragmentary nature of the assemblage.

There were 18 species identified - more than any other assemblage (Table 1). They represented a wide variety of mammals, aves (birds), reptiles, pisces and shellfish. The most common species were cow, pig, sheep, rabbit, chicken and box turtle. In addition to the usual domesticates, a variety of small wild species were identified, including rabbit, squirrel, bat, vole, box turtle, red-tailed hawk, catfish, perch, bass, oyster and hard clam. The diversity of species was evidence of a variety of micro-environments in the vicinity of the site including woodland, meadow, and fresh water stream, etc. Especially sensitive indicators of micro-environments were species like Microtus pennsylvanicus (Meadow Vole) and Eptesicus fuscus (Big Brown Bat) - see species discussion below.

Freshwater habitats were indicated by, at least, four varieties of freshwater fish and one species of freshwater mussel. Conversely, oysters and hard clams are adapted to variable marine conditions.

This assemblage was in good physical condition although highly fragmented. However, the fragile elements of small animals were well preserved, suggesting that the deposit was not exposed to extensive weathering. A number of elements (7) exhibited rodent gnawing and the gnaw marks match the tooth pattern of rat incisors. Rabbit and meadow vole incisors were also compared to the gnaw marks but were either too large or small.

Bos taurus (Cow)

The remains of cows (18) were relatively scarce compared to those of pig and sheep (table 6). Foreleg and isolated teeth represented the bulk of the assemblage. The foreleg remains were articulated and cut off at the distal end. This represented a foreshank meat portion (Figure 1). One tarsal (hind-ankle) was cut, probably, the result of initial butchering when the feet are removed from the lower leg. The teeth, also, represented refuse from initial butchering.

The maturation data from bone fusion and tooth wear patterns indicated that one cow was less than 3 years old and another was at least 3 years old at death.

Sus scrofa (Pig)

There were 42 fragments identified as pig but 19 (45%) of these were isolated teeth (Table 6). Most likely, the teeth and leg extremities (toes, ankles) were refuse from initial butcherings. Other common elements were fore and hindleg, and vertebrae fragments. A number of these were cut, apparently with an axe. Foreleg and shoulder elements were from "Boston Butt", picnic-shoulder, and "hock" portions (Figure 2). Two vertebrae fragments were from loin cuts. One innominate (pelvis) and femur (upper hind leg) fragment represented "butt half" hams while several tibia (lower hindleg) shaft fragments were from "shank-half" hams (Figure 2).

Maturation data from tooth wear and bone fusion patterns represented a variety of ages. The remains of one fetal pig were identified probably less than 3 months old. Two other pigs were less than 1 year old at death.

Ovis aries (Sheep)

Sheep bones (23) were common but represented very specific areas of the body which contrasted with the evidence for cow and pig. Sheep teeth were very rare (1) compared to cow and pig (Table 6). The rest of the refuse consisted of lower foreleg, lower vertebrae and upper hindleg elements which represented the meatiest area of the sheep (Figure 3). The foreleg elements were from foreshank cuts and one of the radius shafts was axed. The vertebrae (lower back) represented loin and "rack of lamb" portions (Figure 3). Many of the vertebrae were split, lengthwise, from cutting the sheep in two equal halves. Each half was then processed into smaller portions.

Two femur (upper hindleg) fragments were from hind, "leg of lamb" cuts (Figure 3) and one of these was sawed but the marks were asymmetrical and suggested the use of a handsaw.

Overall, the sheep portions described above were from meaty areas of the body and represented good quality cuts (Figure 3).

Unidentifiable Large Mammals

The bulk of this assemblage was long bone (legs) and rib fragments. Most of this material, probably, represented large domestic mammal remains. Large wild animal remains (white-tailed deer) were not identified.

Sylvilagus floridanus (Eastern Cottontail Rabbit)

Cottontail remains were very common, especially compared to all the other assemblages from Grant Tenancy (Table 1). This species inhabits open woodland, meadow, field and forest edge-meadow environs. It feeds on a variety of herbs, grasses, berries and cane. A variety of skeletal parts were recorded suggesting that entire carcasses were being processed. The most abundant elements were fore and hindlegs. Rabbits are a very popular food resource.

Sciurus carolinensis (Gray Squirrel)

Only 2 elements were identified as gray squirrel (Table 6). This is a common woodland species and is, also, a common food resource.

Rattus rattus (Black Rat)

Rat remains were scarce (4) and represented, mostly, hindlimbs (Table 6). As noted elsewhere, rats are notorious refuse scavengers and a number of bone fragments (7) exhibited rodent gnaw marks which matched, closely, the pattern for rat incisors (front teeth).

Microtus pennsylvanicus (Meadow Vole)

The vole remains included only teeth and mandible (jaws) but represented 3 individuals (Table 6). Vole elements were not recorded in any other assemblage.

The meadow vole is a very common, small herbivorous rodent. It inhabits open meadows or fields with long grasses and eats a variety of grass-like plants, grass seeds, as well as farm grains.

The vole remains were mandible and cranial elements which are very delicate and, usually, are not well preserved. This suggest, perhaps, the deposit was well protected from prolonged weathering and the recovery techniques employed were such, that, some small fragile bones were recovered. Conversely, there is a possibility that the voles were intrusive but the evidence is inconclusive without knowing the exact nature of the deposit.

Eptesicus fuscus (Big Brown Bat)

This is one of the most common bat species in, either rural or urban settings and sightings are common in the city

as well as on the farm. It is the largest species in this region with a wing span up to 12 inches. It prefers to live in hollow trees, cliffsides and, as usual, caves. It feeds on a variety of insects.

One maxillary (upper jaw) fragment was identified and suggested the refuse was sufficiently protected to allow the preservation of small, delicate bone elements.

Gallus gallus domesticus (Chicken)

The remains of chicken were very common (38) and most were from wing, back, thigh and leg portions (Table 6). The wide range of skeletal elements suggested that whole carcasses were processed at the site.

Of special interest was a rodent gnawed leg bone (tibiatarus). This specimen was systematically gnawed from the joint-end toward the middle of the shaft. The tooth marks match those of rat incisors and several rat elements were identified in the assemblages.

Meleagris gallopavo (Turkey)

Several turkey bones were identified and all were hindlimb elements (Table 6). Turkey remains were uncommon for the site, as a whole. The turkey is a woodland species and is abundant in many areas of the eastern U.S. It prefers woodland environments with ample rainfall and eats a variety of food such as nuts, seeds, fruits of the forest bottoms and insects (grasshoppers, beetles, etc.).

Buteo jamaicensis (Red-tailed hawk)

One coracoid with cut marks (shoulder) was identified (Table 6). This species prefers forest-fringe and open-field environments and hunts, mostly, smaller mammals which was interesting since many smaller mammals were identified in this assemblage. The cut marks on the coracoid were surprising and there is little conclusive evidence that hawks were eaten but they were often hunted for their plumage.

Terrapene carolina (Eastern Box Turtle)

Box turtle remains were very abundant (68) and were mostly shell fragments although limb-bones, vertebrae, innominates and a mandible were identified. This diversity suggests that whole turtle carcasses were processed at the site. This species is common throughout the eastern U.S., in

most woodland and meadow environs. The abundance of this species suggests they were used as food.

Pisces (Fish)

Ictalurus sp. (Catfish) remains included spines, (pectoral) and rays. Catfish are bottom feeders and live in most freshwater streams, lakes and ponds. They are also tolerant of low salinity aquatic conditions. Most catfish species are common food resources.

Perch were also identified (7) from bones and scales. This is also a common freshwater fish and is a popular food resource.

Bass remains included cranial fragments and is another popular freshwater fish.

The remains of all three species were mostly cranial fragments and probably represent butchering refuse when the heads were removed and discarded.

Crassostrea virginica (American Oyster)

There were 29 oysters shell fragments (Table 6) and half these specimens were complete valves (shells). Oysters live in salinity subtidal and estuary zones. This species usually lives in colonies along salt marshes and estuaries. They, also, thrive upstream in shallow brackish waters. As, mentioned elsewhere, oysters are a popular food resource and their shells were, often, pulverized for mortar mix and fertilizer.

Mercenaria mercenaria (Hard Clam)

Hard clam remains were less common than those of oysters (Table 6). They are found in more restricted environs along tidal flats of higher salinity levels compared to oysters. They burrow just beneath the surface in muddy-sand or sandy areas. This species is, also, a common food resource.

Elliptio (cf) dilatatus (Lady finger)

One Elliptio shell was identified. This species is a very common freshwater mussel (bivalve) and suggests that a stream or river exists in the vicinity of the site.

Overview: Group E

Since this assemblage was so large, there are a number of important facts that should be stressed.

This assemblage yielded the widest range of species (18) including large domestic mammals and a variety of small wild animals (Table 1). This included the greatest variety of mammals, aves (birds), pisces (fish) and shellfish. These species represented a diverse number of micro-environments including woodland (turkey, squirrel), woodland-fringe (rabbit, box turtle), meadow/field (hawk, vole, box turtle), freshwater stream (catfish, perch, bass, elliptio) and salt marsh/tidal flats, etc. (oyster, hard clam).

There was considerable variations in the element distributions between the common species. Cow and pig remains were mostly teeth and fore - and hindleg elements. In contrast, sheep teeth were not recorded and common elements were vertebrae, fore - and hindleg bones.

Some species such as pig, rabbit, and chicken, exhibited a wide range of elements suggesting that whole carcasses were butchered in the vicinity of the site.

There was, also, variation in the distribution of meat portions among large domestic mammals. Cow portions were, mostly, shoulder cuts. Pig remains represented a variety of cuts, especially shoulder and "shank-half" hams. Sheep portions were from the loin, shoulder, and hind "leg of lamb".

There was considerable variation in the maturation data between the large domestic mammals. Cows were, generally, 3 years or older at death, pigs were less than 1 year old at death and data was not available for sheep remains due to the absence of teeth and elements with joint.

Group F

This assemblage was very small, consisting of only 34 bone and 1 shell fragment (Table 1). The elements were limited for most species and, thus the assemblage yielded very little specific information.

The collection was in good physical condition but was very fragmented.

Sus scrofa (Pig)

One element was identified as pig which was an isolated canine tooth (Table 7). This was probably from butchering refuse.

Ovis aries (Sheep)

One cervical vertebrae was recorded and was from the neck area. This portion represents a poor quality meat cut.

Sylvilagus floridanus (Cottontail Rabbit)

Rabbit remains included only 2 elements. This species is adapted to open field and woodland-fringe environments. It is commonly hunted and is a popular food resource.

Gallus gallus domesticus (Chicken)

Only two chicken bones were identified and they were leg and toe bones. The leg bone was from a thigh portion.

Pisces (Fish)

Fish remains were very common and two species were identified.

Ictalurus sp. (Catfish) remains included one dorsal spine. This element is a very dense bone and is often recovered in faunal assemblages. Catfish are bottom feeders in rivers, streams, ponds, etc., and are common food resources.

Perca flavescens (Yellow Perch) remains were very common and consisted of cranial elements. This material probably represents butchering refuse when the heads are removed and discarded.

Group G

The faunal assemblage from Group G was small (59) which limits the interpretive data from the analysis. The remains included 58 bones and 1 shell fragment (Table 1). Unidentified large mammal fragments accounted for 68% (40) of the total assemblage. Although small, there were a variety of species (6) identified in the assemblage (Table 8).

The material was in good physical condition but was highly fragmented.

Sus scrofa (Pig)

Pig bones (5) included isolated teeth and hindleg fragments. The teeth probably represent initial butchering refuse. The hindleg bones represent "butt half" and "shank half" hams (figure 2).

Didelphis marsupialis (Opossum)

One element was identified as an opossum (Table 8). This was the only opossum element identified in the entire assemblage. This species is a cat sized mammal which lives in most rural and urban settings. It eats a wide variety of foods and is a common scavenger. In some areas of the eastern U.S., opossum is a popular food.

Sciurus carolinensis (Gray Squirrel)

Two foot elements were identified as gray squirrel (Table 8). Squirrels are common woodland species and are widely distributed across the eastern U.S. They are a popular food resource in many areas.

Gallus gallus domesticus (Chicken)

Chicken remains (5) included wing, breast, and thigh portions (Table 8).

Terrapene carolina (Eastern Box Turtle)

Box turtle remains consisted of 5 shell fragments (Table 8). Box turtles are field/woodland fringe inhabitants and were often used as food.

Mercenaria mercenaria (Hard Clam)

Only one hard clam shell fragment was identified (Table 8). Hard clams are commonly found in saline, tidal flat environs and are a popular food resource.

Group H

The group H faunal assemblage was very small (15) and thus, has minimal interpretive value. The material was in good physical condition.

Sus scrofa (Pig)

There were 3 pig bones identified, consisting of rib and foot bones (Table 9).

Ovis aries (Sheep)

Sheep remains were all rib fragments and several (4) exhibited axe marks. This material, probably, represented "rack of lamb" cuts (Figure 3).

Sylvilagus floridanus (Cottontail Rabbit)

One femur (upper hindleg) was identified as rabbit. This is a common woodland-field species and is, also, a popular food resource.

Gallus gallus domesticus (Chicken)

One chicken bone was identified and was from a thigh meat portion (Table 9).

Terrapene carolina (Eastern Box Turtle)

Two box turtle bones were identified consisting of forelimb remains. This species inhabits moist woodland and field environments often close to fresh water. Box turtle was a common food resource in many areas of the eastern U.S.

Group I

The assemblage from Group I was small and, thus has limited interpretive value. The material consisted of 42 bones and 24 shell fragments (Table 1). The common species were pig, sheep and shellfish. The material was in good condition, although highly fragmented.

Bos taurus (Cow)

Cow remains were rare and included an isolated tooth and rib fragment (Table 10).

Sus Scrofa (Pig)

This material consisted of isolated tooth fragments including those of the upper (maxillae) and lower jaw (mandible). Other elements were rib and hindleg fragments (Table 10). Of this, a sawed tibia (lower hindleg) shaft was from a "shank-half" ham (Figure 2).

Ovis aries (Sheep)

Sheep remains were common and represented a variety of quality meat cuts. Several vertebrae were from shoulder portions. One innominate (pelvis) and femur (upper hindleg) were from butt-half "leg of lamb" (Figure 3).

Microtus sp. (vole)

One element from a vole was identified (Table 10). Voles inhabit open field/meadow environs and are one of the most abundant small field mammals in the eastern U.S. They eat a variety of seeds, grasses and even farm grains.

Terrapene carolina (Eastern Box Turtle)

Three box turtle carapace (upper shell) fragments were identified (Table 10). It inhabits moist field-woodland fringe environs, often close to water. Box turtles are often used for food.

Crassostrea virginica (American Oyster)

Oysters shells were very common (18) and most of the specimens were complete valves (half shell). Oysters inhabit

marine waters of low to moderate salinity from estuaries to subtidal ocean water. They are a popular food resource and the pulverized shell was often used as mortar mix or fertilizer.

Mercenaria mercenaria (Hard Clam)

Hard clams were less common than oysters (Table 10). This species occupies a restricted environment of high salinity of the tidal flats preferring areas of muddy-sand/sand. They are a popular food resource.

Group J

The assemblage from Group J consisted of 95 bones fragments representing eight identified species (Table 1). The material was in good physical condition but very fragmented.

Bos taurus (Cow)

Cow bones were abundant including isolated teeth, vertebrae and hindleg fragments (Table 11). The teeth were probably refuse from initial butcherings since they are not associated with meaty portions of the body. The hindleg remains were from round and hind-shank roasts (Figure 1).

The limited maturation data from tooth wear patterns indicated that one cow was more than 3 years old at death and another was 2 - 2.5 years old.

Sus scrofa (Pig)

Pig remains were scarce and consisted of only 2 isolated teeth and a mandible (lower jaw) fragment. This material was most likely refuse from initial butcherings.

Ovis aries (Sheep)

Sheep remains (9) consisted of vertebrae and forelimb fragments (Table 11). Two cranial fragments were recorded (Tooth, skull) but were much less common than cow and pig. This was a specific trend for nearly all the assemblages. The vertebrae remains were all from the neck region and, probably, represented refuse from initial butcherings. The forelegs remains were from two fore-shank and on "square-cut" shoulder portion (Figure 3). The shoulder fragment was sawed and the asymmetrical sawing pattern suggested the use of a handsaw.

Sylvilagus floridanus (Cottontail Rabbit).

Four rib and forelimb fragments were identified as cottontail rabbit (Table 11). This is a very common species in the eastern U.S. and inhabits moist open-field, woodland fringe, and woodland environs. The cottontail is a very popular food resource.

Gallus gallus domesticus (Chicken)

Chicken remains (5) represented shoulder and leg elements from back, wing and thigh portions.

Bufo sp. (Toad)

One toad leg bone was identified (Table 11). Toads inhabit moist, forest-woodland environments.

Terrapene carolina (Eastern Box Turtle)

Box turtle remains (8) consisted of shell and limb bones (Table 11). The box turtle inhabits moist field and woodland fringe environs, often near water sources. In many areas, the box turtle is a common food resource.

Kinosternon subrubrum (Mud Turtle).

Seven elements were identified as mud turtle (Table 11). This species is very common from the Middle Atlantic region to the South. It prefers areas of fresh or brackish water, shallow, soft bottoms in slow moving water with ample vegetation. There is little evidence that the mud turtle was eaten.

Features 2-12

There were 9 features with small faunal assemblages from the Grant Tenancy Site. All of the assemblages were small and, individually, they have little interpretive value. Six of the nine assemblages had less than 10 specimens. Thus, they were considered as a unit for the analysis (Table 1).

There was little variation between the feature assemblage and a number of important characteristics were recorded. Most of the assemblages included a comparatively high number of unidentifiable large mammal remains. Oyster shell remains were, also, common in most features (Table 1). Four of the features, also, yielded box turtle remains. Otherwise, very few additional species were recorded in large numbers (Table 1).

Based on the preceeding data, the feature assemblages are presented, here, as a simple unit. In Tables 12 to 20, the remains are listed separately, whereas Table 1 shows all the assemblages as a unit with species and specimen counts listed together.

On the whole, the feature assemblage remains were in good physical condition although the material was very fragmented.

The combined assemblages consisted of 101 bones and 14 shell fragments (Table 1). Of the total, 49 (43%) fragments were unidentifiable large mammal bones. The most common identified species were cow, pig, box turtle, and oyster. Sheep material (22) was abundant but only in one feature (F 12/Table 1). The species in all features are discussed, individually, below.

Bos taurus (cow)

Cow remains were scarce (4) and were recovered in only 3 of the 9 features (Tables 1, 16, 17, 20). The elements were isolated teeth, mandible (lower jaw) and shoulder fragments. The bulk of this material was probably initial butchering refuse but one cut scapula (shoulder blade) represented a "blade" pot roast (Figure 1).

Sus scrofa (Pig)

Pig remains were uncommon (5) and were recorded in three of the assemblages (Table 1, 15, 17, 19). This refuse included isolated teeth and forelimb fragments. The teeth probably represents refuse from initial butchering. The

forelimb fragments constituted "picnic" shoulder and "Boston Butt" roasts (Figure 2).

Ovis aries (Sheep)

Sheep remains (22) were only identified in one feature (Table 1, 19). This material consisted, mostly, of vertebrae fragments but, also, one rib and tibia (lower hindleg) shaft. Once again, cranial remains especially teeth, were missing in comparison with those of cow and pig. The vertebrae represented neck and "rack of lamb" and upper loin roasts. Some of the neck vertebrae were from initial butcherings since they are not associated with meaty portions and are usually removed and discarded, immediately, with the head. The hindleg specimen was from a hind-shank "leg of lamb" portion (Figure 3).

Sylvilagus floridanus (Cottontail Rabbit)

Only two elements were identified as cottontail rabbit from Feature 12 (Table 1, 19). Cottontails prefer moist field and woodland fringe environs and are commonly hunted as a food resource.

Gallus gallus domesticus (Chicken)

Only one chicken element was identified from Feature 12 (Table 1, 19). This element represented a thigh portion.

Terrapene carolina (Eastern Box Turtle)

Box Turtle remains (17) were identified in 4 assemblages and consisted of shell fragments (Table 1) 16, 18, 19, 20). Box Turtles prefer moist, field/woodland fringe habitats, often located near freshwater. This species is often used as a food resource.

Crassostrea virginica (American Oyster)

Oyster remains (13) were recorded in six of the nine assemblages (Table 1). Most of the remains were complete valves (shell half). Oysters are adapted to saline water in salt marsh to subtidal ocean environs and represents a popular food resource.

Mercenaria mercenaria (Hard Clam)

A single hard clam valve (shell) was identified (Table 1). Hard clams are restricted to saline, tidal flats and, also, represent a popular shellfish food resource.

Discussion and Conclusions

It was apparent that most of the remains from the Grant Tenancy Site represented both food refuse and initial butchering refuse. The entire site assemblage consisted of 2354 fragments including 2140 bones and 214 shells (Table 1). In all, there were 22 species identified and, considering all the assemblages, the most consistently identified remains were those of cow, pig, sheep, chicken, rabbit, box turtle, oyster, and hard clam (Table 1). Pig remains were found in every assemblage and demonstrated the significance of this species as a food source.

As noted the Feature assemblages were analyzed as a single unit due to the small number of specimens in each.

The remains of large domestic mammals (cow, pig, sheep) dominated all the assemblages and these species constituted the bulk of the meat diet. Cow and pig remains were more common than sheep. Also, in all the assemblages, small wild species were common and represented significant supplementary or secondary food resources. Common wild species remains were rabbit, box turtle, oyster and hard clam (Table 1). Chicken remains were also abundant in most assemblages and this species was an important ancillary domestic food source.

The remains of large wild animals, such as white-tailed deer, were not identified, although it is possible that some of the unidentified large mammal fragments (common in every assemblage) represented deer remains.

As noted, the total assemblage yielded 22 species including those of mammals, aves, reptiles, amphibians, pisces, shellfish and crabs.

This collection represented a variety of micro-environments such as meadow/open field, woodland-fringe and freshwater stream. The Group E assemblage exhibited the widest variety of species (18) which represented a diverse range of micro-environments. These included meadow/open-field (cottontail rabbit, meadow vole, box turtle, hawk), woodland fringe (box turtle, cottontail, hawk), woodlands (squirrel, turkey), freshwater (catfish, perch, bass) and marine-estuary/tidal flats (oysters, hard clam). Many of these species were common in a number of the assemblages and indicated that a variety of micro-environments existed near the site. However, although not knowing the exact location of the site, it is likely that the shellfish species were transported from some distance away.

Distribution of Skeletal Elements/Meat Portions

Post-cranial remains were, by far, the most common fragments in every assemblage (Table 2-20). Teeth, especially from large domestic mammals, were the most common type of cranial elements probably due to their dense, resistant construction.

There was significant variation in the distribution of skeletal elements between the large domestic mammals. Cow and pig remains were more common than those of sheep. Cow and pig teeth were very abundant in nearly every assemblage and probably represented refuse from initial butchering. By contrast, sheep teeth and cranial elements were rare or completely absent in most assemblages. Apparently, sheep skulls were discarded or scavenged without becoming part of the refuse deposit.

There was a considerable difference in the distribution of post-cranial elements and meat portions between the major domestic species. Cow and pig remains represented a wide range of elements in many assemblages, especially those of Group B, C, D, and E which just happen to be the largest collections from the entire site. Much of this material represents refuse from initial butchering such as teeth, jaws, toes and ankle bones. These elements are often removed and discarded during the early stages of the butchering process. Sheep remains, however, were less diversified and, as noted above, teeth/cranial elements were rare or absent and post-cranial remains were restricted to a few body parts.

There was a corresponding difference in the distribution of meat portions between the large domestic species. Cow portions were, consistently, represented by shoulder, chuck, sirloin and round roast meats (Figure 1). The greatest variety of cow meat portions were identified in the Group C assemblage which, also, yielded the widest variety of cow elements. These portions constituted better quality meat cuts. The common pig remains were, consistently, from "Boston Butt" and picnic shoulder cuts as well as "butt" and "shank" half hams (Figure 2). Group E exhibited the widest range of pig meat portions representing all the major parts of the body. The most common sheep portions were foreshank, "rack of lamb", loin, and hind-"leg of lamb" (Figure 3). Again, the widest range of sheep meats were recorded in the Group E assemblage which represented, mostly, better quality meats.

Significant, element and meat portion data were, also, recorded for many smaller species. A wide range of chicken elements was identified in the Group D and E assemblages suggesting the processing of whole carcasses. Common chicken cuts were wings, thighs and legs. A wide variety of rabbit

elements, representing all the major portions of the body, was identified in Group E. Also, near complete box turtle skeletons were recorded in both Group D and E, probably from the processing of whole carcasses. Fish remains, especially from Groups B, E and F, represented, mostly, cranial elements without vertebrae suggesting that only heads were removed and discarded in the refuse.

The preceding evidence clearly demonstrates that the entire carcass of a number of important species including pig, rabbit, chicken and box turtle, were processed at the site.

Only a few of the elements were sawed or cut. Most of the sawed remains were from the Group C assemblage. However, these specimens were not symmetrically sawed and were more indicative of "hand sawing" techniques. Most of the cut marks were the result of axe blows, especially on elements near joints which resulted from initial disarticulation of the animal. Examples were recorded for cow elements in the Group B and C assemblages. A number of vertebrae were split, lengthwise. This resulted from initial butchering where the carcass is cut in two by splitting the backbone from top to bottom. This produces two equal halves of the carcass which is then processed into smaller portions. Most of the split vertebrae were from sheep.

Maturation

Maturation data was recorded, where possible, for the large domestic mammal species. As noted elsewhere, the fragmented condition of the assemblages, significantly, limited the recording of maturation data. However, the limited data indicated important differences between the major species. The evidence suggested that most cows were, at least, 2.5 years old at death. Pigs were, generally less than a year old at death, although, at least, one fetal (less than 2 months) pig was identified. Sheep maturation data was scarce due to limited number of elements for this species. However, the limited evidence indicated that sheep were more than 1 year old at death.

In overview, the faunal remains from the Grant Tenancy Site represented a variety of domestic and wild species from a wide range of micro-environments. Large domestic mammals were the most important food (meat) resources, supplemented by a wide variety of small wild species representing diverse environments. Apparently, many of these species were initially butchered at the site represented by a wide variety of skeletal elements.

References Cited

- Clark, David T.
1985 Modern Farm Butchering Technology. An unpublished report. On file, Zooarcheology Research Facility, Department of Anthropology. The Catholic University of America.

Tables

The following is an explanation of the symbols and abbreviations used in the data Tables. The specimens listed on the Tables are all fragments unless stated otherwise.

The Tables are organized by element and species. The complete scientific name, for each species are used in the text, only. General animal listings are as follows:

- Lg. mam. = unidentifiable large mammal (cow or deer size),
- Med. mam = " " medium " (fox or raccoon size).
- Sm. mam = " " small " (mouse or squirrel size).
- Aves = birds
- Sm. Aves = small bird (robin or sparrow size).
- Lg. Aves = large bird (turkey size).

Several symbols refer to the teeth. They include: I = incisor; C = canine; PM = premolar; M = molar. The distinction between mandibular or maxillary teeth is expressed with subscript numbers - for example:

- M = first mandibular molar
- M = first maxillary molar
- I = first mandibular incisors
- I = first maxillar incisors

References to maturation data are expressed as : (-) = immature and (+) = mature. Also, the symbol "ep" refers to epiphysis - the end of the bone referring to bone fusion, and "dia" refers to diaphysis - the shaft of a bone. Symbols for sawed elements are =[1] and cut or axed elements are =(1). Terms referring to the orientation of limb elements include : px = proximal - the end nearest the trunk or head, and dst = distal - the end farthest from the trunk or head. The designation of "L" = a left element (L-ulna) and "R" = a right element (R-ulna).

Every assemblage has a number of indeterminable bone fragments. This material is often listed as follows:

- L.B.F. = long bone fragment(s) (leg bones).
- R.F. = rib fragment(s).
- V.T. = vertebrae fragment(s).

Many elements represent symmetrically sawed cross-section bone specimens which are listed as : sec. = sections.

A number of skeletal element terms for Aves, Reptiles, Amphibians and Pisces are different than those of mammals. The common elements are as follows:

Aves (Birds)

- cora. (coracoid) = shoulder element.
- furc. (furculum) = breast or "wish" bone.
- pygo. (pygostyle) = tail bone.
- tarmet. (tarsometatarsal) = lower leg.
- tibio (tibiotarsus) = middle leg.

Turtle

- carap. (carapace) = upper shell.
- plas. (plastron) = lower shell.

Pisces



- pect. sp. (pectoral spine).

Table 1	Crane Technology Sites	Distribution of Species
1	1	1
2	2	2
3	3	3
4	4	4
5	5	5
6	6	6
7	7	7
8	8	8
9	9	9
10	10	10
11	11	11
12	12	12
13	13	13
14	14	14
15	15	15
16	16	16
17	17	17
18	18	18
19	19	19
20	20	20
21	21	21
22	22	22
23	23	23
24	24	24
25	25	25
26	26	26
27	27	27
28	28	28
29	29	29
30	30	30
31	31	31
32	32	32
33	33	33
34	34	34
35	35	35
36	36	36
37	37	37
38	38	38
39	39	39
40	40	40
41	41	41
42	42	42
43	43	43
44	44	44
45	45	45
46	46	46
47	47	47
48	48	48
49	49	49
50	50	50
51	51	51
52	52	52
53	53	53
54	54	54
55	55	55
56	56	56
57	57	57
58	58	58
59	59	59
60	60	60
61	61	61
62	62	62
63	63	63
64	64	64
65	65	65
66	66	66
67	67	67
68	68	68
69	69	69
70	70	70
71	71	71
72	72	72
73	73	73
74	74	74
75	75	75
76	76	76
77	77	77
78	78	78
79	79	79
80	80	80
81	81	81
82	82	82
83	83	83
84	84	84
85	85	85
86	86	86
87	87	87
88	88	88
89	89	89
90	90	90
91	91	91
92	92	92
93	93	93
94	94	94
95	95	95
96	96	96
97	97	97
98	98	98
99	99	99
100	100	100

[illegible]



Bos taurus (Cow) Meat Portions.

Figure 1.





Sus scrofa (Pig) Meat Portions.

Figure 2.



Ovis aries (Sheep) Meat Portions.

Figure 3.



APPENDIX IV

Chemical Soils Analysis Tabulations

by

The University of Delaware
College of Agriculture
Soils Laboratory

TABLE 1
Soil Chemistry Data

Grant Tenancy 7NCE-6 Soil Chemistry Data

Context	F.S. Number	North	East	pH	P (FI)	K (FI)	Ca (FI)	Mg (FI)	Mn (lbs/ac)	Zn (lbs/ac)
Ap	262	130	390	6.4	50	44	150	150	50.1	8.6
Ap	263	125	390	6.3	50	61	150	150	50.1	8.3
IIAp	266	130	390	6.5	55	33	150	150	50.1	6.8
Ap	273	130	395	6.4	64	72	150	150	50.1	9.5
Ap	275	140	395	6.9	61	48	150	150	50.1	7
Ap	276	125	395	6.6	61	66	150	150	50.1	8.5
Ap	283	120	395	6.3	53	59	150	150	50.1	7.2
Ap	292	145	395	6.7	68	46	150	150	50.1	9.9
Ap	295	135	390	6.5	87	96	150	150	50.1	11.6
Ap	297	140	390	6.5	80	86	150	150	50.1	9.6
Ap	298	115	395	6.2	43	41	150	150	50.1	7.3
Ap	307	130	425	6.5	33	36	150	150	50.1	6.5
Ap	311	155	395	6.1	75	85	150	150	50.1	9.3
Ap	312	150	395	6.5	78	77	150	150	50.1	9.4
Ap	317	135	395	6.6	64	69	150	150	50.1	8.4
Ap	319	135	420	6.4	27	41	150	150	50.1	5.9
Ap	324	130	415	6.1	35	33	149	150	50.1	6
Ap	326	135	400	6.5	54	90	150	150	50.1	9
Ap	329	130	420	6.1	24	32	138	150	50.1	4.9
Ap	332	125	415	6.3	32	41	140	150	50.1	6.1
Ap	334	125	410	6.4	34	61	150	150	50.1	6.4
Ap	337	140	415	6.9	80	54	150	150	50.1	9.5
Ap	349	130	410	6.3	37	35	150	150	50.1	6.5
Ap	353	110	410	6.4	24	34	142	150	50.1	5.4
Ap	355	125	420	5.9	22	55	147	150	50.1	6.1
Ap	364	125	425	5.9	29	47	150	150	50.1	7
Ap	368	120	390	5.9	74	66	150	150	50.1	9.6
Ap	481	130	405	6.5	60	50	150	150	50.1	9.7
Ap	488	170	390	6.3	107	52	150	150	50.1	6.4
Ap	472	175	400	6.3	85	143	150	150	50.1	9.7
Ap	476	160	405	6	42	65	150	150	50.1	7.9
Ap	479	165	400	6.1	64	123	150	150	50.1	8.5
Ap	485	180	400	6.1	136	112	150	150	50.1	10.2
Ap	492	160	390	6	71	61	150	150	50.1	7.5
Ap	493	175	390	6.3	150	44	150	150	50.1	7.9
Ap	533	210	400	5.4	50	38	150	150	50.1	8
Ap	536	230	400	5.9	36	18	131	150	21.6	5.3
Ap	538	250	400	6.4	29	35	150	150	50.1	17
Ap	544	195	400	5.9	30	23	150	150	50.1	4.3
Fea 1	279			7	42	49	150	150	50.1	2.8
Kidden	482	130	390	6.8	23	21	129	150	50.1	4.2
Fea 7	542			6.7	19	14	123	150	31.4	1.8
Fea 9	550			6.3	61	27	139	150	50.1	25.1
Psh & Br	561			6.4	6	10	150	150	3.6	1.6
Fea 2	571			7.4	42	16	150	150	50.1	2.1
Fea 11	572			7.2	48	20	150	150	47	3.3
Fea 10	577			6.8	60	25	150	150	44	3.4
Ext Mid	584			6.7	26	34	132	150	25.8	1.7
Fea 12	586			6.9	39	68	150	150	43	4.9

TABLE 1, cont.....

Grant Tenancy 7NCB-6 Soil Chemistry Data

Context	F.S. Number	North	East	Ph	P (FI)	K (FI)	Ca (FI)	Mg (FI)	Mn (lbs/ac)	Zn (lbs/ac)
PM	524			6.6	85	17	150	150	46	3.2
PM	525			6.6	117	43	150	150	50.1	14.3
PM	526			6.6	103	27	150	150	50.1	3.7
PM	527			6.7	32	30	114	150	35.8	7
PM	528			6.7	136	24	150	150	50.1	4.7
PM	530			6.7	13	14	97	150	50.1	2.1
PM	531			6.5	8	20	125	150	50.1	2.2
PM	546			6.8	8	14	139	150	50.1	2.1

APPENDIX Y

Public Consumption Handout

1985-1986



STATE OF DELAWARE
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

OFFICE OF THE
DIRECTOR

P.O. Box 778
DOVER, DELAWARE 19903

TELEPHONE: 302-736-4644

**HISTORIC ARCHEOLOGY RESEARCH PROGRAM AT
THE H. GRANT TENANCY SITE (7NC-B-6)**



A historic archeology research program is being conducted by the Delaware Department of Transportation, Division of Highways, and the Federal Highway Administration in conjunction with Thunderbird Archeological Associates at the H. Grant Tenancy Site.



The Route 48 - (Lancaster Pike) intersection improvement plan calls for the construction of an enlarged and safer intersection. The H. Grant Tenancy Site (7NC-B-6) is the only area along the proposed improvement that has not been built up with housing complexes or is not still in cultivation. At one time the site was cultivated but it is presently pasture, and the thickness of the root mat suggests that it has been so for some time.

At the H. Grant Tenancy Site an early to mid 19th century historic component tentatively identified as a tenancy or former tenant house was found. Along with the tenancy site there was also one small prehistoric site of unknown cultural affiliation that was of little significance. Historic map and deed research suggests that the H. Grant Tenancy Site was a short lived domestic structure and further evidence comes from the various classes of ceramics found representing the domestic activities of food storage, food preparation, and food consumption. The structure was oriented towards Lancaster Pike and post molds indicate probable outbuildings of unknown function.

The H. Grant Tenancy Site has high significance because it contributes data important in the understanding of the history of this area and the surrounding region. The intact subsurface archeological features may yield information directly relevant to an understanding of the changing economic patterns observed in the beginning of the 19th century. There is a great potential for the reconstruction of patterns of disposal for the site, as well as the discernment of functionally specific site areas. Another significance of the site is that it provides a good opportunity to study the economic unit of the tenancy. None from this period have been excavated to date in Delaware and few in the Middle Atlantic region. Data recovery would provide comparative information to be used with other known Middle Atlantic tenancies. Such sites occupy an important place in the economic structure of the late 18th century and early 19th century, when the eastern seaboard was undergoing radical economic change. The tenancies represent a relatively little described class in the historical documentation of the era, yet formed a very large and important economic substrate of American Society.

If you would like further information concerning this research program, please contact Kevin Cunningham at 730-4644 or Tim Thompson at the site.

APPENDIX VI

Glossary

GLOSSARY

Chi Square Test of Association: a test used to determine if variables within a sample are statistically associated, that is, to determine if statistically significant differences exist which can not be attributed to chance.

Robinson Coefficient of Agreement: a test used to measure statistically significant similarities between two sets of values.

Terminus Post Quem: the beginning date of the most recent artifact in a context, provides a date before which the occupation could not have taken place.

Z Score: a test that allows the comparison of values from two different normal distributions and uses the score obtained to measure deviation from the population mean.

APPENDIX VII

Research Design

THUNDERBIRD ARCHEOLOGICAL ASSOCIATES, INCORPORATED

ARCHAEOLOGY, CULTURAL RESOURCE MANAGEMENT

ROUTE ONE, BOX 1375
FRONT ROYAL, VIRGINIA 22630

(703) 635-3860

MITIGATION PROPOSAL, SCHEDULE & BUDGET
FOR CONDUCTING
DATA RECOVERY (PHASE III) INVESTIGATIONS
AT THE
H. GRANT TENANCY SITE (7NC-B-6)
WILMINGTON, NEW CASTLE COUNTY, DELAWARE

William M. Gardner, PhD.
Principal Investigator

Timothy A. Thompson
Project Director

MAY 1985

Length of Project: 7 months

Introduction

This transmittal presents a proposal for conducting data recovery investigations at the H. Grant Tenancy site in New Castle County, Delaware (Figures 1 & 2). Significant archeological remains will be affected by proposed construction connected with intersection improvements to Rt. 48 (Lancaster Pike). This proposal was prepared in response to a request for proposal from the Delaware Department of Transportation.

Background and Research Questions

In response to changing economic conditions in the beginning of the nineteenth century, land tenure became consolidated into the hands of fewer individuals in northern Delaware. Landowners often had business interests connected with industrialization or commerce in urban centers and frequently lived in the city. To maintain agricultural production, a system of tenancy was employed. Tenants were probably drawn from groups of lower economic status in both urban and rural populations, but very little historical research has been devoted to these individuals and little is known of their economic or cultural background. Likewise, little remains of their material culture, including their housing, have survived. It appears that the H. Grant Tenancy site represents a tenant occupation for reasons presented in the Phase I & II report (Barse 1985).

The testing program at this site revealed the remains of a structure and other sub-plowzone features, as well as a large quantity of artifact remains within the plowzone. The data recovery program proposed here has been designed to retrieve a sample of data to address several research questions. We would

like to learn more about the spatial arrangement and relationships of the dwelling and other service buildings such as storage sheds, animal pens, privies, etc., to show how these compare to the larger complexes of the owners, many of which are still extant. We also expect that discarded material possessions in the plowzone and features will allow a more precise characterization of the social and economic status of the tenant occupants of the site. Patterning in the distribution of economically significant attributes in the artifacts can be compared with data collected in future research to see if there are broad patterns reflecting the economic conditions of tenants as a group.

Both the spatial and artifact patterns identified at this site can serve as a baseline for comparison with data developed in future research into this little known class of archeological occupations. Future research questions might include the examination of the effects of proximity to a major market center (Wilmington) in comparison with situations more removed from such centers.


Research Methods

The research methodology has been designed to gather data to address these, and other research questions. The Background and Archival research will attempt to identify the occupants of the site and also develop more general data concerning the economic and social conditions in which tenant farmers lived. If specific information on the site and its occupants can be discovered this will be used for comparison with the results of the field work.

Research strategies for the field work will vary for different portions of the site (Figure 3). The area around the foundation (Area A) that was identified during the survey and testing program will be excavated by hand. The alignment of the remaining foundation wall will be exposed, and the overlying and adjacent soil will be screened through 1/4" mesh. In the 18th Century, artifact concentrations were usually located next to structure openings such as doors and windows, and such concentrations may be preserved beneath and even within the plow zone, allowing the identification of the location of these structure openings. Alternatively, this disposal pattern may not survive into the early nineteenth century when this site was occupied and a diffuse distribution of artifacts may be found. This result would be one step in establishing the characteristic archaeological patterns for tenant occupations in the first half of the nineteenth century. The equivalent of 45 five-foot-by-five-foot units has been allocated for this portion of the work.

While the hand excavations of that part of the site are underway, the remainder of the site will be plowed and a 10 foot grid set up over the plowed area. The roughly 470 ten-foot-by-ten-foot squares will be surface collected and bagged separately, and artifact concentrations mapped. The equivalent of up to 20 additional five-foot-by-five-foot units will be distributed in locations where artifact concentrations suggest the presence of artifact-bearing features. Such features are important because they will provide raw data for the economic and functional analysis, and trash pits and ²⁰⁷abandoned wells and pivies are likely to be helpful for this purpose. All such features will be

FIGURE 3
H. GRANT TENANCY SITE (7NC-B-)



excavated.

Not all significant features will produce noticeable quantities of artifacts, however, so after the excavation of artifact concentrations identified in the controlled surface collection, the plow zone will be stripped off the site with heavy equipment and features such as fence lines and post foundations from outbuildings will be mapped and excavated. This will allow for the characterization of at least those portions of the spatial organization of the farmstead for which evidence remains below the plowzone. In addition to the collection of artifacts, soil samples will be taken and samples collected from feature matrix for laboratory analysis.

Up to 16 crew days have been allocated for this last procedure, but if it becomes clear that further work will be unproductive or redundant, the field work will end. A maximum of forty days has been allocated for the field work described here.

All field work will be coordinated and reviewed weekly with the appropriate officials from DelDOT, FHWA and BAHF offices.

After the completion of the fieldwork, all artifacts will be returned to the laboratory, washed, marked and subjected to any needed conservation measures. To address research questions about economic status and intra-site functional patterning, the artifacts from all proveniences will be subject to a comprehensive analysis procedure which records formal, decorative and functional attributes for all materials (to the degree possible). The analysis procedure will consist of numerically coding the attribute variates for each variable, and entering

these codings into the computer for further statistical manipulation.

Soil samples will be analyzed for chemical composition, and floral and faunal samples analyzed for information on diet. Matrix samples from features will be water-screened for microfloral and micro-faunal data.

The personnel hours for the field work, lab processing, data coding, and analysis hours are based on extensive experience with similar procedures on other projects, as are the report preparation hours.

Costs, shown in the attached budget, are therefore based directly on work activity, and adjustments in the budget can only be made by altering the amount of work produced. Plowing and stripping will be provided by the Delaware Department of Transportation.

